



14421 County Rd. 10 • Ft. Lupton, Colorado 80621 • (303) 857-9999 • FAX (303) 857-0577 • E-MAIL Permitco 1@aol.com

January 9, 2006

Division of Oil, Gas & Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

Re: Gasco Production Company
Federal #12-30-9-19
2084' FNL and 716' FWL
SW NW Section 30, T9S - R19E
Uintah County, Utah
Lease No. U-37246

Gentlemen:

Enclosed please find two copies of the Application for Permit to Drill, along with one copy of the Onshore Order No. 1 which was filed with the BLM in Vernal, Utah.

If you should need additional information, please don't hesitate to contact me. Approved copies of the A.P.D. should be sent to Permitco Inc. at the address shown above.

Sincerely,

PERMITCO INC.

Venessa Langmacher
Consultant for
Gasco Production Company

RECEIVED
JAN 13 2006

Enc.

cc: Gasco Production Company - Englewood, CO
Shawn Elworthy - Roosevelt, UT

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. MINERAL LEASE NO.:	6. SURFACE:
		U-37246	BLM
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME: N/A	
2. NAME OF OPERATOR: Gasco Production Company		9. WELL NAME and NUMBER: Federal #12-30-9-19	
3. ADDRESS OF OPERATOR: 8 Inverness Drive East, Suite 100, Englewood, CO 80112		10. FIELD AND POOL, OR WILDCAT: Riverbend Darlette Birch	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 599939X 40.003471 2084' FNL and 716' FWL AT PROPOSED PRODUCING ZONE: SW NW 4428589Y -109.829187		11. QTR/QTR, SECTION, TOWNSHIP, RANGE MERIDIAN: Sec. 30, T9S-R19E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 24.4 miles Southeast of Myton, UT		12. COUNTY: Uintah	13. STATE: Utah
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 716'	16. NUMBER OF ACRES IN LEASE: 1335.85	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 Acres; SW NW	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET): Approx. 2150'	19. PROPOSED DEPTH: 12,875'	20. BOND DESCRIPTION: Bond #UT-1233	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 4854' GL	22. APPROXIMATE DATE WORK WILL START: ASAP	23. ESTIMATED DURATION: 35 Days	

24. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
17-1/2"	13-3/8", H40, 48#	200'	200 sx Premium Type 5, 15.6 ppg, 1.18 yield
12-1/4"	8-5/8", J-55, 32#	3,453'	575 sx Hi-Lift, 11 ppg, 3.91 yield & 185 sx 10-2 RFC, 14.2 ppg, 1.63 yield
7-7/8"	4-1/2", P110, 13.5#	12,875'	366 sx Hi-Lift, 11.5 ppg, 3.05 yield & 1713 sx 50-50 Poz, 14.1 ppg, 1.28 yield
			CONFIDENTIAL-TIGHT HOLE

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|----------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PROGRAM |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

AGENT: PermitCo Inc.

AGENT'S PHONE NO.: 303-857-9999

NAME (PLEASE PRINT) Venessa Langmacher

TITLE Agent for Gasco Production Company

SIGNATURE *Venessa Langmacher*

DATE January 9, 2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-37613


Approved by the
Utah Division of
Oil, Gas and Mining

Date: 01-17-06
By: *[Signature]*

RECEIVED

JAN 13 2006

DIV. OF OIL, GAS & MINING



LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.


(AUTONOMOUS NAD 83)
 LATITUDE = 40°00'12.42" (40.003450)
 LONGITUDE = 109°49'48.12" (109.830033)
 (AUTONOMOUS NAD 27)
 LATITUDE = 40°00'12.55" (40.003486)
 LONGITUDE = 109°49'45.60" (109.829333)

GASCO PRODUCTION COMPANY

Well location, FEDERAL #12-30-9-19, located as shown in the SW 1/4 NW 1/4 of Section 30, T9S, R19E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE NORTHEAST CORNER OF SECTION 21, T9S, R19E, S.L.B.&M. TAKEN FROM THE UTELAND, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4711 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 07-20-05	DATE DRAWN: 07-22-05
PARTY A.F. T.C. L.K.	REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE GASCO PRODUCTION COMPANY	

ONSHORE OIL & GAS ORDER NO. 1

Approval of Operations on Onshore
Federal and Indian Oil & Gas Leases

FEDERAL #12-30-9-19
2084' FNL and 716' FWL
SW NW Section 30, T9S - R19E
Uintah County, Utah

Prepared For:

Gasco Production Company

By:

PERMITCO INC.
14421 County Road 10
Ft. Lupton, Colorado 80621
303/857-9999

CONFIDENTIAL-TIGHT HOLE

Copies Sent To:

- 3 - Bureau of Land Management - Vernal, UT
- 2 - Utah Division of Oil, Gas & Mining - SLC, UT
- 2 - Gasco Production Company - Englewood, CO
- 1 - Shawn Elworthy - Roosevelt, UT



APPLICATION FOR PERMIT TO DRILL OR REENTER

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
Attached.
2. A Drilling Plan
Attached.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the Appropriate Forest Service Office.
See Surface Use Plan Attached.
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20).
Bond coverage for this well is provided by Gasco Production Company under their BLM Bond No. Bond #UT-1233.
5. Operator certification.
Please be advised that Gasco Production Company is considered to be the operator of the above mentioned well. Gasco Production Company agrees to be responsible under the terms and conditions of the lease for the operations conducted upon the leased lands.
6. Such other site specific information and/or plans as may be required by the authorized officer.

ONSHORE OIL & GAS ORDER NO. 1

Approval of Operations on Onshore
Federal and Indian Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Order No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

1. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS

<i>Formation</i>	<i>Depth</i>	<i>Subsea</i>
Wasatch	5,306'	-440'
Mesaverde	9,125'	-4,259'
Castlegate	11,655'	-6,789'
Blackhawk	11,875'	-7,009'
Spring Canyon	12,575'	-7,709'
T.D.	12,875'	-8,009'

2. ESTIMATED DEPTH OF ANTICIPATED WATER, OIL, GAS OR MINERAL FORMATIONS:

<i>Substance</i>	<i>Formation</i>	<i>Depth</i>
Gas	Wasatch	5,800'-9,125'
Gas	Mesaverde	9,125'-11,655'
Gas	Blackhawk	11,875'-12,800'

All fresh water prospectively valuable minerals encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.



3. PRESSURE CONTROL EQUIPMENT

Gasco Production Company's minimum specifications for pressure control equipment are as follows:

Ram Type: 11" Hydraulic double with annular, 5000 psi w.p.

Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 70 percent of internal yield pressure of casing. Pressure shall be maintained for at least 10 minutes or until requirements of test are met, whichever is longer. If a test plug is utilized, no bleed-off pressure is acceptable. For a test not utilizing a test plug, if a decline in pressure of more than 10 percent in 30 minutes occurs, the test shall be considered to have failed. Valve on casing head below test plug shall be open during test of BOP stack.

Annular type preventers (if used) shall be tested to 50 percent of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.

As a minimum, the above test shall be performed:

- a. when initially installed;
- b. whenever any seal subject to test pressure is broken
- c. following related repairs; and
- d. at 30-day intervals

Valves shall be tested from working pressure side during BOPE tests with all down stream valves open.

When testing the kill line valve(s) the check valve shall be held open or the ball removed.

Annular preventers shall be functionally operated at least weekly.

Pipe and blind rams shall be activated each trip, however, this function need not be performed more than once a day.

A BOPE pit level drill shall be conducted weekly for each drilling crew.

Pressure tests shall apply to all related well control equipment.

All of the above described tests and/or drills shall be recorded in the drilling log.



BOP systems shall be consistent with API RP53. Pressure tests will be conducted before drilling out from under casing strings which have been set and cemented in place. Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily to ensure good mechanical working order, and this inspection will be recorded on the daily drilling report. Preventers will be pressure tested before drilling casing cement plugs.

The District Office should be notified, with sufficient lead time, in order to have the BLM representative on location during pressure testing.

- a. The size and rating of the BOP stack is shown on the attached diagram. Although a rig has not been chosen to drill this well, most of the equipment for this depth of hole in the area use a 11", 5000 psi working pressure blowout preventor.
- b. A choke line and a kill line are to be properly installed. The kill line is not to be used as a fill-up line.
- c. The accumulator system shall have a pressure capacity to provide for repeated operation of hydraulic preventers.
- d. Drill string safety valve(s), to fit all tools in the drill string, are to be maintained on the rig floor while drilling operations are in progress.

4. PROPOSED CASING AND CEMENTING PROGRAM:

- a. The proposed casing and cementing program shall be conducted as approved to protect and/or isolate all usable water zones, potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals. Any isolating medium other than cement shall receive approval prior to use. The casing setting depth shall be calculated to position the casing seat opposite a competent formation which will contain the maximum pressure to which it will be exposed during normal drilling operations. Determination of casing setting depth shall be based on all relevant factors, including; presence/absence of hydrocarbons; fracture gradients; usable water zones; formation pressures; lost circulation zones; other minerals; or other unusual characteristics. All indications of usable water shall be reported.



- b. Casing design shall assume formation pressure gradients of 0.44 to 0.50 psi per foot for exploratory wells (lacking better data).
- c. Casing design shall assume fracture gradients from 0.70 to 1.00 psi per foot for exploratory wells (lacking better data)
- d. Casing collars shall have a minimum clearance of 0.422 inches of all sides in the hole/casing annulus, with recognition that variances can be granted for justified exceptions.
- e. All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.
- f. All casing except the conductor casing, shall be new or reconditioned and tested used casing that meets or exceeds API standards for new casing.
- g. The surface casing shall be cemented back to surface either during the primary cement job or by remedial cementing.
- h. All indications of usable water shall be reported to the authorized officer prior to running the next string of casing or before plugging orders are requested, whichever occurs first.
- i. Three centralizers will be run on the bottom three joints of surface casing with a minimum of one centralizer per joint starting with the shoe joint.
- j. Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc. shall be utilized to help isolate the cement from contamination by the mud fluid being displaced ahead of the cement slurry.
- k. All casing strings below the conductor shall be pressure tested to 0.22 psi per foot of casing string length or 1500 psi, whichever is greater, but not to exceed 70 percent of the minimum internal yield. If pressure declines more than 10 percent in 30 minutes, corrective action shall be taken.
- l. On all exploratory wells, and on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.



Gasco Production Company

Federal #12-30-9-19

Lease No. U-37246

2084' FNL and 716' FWL

SW NW Section 30, T9S - R19E

DRILLING PROGRAM

Uintah County, Utah

Page 5

- m. The proposed casing program will be as follows:

Purpose	Depth	Hole Size	O.D.	Weight	Grade	Type	New/Used
Conductor	0-200'	17-1/2"	13-3/8"	48#	H-40	---	New
Surface	0-3,453'	12-1/4"	8-5/8"	32#	J-55	ST&C	New
Production	0-12,875'	7-7/8"	4-1/2"	13.5#	P-110	LT&C	New

- n. Casing design subject to revision based on geologic conditions encountered.

- o. The cement program will be as follows:

Conductor	Type and Amount
Surface	200 sx Premium Type 5 mixed @ 15.6 ppg, 1.18 yield
Surface	Type and Amount
TOC @ Surface	Lead: 575 sx Hi-Lift @ 11 ppg, 3.91 yield Tail: 185 sx 10-2 RFC @ 14.2 ppg, 1.63 yield
Production	Type and Amount
TOC @ 2,500'	Lead: 366 sx Hi-Lite @ 11.5 ppg, 3.05 yield Tail: 1713 sx 50:50 Poz @ 14.1 ppg, 1.28 yield

- p. Anticipated cement tops will be reported as to depth; not the expected number of sacks of cement to be used. The District Office should be notified, with sufficient lead time, in order to have a BLM representative on location while running all casing strings and cementing.
- q. After cementing but before commencing any test, the casing string shall stand cemented until the cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the driller's log.
- r. The following reports shall be filed with the District Manager within 30 days after the work is completed.



1. Progress reports, Form 3160-5 (formerly 9-331) "Sundry Notices and Reports on Wells", must include complete information concerning:
 - a. Setting of each string of casing, showing the size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.
 - b. Temperature or bond logs must be submitted for each well where the casing cement was not circulated to the surface.
- s. Auxiliary equipment to be used is as follows:
 1. Kelly cock
 2. No bit float is deemed necessary.
 3. A sub with a full opening valve.

5. MUD PROGRAM

- a. The proposed circulating mediums to be employed in drilling are as follows:

<i>Interval</i>	<i>Mud Type</i>	<i>Mud Wt.</i>	<i>Visc.</i>	<i>F/L</i>	<i>PH</i>
1' - 200'	Fresh Water	8.33	1	---	7
200' - 3,453'	Fresh Water	8.33	1	---	7-8
3,453' - 12,875'	Fresh Water/DAP	9.0-11.5	30-40	12-20	8

There will be sufficient mud on location to control a blowout should one occur.

A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, static filtration loss, and Ph.



- b. Mud monitoring equipment to be used is as follows:
 - 1. Periodic checks will be made each tour of the mud system. The mud level will be checked visually.
- c. No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.
- d. No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.
- e. The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

6. **EVALUATION PROGRAM**

The anticipated type and amount of testing, logging and coring are as follows:

- a. No drill stem tests are anticipated, however, if DST's are run, the following requirements will be adhered to:

Initial opening of drill stem test tools shall be restricted to daylight hours unless specific approval to start during other hours is obtained from the authorized officer. However, DST's may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e. lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released, but tripping shall not begin before daylight, unless prior approval is obtained from the authorized officer. Closed chamber DSTs may be accomplished day or night.

A DST that flows to the surface with evidence of hydrocarbons shall be either reversed out of the testing string under controlled surface conditions. This would involve provided some means for reverse circulation.

Separation equipment required for the anticipated recovery shall be properly installed before a test starts.



All engines within 100 feet of the wellbore that are required to "run" during the test shall have spark arresters or water cooled exhausts.

- b. The logging program will consist of a Schlumberger Platform Express (or equivalent) to be run from base of surface casing to TD.
- c. No cores are anticipated.
- d. Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with form 3160-4. Samples (cutting, fluids, and/or gases) will be submitted when requested by the authorized officer (AO).
- e. The anticipated completion program is as follows: Perform multistage fracs and complete all productive Blackhawk, Mesaverde and Wasatch zones present in wellbore. Produce all zones commingled.
- f. Daily drilling and completion progress reports shall be submitted to the BLM in Vernal on a weekly basis.

7. ABNORMAL TEMPERATURES OR PRESSURES

- a. The expected bottom hole pressure is 7725 psi. The maximum bottom hole temperature anticipated is 232 degrees F.
- b. No hydrogen sulfide gas is anticipated. Abnormal pressures will be controlled with mud weight and 5000# BOP and rotating head.

8. ANTICIPATED STARTING DATES AND NOTIFICATION OF OPERATIONS

- a. Drilling is planned to commence on upon approval of this application.



- b. It is anticipated that the drilling of this well will take approximately 35 days.
- c. The BLM in Vernal, Utah shall be notified of the anticipated date of location construction commencement and of anticipated spud date.
- d. No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.
- e. The spud date will be reported orally to the AO within 48 hours after spudding. If the spudding occurs on a weekend or holiday, the report will be submitted on the following regular work day. The oral report will be followed up with a Sundry Notice.
- f. In accordance with Onshore Oil and Gas Order No. 1, this well will be reported on Form 3160-6 "Monthly Report of Operations", starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report will be filed with the Vernal BLM District Office, 170 South 500 East, Vernal, UT 84078.
- g. Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.
- h. If a replacement rig is contemplated for completion operations, a "Sundry Notice" Form 3160-5 to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.
- i. Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communications, not later than 5 days following the date on which the well is placed on production.
- j. Pursuant to Onshore Order No. 7, with the approval of the District Engineer, produced water may be temporarily disposed of into unlined pits for a period of up to 90 days. During the period so authorized, an application for approval of the permanent disposal method, along with the required water analysis and other information, must be submitted to the District Engineer.



Gasco Production Company

Federal #12-30-9-19**Lease No. U-37246**

2084' FNL and 716' FWL

SW NW Section 30, T9S - R19E

DRILLING PROGRAM

Uintah County, Utah


Page 10

- k. Pursuant to NTL-4A, lessees or operators are authorized to vent/flare gas during initial well evaluation tests, not exceeding a period of 30 days or the production of 50 MMCF of gas, whichever occurs first. An application must be filed with the District Engineer and approval received, for any venting/flaring of gas beyond the initial 30 day or authorized test period.
- l. A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9.d.), shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b.4.).
- m. A first production conference will be scheduled within 15 days after receipt of the first production notice.
- n. No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the SO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within 30 days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.
- o. Pursuant to Onshore Oil and Gas Order No. 1, lessees and operators have the responsibility to see that their exploration, development, production, and construction operations are conducted in a manner which conforms with applicable Federal laws and regulations and with State and local laws and regulations to the extent that such State and local laws are applicable to operations on Federal or Indian lands.


Bureau of Land Management 170 South 500 East Vernal, Utah 84078		
Phone: 435/781-4400		Fax: 435/781-4410
After Hours:		
Matt Baker	Petroleum Engineer	435/828-4470
Michael Lee	Petroleum Engineer	435/828-7875



BOP SCHEMATIC
5000 PSI WORKING PRESSURE



PLAN VIEW CHOKER MANIFOLD



THE HYDRAULIC CLOSING UNIT WILL BE LOCATED MORE THAN 30' FROM THE WELLHEAD. CHOKER AND BLEED/PANIC LINES WILL GO TO THE PIT AND FLARE. ALL CONNECTIONS IN CHOKER LINES AND MANIFOLD WILL BE FLANGED OR WELDED. ALL FLANGES SHOULD BE RING JOINT GASKET TYPE. ALL TURNS IN LINES SHALL BE CONSTRUCTED USING TARGETING 90° TEES OR ELLS. ALL LINES SHALL BE ANCHORED.

**ONSHORE OIL & GAS ORDER NO. 1
NOTIFICATION REQUIREMENTS**

Location Construction -	forty-eight (48) hours prior to construction of location and access roads.
Location Completion -	prior to moving on the drilling rig.
Spud Notice -	at least twenty-four (24) hours prior to spudding the well.
Casing String and Cementing -	twenty-four (24) hours prior to running casing and cementing all casing strings.
BOP and Related Equipment Tests -	twenty-four (24) hours prior to initiating pressure tests.
First Production - Notice	within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

The onsite inspection for the subject well site was conducted on August 18, 2005 at approximately 9:45 a.m. Weather conditions were clear, warm and sunny. In attendance at the onsite inspection were the following individuals:

Karl Wright	Natural Resource Specialist	Bureau of Land Management
Amy Torres	Wildlife Biologist	Bureau of Land Management
Lisa Smith	Permitting Agent	Permitco Inc.
Venessa Langmacher	Permitting Agent	Permitco Inc.
Shawn Elworthy	Production Superintendent	Gasco Production Company
John Floyd	Land Surveyor	Uintah Engineering and Land Surveying

1. EXISTING ROADS

- a. The proposed well site is located approximately 24.4 miles southeast of Myton, Utah.



- b. Directions to the location from Myton, Utah are as follows:

Proceed in a southeasterly direction from Myton, Utah for approximately 19.2 miles. Turn right at the Eight Mile Flat area and proceed southeasterly for 4.3 miles until reaching the fork in the road. Stay left and continue easterly 0.2 miles until reaching the second fork in the road. Stay left and continue easterly 0.5 miles. Turn left onto an existing two track road and proceed north for 0.1 miles. Turn left and proceed west 0.1 miles on the new access to the proposed location.

- c. For location of access roads within a 2-Mile radius, see Maps A & B.
- d. Improvement to existing main roads will not be required.
- e. All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.
- f. Existing roads and newly constructed roads on surface under the jurisdiction of any Surface Managing Agency shall be maintained in accordance with the standards of the SMA.

2. PLANNED ACCESS ROADS

- a. Approximately 0.1 miles will be new access road. Approximately 0.1 miles will be 2-track to be upgraded.
- b. The maximum grade of the new construction will be approximately 3%.
- c. No turnouts are planned.
- d. No low water crossings or culverts are anticipated.
- e. The last 0.1 miles of new access road was centerline flagged at the time of staking.
- f. The use of surfacing material is not anticipated, however it may be necessary depending on weather conditions.
- g. No cattle guards will be necessary.



Gasco Production Company

Federal #12-30-9-19**Lease No. U-37246**

2084' FNL and 716' FWL

SW NW Section 30, T9S - R19E

SURFACE USE PLAN

Uintah County, Utah

Page 3

- h. Surface disturbance and vehicular travel will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.
- i. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).
- j. The road will be constructed/upgraded to meet the standards of the anticipated traffic flow and all weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowing and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.
- k. No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.
- l. No road right of way will be necessary.

3. LOCATION OF EXISTING WELLS WITHIN A 1-MILE RADIUS OF THE PROPOSED LOCATION.
(See Map "C")

- a. Water wells - none
- b. Injection wells - none
- c. Producing wells - three
- d. Drilling wells - none
- e. Shut-in wells - one



- f. Temporarily abandoned wells - none
- g. Disposal wells -none
- h. Abandoned wells - three
- i. Dry Holes - none

4. LOCATION OF TANK BATTERIES AND PRODUCTION FACILITIES.

- a. All permanent structures (onsite for six months or longer) constructed or installed (including oil well pump jacks) will be painted Carlsbad Canyon. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.
- b. If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall surrounded by a containment dike of sufficient capacity to contain at a minimum, the entire contents of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.
- c. If the well is productive, the production facilities will be submitted via sundry.
- d. All loading lines will be placed inside the berm surrounding the tank battery.
- e. Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flow line will be buried or anchored down from the wellhead to the separator. Meter runs will be housed and/or fenced.
- f. The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal Field Office. All meter measurement facilities will conform with Onshore Oil and Gas Order No. 4 for liquid hydrocarbons and Onshore Oil and Gas Order No. 5 for natural gas measurement.



- g. If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.
- h. Any necessary pits will be properly fenced to prevent any wildlife entry.
- i. All site security guidelines identified in 43 CFR 3162.7 regulations will be adhered to.
- j. All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the District Manager.
- k. All access roads will be maintained as necessary to prevent erosion and accommodate year-round traffic.
- l. The road will be maintained in a safe useable condition.
- m. Produced water will be stored in a 300 bbl heated, insulated tank, then hauled to a commercial disposal site such as Disposal Inc., or Brennan Bottom.
- n. Pipelines will follow the route shown on Map D. See Pipeline detail attached.

5. LOCATION AND TYPE OF WATER SUPPLY

- a. The proposed water source will be the Nebecker Water Service at the Nebecker Water Station in Myton. The Water Use Claim # is 43-1721.
- b. Water will be hauled by Nebecker Water Service to the location over the access roads shown on Maps A and B.
- c. No water well will be drilled on this lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- a. Surface and subsoil materials in the immediate area will be utilized.



- b. Any gravel used will be obtained from a commercial source.
- c. The use of materials under BLM jurisdiction will conform with 43 CFR 3610.2.3. Construction material will not be located on lease.
- d. No construction materials will be removed from Federal land.

7. METHODS OF HANDLING WASTE DISPOSAL

- a. The reserve pit will be constructed so as not to leak, break, or allow discharge.
- b. At the request of the BLM, the reserve pit will be lined with a 12 mil liner. If fractured rock is encountered, the pit will be first lined with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.
- c. Burning will not be allowed. All trash will be contained in a trash cage and its contents removed at the end of drilling operations and hauled to an approved disposal sight.
- d. After first production, produced waste water will be confined to a unlined pit or storage tank for a period not to exceed ninety (90) days. During the 90-day period, in accordance with Onshore Order No. 7, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.
- e. Drill cuttings are to be contained and buried in the reserve pit.
- f. Any salts and/or chemicals which are an integral part of the drilling system will be disposed of in the same manner as the drilling fluid.
- g. A chemical porta-toilet will be furnished with the drilling rig.
- h. The produced fluids will be produced into a test tank until such time as construction of production facilities is completed. Any spills of oil, gas salt water or other produced fluids will be cleaned up and removed.



8. ANCILLARY FACILITIES

There are no airstrips, camps, or other facilities planned during the drilling of the proposed well.

9. WELL SITE LAYOUT

- a. The operator or his/her contractor shall contact the BLM Office at 435/781-4400 forty-eight (48) hours prior to construction activities.
- b. The reserve pit will be located on the east side of the location.
- c. The flare pit will be located on the southwest side of the reserve pit, a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.
- d. The stockpiled topsoil (first six inches) will be stored on the south side of the location, along with Corners 7, 6 and 5 near the wellpad. Topsoil along the access route will be wind rowed on the uphill side.
- e. Access to the well pad will be from the east as shown on the Pit & Pad Layout.
- f. See Location Layout for orientation of rig, cross section of drill pad and cuts and fills.
- g. The location of mud tanks; reserve pit, trash cage; pipe racks; living facilities and soil stockpiles will be shown on the Location Layout.
- h. All pits will be fenced according to the following minimum standards:
 1. 39 inch net wire shall be used with at least one strand or barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
 2. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.
 3. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.



4. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
5. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.
- i. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE**

Producing Location

- a. Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash and junk not required for production.
- b. Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.
- c. If a plastic nylon reinforced liner is used it shall be torn and perforated before backfilling of the reserve pit.
- d. The reserve pit and that portion of the location not needed for production facilities or operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 120 days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed and all cans, barrels, pipe, etc., will be removed.
- e. Reclamation of unused disturbed areas on the well pad/access road no longer needed for operations, such as cut slopes, and fill areas will be accomplished by grading, leveling and seeding as recommended by the Authorized Officer. A seed mixture will be specified by the Bureau of Land Management in their Conditions of Approval for the subject well.

Seeding will be performed immediately after the location has been reclaimed and the pit has been backfilled, regardless of the time of year. Seed will be broadcast and walked in with a dozer.



- g. The topsoil stockpile will be seeded as soon as the location has been constructed with the same recommended seed mix. The seed will be walked in with a cat.

Dry Hole

- h. At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

Interim Surface Reclamation will be as follows:

1. Immediately after final well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production operations.
2. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in the reserve pit will be removed. Other waste and spoil materials will be disposed of immediately, weather permitting, upon final well completion.
3. If a synthetic, nylon re-enforced, liner is used, the excess liner will be cut off and removed and the remaining liner will be torn and perforated while backfilling the reserve pit. Alternatively, the pit will be pumped dry, the liner folded into the pit, and the pit backfilled. The liner will be buried to a minimum of four (4) feet deep.
4. The reserve pit will be reclaimed within 180 days from the date of final well completion, weather permitting.
5. The reserve pit and that portion of the location not needed for production and storage facilities, and everyday production operations, will be reshaped to the approximate original contours to the extent possible. This will be completed by backfilling and crowning the pit to prevent water from standing. Topsoil will be re-spread up to the rig anchor points, excluding the area needed for production and storage facilities and everyday production operations. Re-seeding, using appropriate reclamation methods, will occur immediately following the re-spreading of topsoil, weather permitting. The Authorized Officer will provide a seed mixture to re-vegetate the reserve pit and other unused disturbed areas at the time of the onsite.



11. SURFACE OWNERSHIP

Access Roads - The majority of the access roads are maintained by the County Road Department or the Bureau of Land Management.

Well pad - The well pad is located on lands managed by the BLM.

12. OTHER INFORMATION

- a. A Class III archeological survey and paleontological survey has been conducted by SWCA. No significant cultural resources were found and clearance is recommended. A copy of this report is on file with the BLM.
- b. The operator is responsible for informing all persons in the areas who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to:
 - whether the materials appear eligible for the National Register of Historic Places;
 - the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
 - a time frame for the AO to complete and expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate. If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.



Gasco Production Company

Federal #12-30-9-19**Lease No. U-37246**

2084' FNL and 716' FWL

SW NW Section 30, T9S - R19E

Uintah County, Utah

SURFACE USE PLAN

Page 11

- c. The operator will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- d. Drilling rigs and/or equipment used during drilling operations on this wellsite will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure.
- e. All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.
- f. A complete copy of the approved APD shall be on location during construction of the location and drilling activities.
- g. There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended or abandoned will be identified in accordance with 43 CFR 3162.
- h. "Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.
- i. This permit will be valid for a period of one year from the date of approval. An extension period may be granted, if requested, prior to the expiration of the original approval period. After permit termination, a new application will be filed for approval for any future operations.
- j. The operator or his contractor shall contact the BLM Offices at 435/781-4400 48 hours prior to construction activities.
- k. The BLM Office shall be notified upon site completion prior to moving on the drilling rig.



ONSHORE ORDER NO. 1
Gasco Production Company
Federal #12-30-9-19
2084' FNL and 716' FWL
SW NW Section 30, T9S - R19E
Uintah County, Utah

CONFIDENTIAL - TIGHT HOLE

Lease No. U-37246

SURFACE USE PLAN

Page 12

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

Permit Matters

PERMITCO INC.
14421 County Road 10
Ft. Lupton, CO 80621
303/857-9999 (O)
303/857-0577 (F)
Lisa Smith

Drilling & Completion Matters

Gasco Production Company
8 Inverness Drive East, Suite 100
Englewood, CO 80112
John Longwell
303/483-0044 (O)
303/ 483-0011(F)

Shawn Elworthy - Field Superintendent
Roosevelt, UT
435-823-4272 (cell)

CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Gasco Production Company and its contractors and subcontractors in conformity with the plan and the terms and conditions under which it is approved.

This statement is subject to the provisions of 18.U.S.C. 1001 for the filing of a false statement.

September 9, 2005
Date:

Venessa Langmacher
Venessa Langmacher - PERMITCO INC.
Authorized Agent for:
Gasco Production Company



PIPELINE INFORMATION

Federal #12-30-9-19

1. The type of pipeline is a single well flow line.
2. The outside diameter (O.D.) of all will be 8 inches maximum.
3. The anticipated production through the line is approximately 2000 MCF per day.
4. The anticipated maximum test pressure is 1000 psi.
5. The anticipated operating pressure is 100-200 psi.
6. The type of pipe is steel.
7. The method of coupling is welded.
8. The pipeline will be buried 2-5 feet deep.
9. The method of entrenchment will be with a trenching machine.
10. The depth of cover will be 2-5 feet.
11. There are no other pipelines to be associated in same right of way.
12. There will be other objects to be associated in the same right of way. (Risers, Pig Launchers Pig Traps, meters and other appurtenances as required.)
13. The total length of pipeline is approximately 623' feet - see Map D.
14. The line will be buried as shown on Map D. Where possible, the pipeline will follow existing or proposed roads.
15. The construction width for total surface disturbing activities is 30 feet.
16. The estimated total acreage involving all surface disturbing activities is 0.43 acres
17. Any surface disturbance created as a result of the pipeline construction will be reclaimed utilizing the reclamation procedures and seed mixture specified by the Bureau of Land Management.
18. The line will be tested with gas pressure to 1000 psi.

GASCO PRODUCTION COMPANY

FEDERAL #12-30-9-19

LOCATED IN UINTAH COUNTY, UTAH

SECTION 30, T9S, R19E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHWESTERLY



UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


07 27 05
MONTH DAY YEAR

PHOTO

TAKEN BY: A.F.

DRAWN BY: L.K.

REVISED: 00-00-00



LEGEND:

○ PROPOSED LOCATION

N

GASCO PRODUCTION COMPANY

FEDERAL #12-30-9-19

SECTION 30, T9S, R19E, S.L.B.&M.

2084' FNL 716' FWL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
 MAP

07 27 05
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: L.K. REVISED: 00-00-00





LEGEND:

- | | |
|-------------------|-------------------------|
| ⊗ DISPOSAL WELLS | ⊗ WATER WELLS |
| ● PRODUCING WELLS | ⊖ ABANDONED WELLS |
| ⊖ SHUT IN WELLS | ⊖ TEMPORARILY ABANDONED |

GASCO PRODUCTION COMPANY

FEDERAL #12-30-9-19
SECTION 30, T9S, R19E, S.L.B.&M.
2084' FNL 716' FWL

U E I S
Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC 07 27 05
MAP MONTH DAY YEAR
 SCALE: 1" = 2000' DRAWN BY: L.K. REVISED: 00-00-00


C
TOPO

D
TOPO

ASCO PRODUCTION COMPANY

LOCATION LAYOUT FOR

FEDERAL #12-30-9-19
 SECTION 30, T9S, R19E, S.L.B.&M.
 2084' FNL 716' FWL








GASCO PRODUCTION COMPANY

TYPICAL CROSS SECTIONS FOR

FEDERAL #12-30-9-19
SECTION 30, T9S, R19E, S.L.B.&M.
2084' FNL 716' FWL

1" = 20'
X-Section
Scale
1" = 50'
DATE: 07-22-05
Drawn By: L.K.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

CUT

(6") Topsoil Stripping = 2,020 Cu. Yds.

Remaining Location = 13,420 Cu. Yds.

TOTAL CUT = 15,440 CU.YDS.

FILL = 7,910 CU.YDS.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

EXCESS MATERIAL = 7,530 Cu. Yds.

Topsoil & Pit Backfill (1/2 Pit Vol.) = 3,650 Cu. Yds.

EXCESS UNBALANCE (After Rehabilitation) = 3,880 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (801) 789-1017

FEDERAL STIPULATIONS

There are no federal stipulations at this time.




ARCHEOLOGY

A Class III Archeological Survey has been conducted by SWCA. No significant cultural resources found and clearance has been recommended. A copy of this report is on file with the Bureau of Land Management.



GASCO
Energy Inc



Bureau of Land Management
Vernal Field Office
170 S. 500 E.
Vernal, UT 84078

Attn: Minerals

Re: All Wells
Uintah County, Utah

Gentlemen:

This letter is to inform you that Permitco Inc. is authorized to act as Agent and to sign documents on behalf of (Company Name) when necessary for filing county, state and federal permits including Onshore Order No. 1, Right of Way applications, etc., for the above mentioned well.

It should be understood that Permitco is acting as Agent only in those matters stated above and is not responsible for drilling, completion, production or compliance with regulations.

Gasco Energy, Inc. / Pannanien Energy (Company Name) agrees to accept full responsibility for operations conducted in order to drill, complete and produce the above-mentioned well.

Sincerely,


John D. Longwell
Operations Manager

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 01/13/2006

API NO. ASSIGNED: 43-047-37613

WELL NAME: FEDERAL 12-30-9-19

OPERATOR: GASCO PRODUCTION (N2575)

CONTACT: VENESSA LANGMACHER

PHONE NUMBER: 303-857-9999

PROPOSED LOCATION:

SNWN 30 090S 190E

SURFACE: 2084 FNL 0716 FWL

BOTTOM: 2084 FNL 0716 FWL

COUNTY: UINTAH

LATITUDE: 40.00347 LONGITUDE: -109.8292

UTM SURF EASTINGS: 599939 NORTHINGS: 4428589

FIELD NAME: PARIETTE BENCH (640)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: U-37246

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: BLKHK

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. UT-1233)

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit

(No. 43-1721)

☒ RDCC Review (Y/N)

(Date: _____)

☒ Fee Surf Agreement (Y/N)

☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

☐ R649-2-3.

Unit: _____

☒ R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

☐ R649-3-3. Exception

☐ Drilling Unit

Board Cause No: _____

Eff Date: _____

Siting: _____

☐ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: _____

1. Federal Approved
2. Spacing Stip



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

January 17, 2006

Gasco Production Company
8 Inverness Drive East, Suite 100
Englewood, CO 80112

Re: Federal 12-30-9-19 Well, 2084' FNL, 716' FWL, SW NW, Sec. 30, T. 9 South,
R. 19 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-37613.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Gasco Production Company
Well Name & Number Federal 12-30-9-19
API Number: 43-047-37613
Lease: U-37246

Location: SW NW Sec. 30 T. 9 South R. 19 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-37246
CONFIDENTIAL		7. Indian Allottee or Tribe Name N/A
		8. Unit or Communitization Agreement N/A
		9. Well Name and Number Federal #12-30-9-19
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		10. API Well Number 43-047-37613
2. Name of Operator Gasco Production Company		11. Field and Pool, or Wildcat Pariette Bench
3. Address of Operator 8 Inverness Drive East, Suite #100, Englewood, CO 80112	4. Telephone Number 303/483-0044	
5. Location of Well Footage : 2084' FNL and 716' FWL County : Uintah QQ, Sec. T., R., M. : SW NW, Sec. 30, T9S - R19E State : Utah		
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		

<p style="text-align: center;">NOTICE OF INTENT (Submit in Duplicate)</p> <div style="display: flex; justify-content: space-between;"> <div style="width: 48%;"> <input type="checkbox"/> Abandonment <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Multiple Completion <input checked="" type="checkbox"/> Other Request 1 year extension of APD </div> <div style="width: 48%;"> <input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recompletion <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off </div> </div> <p>Approximate Date Work Will Start _____</p>	<p style="text-align: center;">SUBSEQUENT REPORT (Submit Original Form Only)</p> <div style="display: flex; justify-content: space-between;"> <div style="width: 48%;"> <input type="checkbox"/> Abandonment * <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Other _____ </div> <div style="width: 48%;"> <input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off </div> </div> <p>Date of Work Completion _____</p> <p><small>Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form. * Must be accompanied by a cement verification report.</small></p>
----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Gasco Production Company requests a one year extension of the subject APD.

Approved by the
Utah Division of
Oil, Gas and Mining
 Date: **08-22-06**
 By: *[Signature]*

14. I hereby certify that the foregoing is true and correct.

Name & Signature *Veronica Gangmacker* Title Gasco Production Company Date 08/17/06

(State Use Only)

COPY SENT TO OPERATOR
 Date: **9/21/06**
 Initials: **DM**

AUG 21 2006

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-37613

Well Name: Federal #12-30-9-19

Location: SW NW, 2084' FNL and 716' FWL, Sec. 30, T9S - R19E

Company Permit Issued to: Gasco Production Company

Date Original Permit Issued: 1/17/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If location on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which would require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐



Vanessa Langmacher - Permitco Inc.

August 17, 2006

Date

Title: Consultant for Gasco Production Company

AUG 21 2006

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SEP 12 2005

FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. U-37246
b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name N/A
2. Name of Operator Gasco Production Company		7. If Unit or CA Agreement, Name and No. N/A
3. Name of Agent Permitco Inc. - Agent		8. Lease Name and Well No. Federal #12-30-9-19
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 2084' FNL and 716' FWL At proposed prod. zone SW NW		9. API Well No. 43-047-37613
14. Distance in miles and direction from nearest town or post office* Approximately 24.4 miles Southeast of Myton, UT		10. Field and Pool, or Exploratory Riverbend
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 716'	16. No. of Acres in lease 1335.85	11. Sec., T., R., M., or Blk. and Survey or Area Section 30, T9S-R19E
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 2150'	19. Proposed Depth 12,875'	12. County or Parish Uintah
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4854' GL	22. Approximate date work will start* ASAP	13. State UT
23. Estimated duration 35 Days		

24. Attachments

CONFIDENTIAL-TIGHT HOLE

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest, State Land, or BLM land, SUPO shall be filed with the appropriate Forest Service Office.)
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized office.

25. Signature <i>Venessa Langmacher</i>	Name (Printed/Typed) Venessa Langmacher	Date 9/9/2005
Title Authorized Agent for Gasco Production Company		
Approved by (Signature) <i>Jerry Kewerka</i>	Name (Printed/Typed) JERRY KEWERKA	Date 1-16-2007
Title Assistant Field Manager		
Office VERNAL FIELD OFFICE		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

RECEIVED

IAN 30 2007

DIV. OF OIL, GAS & MINING

NOTICE OF APPROVAL CONDITIONS OF APPROVAL ATTACHED

06 4150385 A

UDOGM




UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Gasco Production Company

Well No: Federal 12-30-9-19

API No: 43-013-37613

047

Location: SWNW, Sec. 30, T9S, R19E

Lease No: UTU-37246

Agreement: N/A

Petroleum Engineer:

Matt Baker

Office: 435-781-4490

Cell: 435-828-4470

Petroleum Engineer:

Michael Lee

Office: 435-781-4432

Cell: 435-828-7875

Petroleum Engineer:

Jim Ashley

Office: 435-781-4470

Cell: 435-828-7874

Supervisory Petroleum Technician:

Jamie Sparger

Office: 435-781-4502

Cell: 435-828-3913

Environmental Scientist:

Paul Buhler

Office: 435-781-4475

Cell: 435-828-4029

Environmental Scientist:

Karl Wright

Office: 435-781-4484

Natural Resource Specialist:

Holly Villa

Office: 435-781-4404

Natural Resource Specialist:

Melissa Hawk

Office: 435-781-4476

Natural Resource Specialist:

Darren Williams

Office: 435-781-4447

After Hours Contact Number: 435-781-4513

Fax: 435-781-4410

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a one-year period. An additional year extension may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

- Location Construction (Notify Karl Wright) - Forty-Eight (48) hours prior to construction of location and access roads.
- Location Completion (Notify Karl Wright) - Prior to moving on the drilling rig.
- Spud Notice (Notify Petroleum Engineer) - Twenty-Four (24) hours prior to spudding the well.
- Casing String & Cementing (Notify Jamie Sparger) - Twenty-Four (24) hours prior to running casing and cementing all casing strings.
- BOP & Related Equipment Tests (Notify Jamie Sparger) - Twenty-Four (24) hours prior to initiating pressure tests.
- First Production Notice (Notify Petroleum Engineer) - Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

GENERAL SURFACE CONDITIONS OF APPROVAL

1. Operator shall notify any active gilsonite mining operation within 2 miles of the location 48 hours prior to any blasting during construction for this well.
2. Construction for this site will be impacting a known paleontological site (PCM10Aug05-2). As a result, paleontological monitoring will be required by a BLM permitted paleontologist throughout the construction phase of the pipeline, access road and well pad for this location.
3. Due to the presence of bedrock on this site the operator shall install the pipeline on the surface rather than follow the buried pipeline proposal discussed within the APD.
4. Within 90 calendar days of the approval date for this Application for Permit to Drill (APD), the operator/lessee shall submit to the Authorized Officer (AO), on Sundry Notice Form 3160-5, an Interim Surface Reclamation Plan for surface disturbance on well pads, access roads, and pipelines. At a minimum, this will include the reshaping of the pad to the original contour to the extent possible; the respreading of the top soil up to the rig anchor points; and, the area reseeded using appropriate reclamation methods. The AO will provide written approval or concurrence within 30 calendar days of receipt. The following seed mix shall be used:

Type		lbs./acre
Western Wheatgrass	<i>Agropyron smithii</i>	4
Needle and Threadgrass	<i>Stipa comata</i>	4
Hy-crest Crested wheatgrass	<i>Agropyron cristatum</i>	4
** Seed should be drilled; but if broadcasted double the pounds per acre used and work the solids mechanically to cover the seed.		

5. Following well plugging and abandonment, the location, access roads, pipelines, and other facilities shall be reclaimed. All disturbed surfaces shall be reshaped to approximate the original contour; the top soil respread over the surface; and, the surface revegetated. The following seed mix shall be used, unless BLM personnel determine that conditions have changed and another mix would be more suitable:

Type		lbs./acre
Shadscale	<i>Atriplex confertifolia</i>	3
Winterfat	<i>Eurotia lanata</i>	3
Galleta grass	<i>Hilaria jamesil</i>	3
Indian Rice Grass	<i>Oryzopsis hymenoides</i>	3
** Seed should be drilled; but if broadcasted double the pounds per acre used and work the solids mechanically to cover the seed.		

DOWNHOLE CONDITIONS OF APPROVAL

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

SITE SPECIFIC DOWNHOLE CONDITIONS OF APPROVAL

1. None

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

1. There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well. Any changes in operation must have prior approval from the BLM, Vernal Field Office Petroleum Engineers.
2. The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
3. **Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.**
4. Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.

All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.

BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.

Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.

No aggressive/fresh hard-banded drill pipe shall be used within casing.

Cement baskets shall not be run on surface casing.

The lessee/operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled and analyzed (a copy of the analyses to be submitted to the BLM Field Office in Vernal, Utah).

All oil and gas shows shall be adequately tested for commercial possibilities, reported, and protected.

The lessee/operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, etc.) to Peter Sokolosky or another geologist of the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

5. All shows of fresh water and minerals shall be reported and protected. A sample shall be taken of any water flows and a water analysis furnished the BLM, Vernal Field Office. All oil and gas shows shall be adequately tested for commercial possibilities, reported, and protected.
6. No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM, Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM, Vernal Field Office shall be obtained and notification given before resumption of operations.
7. Chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.

Any change in the program shall be approved by the BLM, Vernal Field Office. "Sundry Notices and Reports on Wells" (Form BLM 3160-5) shall be filed for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Emergency approval may be obtained orally, but such approval does not waive the written report requirement. Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan pursuant to Onshore Oil & Gas Order No. 1 of 43 CFR 3164.1 and prior approval by the BLM, Vernal Field Office.

In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.

8. Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

A cement bond log (CBL) will be run from the production casing shoe to the surface casing shoe and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.

9. All off-lease storage, off-lease measurement, or commingling on-lease or off-lease shall have prior written approval from the BLM, Vernal Field Office.

All measurement points shall be identified as point of sales or allocation for royalty determination prior to the installation of facilities.

10. Oil and gas meters shall be calibrated in place prior to any deliveries. The Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM, Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement.
11. A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM, Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
12. This APD is approved subject to the requirement that, should the well be successfully completed for production, the BLM, Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - a. Operator name, address, and telephone number.
 - b. Well name and number.
 - c. Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - d. Date well was placed in a producing status (date of first production for which royalty will be paid).
 - e. The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).

- f. The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - g. Unit agreement and / or participating area name and number, if applicable.
 - h. Communitization agreement number, if applicable.
- 13. Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from Field Office Petroleum Engineers.
- 14. All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production
- 15. Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- 16. Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: Gasco Production CompanyWell Name: Federal 12-30-9-19API No: 43-047-37613 Lease Type: FederalSection 26 Township 09S Range 22E County Uintah

Drilling Contractor _____ Rig # _____

SPUDDED:Date 4-18-07

Time _____

How Dry**Drilling will Commence:** _____Reported by Jeff DuncanTelephone # 281-833-2368Date 4-20-07 Signed RM

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Gasco Production Co Operator Account Number: N 2575
Address: 8 Inverness Drive East, Ste 100
city Englewood
state Co zip 80112 Phone Number: (303) 483-0044

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304737613	Federal 12-30-9-19		SWNW	30	9S	19E	Uintah
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	16052	4/18/2007		4/23/07		
Comments: Spud Well <u>BLKHK = MVRD</u> <div align="right" style="font-size: 2em; font-weight: bold;">CONFIDENTIAL</div>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Beverly Walker

Name (Please Print)

Signature

Engineering Tech

4/19/2007

Date


RECEIVED

APR 19 2007


DIV. OF OIL, GAS & MINING

[illegible]

[illegible]



~~DIV. OF OIL, GAS & MINING~~




GASCO ENERGY DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL
T09S R19E S-30
43-047-37613

Well: Federal 12-30-9-19			Permit Depth: 12875			Prog. Depth:			Date: 5/10/2007			Days Since Spud: RU6		
Current Operations:						Rig Up								
Depth: 218'		Prog:		D Hrs:		AV ROP:		#DIV/0!		Formation:				
DMC:				TMC:				TDC: \$28,930		CWC: \$318,730				
Contractor: Nabors 270				Mud Co: M-I DRLG FLUIDS				TANGIBLE COST			INTANGIBLE COST			
MW:		#1 PZ-10	Bit #:	1		Conductor: \$ -			Loc, Cost: \$ -					
VIS:		SPM:	Size:	12 1/4		Surf. Csg: \$ -			Rig Move: \$ -					
PV/YP:		#2 PZ-10	Type:	HP51a		Int. Csg: \$ -			Day Rate: \$ 20,000					
Gel:		SPM:	MFG:	Hycalog		Prod Csg: \$ -			Rental Tools: \$ 800					
WL:		GPM :	S/N:	JT9607		Float Equip: \$ -			Trucking: \$ 880					
Cake:		Press:	Jets:	3/22		Well Head: \$ -			Water: \$ -					
Solids:		AV DC:	TD Out:			TBG/Rods: \$ -			Fuel: \$ -					
MBT:		AV DP:	Depth In:	218		Packers: \$ -			Mud Logger: \$ -					
PH :		JetVel:	FTG:			Tanks: \$ -			Logging: \$ -					
Pf/Mf:		ECD:	Hrs:			Separator: \$ -			Cement: \$ -					
Chlor:		SPR #1 :	FPH:	#DIV/0!		Heater: \$ -			Bits: \$ -					
Ca :		SPR #2 :	WOB:			Pumping L/T: \$ -			Mud Motors: \$ -					
Dapp ppb:		Btm.Up:	R-RPM:			Prime Mover: \$ -			Corrosion: \$ -					
Time Break Down:			Total D.T.		M-RPM:		Misc: \$ -		Consultant: \$ 1,000					
START	END	TIME			Total Rot. Hrs:		Daily Total: \$ -		Drilling Mud: \$ -					
06:00			Raise top drive, pin blocks to top drive, install rams & slides for						Misc. / Labor: \$ 6,250					
			top drive , rig electric to top drive, had to remove kick pads remodify						Csg. Crew: \$ -					
			to get top drive over hole, set bop under sub behind conductor, Run						Daily Total: \$ 28,930					
	18:00	12:00	power across to camps						Cum. Wtr: \$ 5,200					
18:00	01:00	7:00	Work on top drive modifications						Cum. Fuel \$ 49,700					
01:00	05:00	4:00	Set skate to rig floor , Rigup rotating head on conductor						Cum. Bits: \$ -					
05:00	06:00	1:00	Rig up Floor						BHA					
									Bits:					
			Rig up @ 95% complete						Shock Sub					
			Called Randy Bywater - BLM prior to spudding on 5/8/07 ,no answer left						Tel drift					
			message - twice						1-8" DC					
									IBS					
			RECEIVED						1-8" DC					
			MAY 10 2007						IBS					
									1 - 8" DC					
			DIV. OF OIL, GAS & MINING						TOTAL BHA = 0.00					
									Survey					
									Survey					
P/U		K#	LITH:		BKG GAS									
S/O		K#	FLARE:		GAS BUSTER									
ROT.		K#	LAST CSG. RAN: 13 3/8		SET @ 218'		PEAK GAS							
FUEL		Used: 4549	On Hand: 17151		Co. Man Rick Felker		TRIP GAS							
BIT # 1 CONDITION		ICS	OCS	DC	LOC	B/S	G	ODC						



GASCO ENERGY DAILY DRILLING REPORT

AFE # 40129


GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL

T09S R119E S-30

43-044-34613

Well: Federal 12-30-9-19			Permit Depth: 12875			Prog. Depth:			Date: 5/11/2007			Days Since Spud: RU7						
Current Operations:						Work on Top Drive												
Depth: 218'			Prog:			D Hrs:			AV ROP:			#DIV/0!			Formation: Surface			
DMC:						TMC:						TDC: \$26,600			CWC: \$345,330			
Contractor: Nabors 270						Mud Co: M-I DRLG FLUIDS						TANGIBLE COST			INTANGIBLE COST			
MW:			#1 PZ-10			Bit #: 1			Conductor: \$ -			Loc, Cost: \$ -						
VIS:			SPM:			Size: 12 1/4			Surf. Csg: \$ -			Rig Move: \$ -						
PV/YP:			#2 PZ-10			Type: HP51a			Int. Csg: \$ -			Day Rate: \$ 20,000						
Gel:			SPM:			MFG: Hycalog			Prod Csg: \$ -			Rental Tools: \$ 1,000						
WL:			GPM :			S/N: JT9607			Float Equip: \$ 3,100			Trucking: \$ -						
Cake:			Press:			Jets: 3/22			Well Head: \$ -			Water: \$ -						
Solids:			AV DC:			TD Out:			TBG/Rods: \$ -			Fuel: \$ -						
MBT:			AV DP:			Depth In: 218			Packers: \$ -			Mud Logger: \$ -						
PH :			JetVel:			FTG:			Tanks: \$ -			Logging: \$ -						
Pf/Mf:			ECD:			Hrs:			Separator: \$ -			Cement: \$ -						
Chlor:			SPR #1 :			FPH: #DIV/0!			Heater: \$ -			Bits: \$ -						
Ca :			SPR #2 :			WOB:			Pumping L/T: \$ -			Mud Motors: \$ -						
Dapp ppb:			Btm.Up:			R-RPM:			Prime Mover: \$ -			Corrosion: \$ -						
Time Break Down:						Total D.T.			M-RPM:			Misc: \$ -			Consultant: \$ 1,000			
START			END			TIME			Total Rot. Hrs:			Daily Total: \$ 3,100			Drilling Mud: \$ -			
06:00			18:00			12:00			Rig up flowline to conductor, intall pop off lines , fill pits with water .						Misc. / Labor: \$ 1,500			
									install kelly hose to top drive, readjust skate to rig						Csg. Crew: \$ -			
18:00			23:00			5:00			Finish install skate, set front stairs, hook water lines to rig						Daily Total: \$ 23,500			
23:00			01:00			2:00			Strap all BHA, work on electrical system						Cum. Wtr: \$ 5,200			
01:00			02:00			1:00			Pick up stabilizers , shock , bit to rig floor						Cum. Fuel \$ 49,700			
02:00			03:00			1:00			Work on drawworks -electrical						Cum. Bits: \$ -			
03:00			05:00			2:00			Pick up BHA and go in hole .Bit shock ,lbs, 8" Drill Collars						BHA			
05:00			06:00			1:00			Work on Top Drive ,swap cameras around in derrick						Bits/Bit Sub		4.06	
															Ssub/Tele		21.58	
									A lot of intermitent electric problem with system ,tested system thru						1-8" DC		29.78	
									out rig up ,seems to be ok, until we start running system.						IBS		6.30	
									lost average of 4 hrs aday on academy system on rig up						1-8" DC		28.9	
															IBS		6.73	
									RECEIVED						1 - 8" DC		30.32	
									MAY 11 2007						21 -6.5 DC		0.00	
															TOTAL BHA = 127.67			
									DIV. OF OIL, GAS & MINING						Survey			
															Survey			
P/U			K#			LITH:			BKG GAS									
S/O			K#			FLARE:			GAS BUSTER						CONN GAS			
ROT.			K#			LAST CSG. RAN: 13 3/8			SET @ 218'			PEAK GAS						
FUEL Used: 492			On Hand: 16659			Co. Man Rick Felker			TRIP GAS									
BIT # 1 CONDITION			ICS		OCS		DC		LOC		B/S		G		ODC		RP	



GASCO ENERGY DAILY DRILLING REPORT

AFE # 40129


GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL

T095 R19E S-30

43-047-37613

Well: Federal 12-30-9-19			Permit Depth: 12875			Prog. Depth: 12875			Date: 5/12/2007			Days Since Spud: 1			
Current Operations:						Drig									
Depth: 1389'		Prog: 589		D Hrs: 6 1/2		AV ROP: 90.6		Formation:		Surface					
DMC: \$0			TMC: \$0			TDC: \$51,460			CWC: \$396,790						
Contractor: Nabors 270				Mud Co: M-I DRLG FLUIDS				TANGIBLE COST				INTANGIBLE COST			
MW:	W	#1 PZ-10		Bit #:	1		Conductor:	\$ -		Loc. Cost:		\$ -			
VIS:	a	SPM: 90		Size:	12 1/4		Surf. Csg:	\$ -		Rig Move:		\$ -			
PV/YP:	t	#2 PZ-10		Type:	HP51a		Int. Csg:	\$ -		Day Rate:		\$ 23,000			
Gel:	e	SPM: 90		MFG:	Hycalog		Prod Csg:	\$ -		Rental Tools:		\$ 1,870			
WL:	r	GPM: 600		S/N:	JT9607		Float Equip:	\$ 3,100		Trucking:		\$ 890			
Cake:		Press: 750		Jets:	3/22		Well Head:	\$ -		Water:		\$ -			
Solids:		AV DC:		TD Out:			TBG/Rods:	\$ -		Fuel:		\$ -			
MBT:		AV DP:		Depth In:	800		Packers:	\$ -		Mud Logger:		\$ -			
PH :		JetVel:		FTG:	589		Tanks:	\$ -		Logging:		\$ -			
Pf/Mf:		ECD:		Hrs:	6.5		Separator:	\$ -		Cement:		\$ -			
Chlor:		SPR #1 :		FPH:	90.6		Heater:	\$ -		Bits:		\$ 15,450			
Ca :		SPR #2 :		WOB:	40		Pumping L/T:	\$ -		Mud Motors:		\$ -			
Dapp ppb:		Btm.Up:		R-RPM:	125		Prime Mover:	\$ -		Corrosion:		\$ -			
Time Break Down:				Total D.T.		M-RPM:				Misc:		\$ -			
START	END	TIME			Total Rot. Hrs:				Daily Total:		\$ 3,100		Consultant: \$ 1,000		
06:00	08:00	2:00	Work on Top Drive								Drilling Mud: \$ -		Misc. / Labor: \$ 6,150		
08:00	08:30	0:30	Pick up 6 1/2 collars								Csg. Crew: \$ -				
08:30	10:00	1:30	Work on top drive ,repair stand pipe, and goose neck								Daily Total: \$ 48,360				
10:00	22:30	12:30	Ream from 160 - 800								Cum. Wtr: \$ 5,200				
22:30	23:00	0:30	Install Rotating Head								Cum. Fuel \$ 49,700				
23:00	02:00	3:00	Drig f/800 - 1166 366' @122fph								Cum. Bits: \$ 15,450				
02:00	02:30	0:30	Rig Service								BHA				
02:30	06:00	3:30	Drig f/1166 - 1389 223' @63.7fph								Bits/Bit Sub		4.06		
											Ssub/Tele		21.58		
											1-8" DC		29.78		
											IBS		6.30		
											1-8" DC		28.9		
											IBS		6.73		
											1 - 8" DC		30.32		
											21 -6.5 DC		657.34		
			RECEIVED								TOTAL BHA =		785.01		
			MAY 14 2007								Survey		1/2 1070'		
			DIV. OF OIL, GAS & MINING								Survey				
P/U 108 K# LITH:														BKG GAS	
S/O 103 K# FLARE:														CONN GAS	
ROT. 105 K# LAST CSG. RAN: 13 3/8 SET @ 218'														PEAK GAS	
FUEL Used: 907 On Hand: 15757 Co. Man Rick Felker														TRIP GAS	
BIT # 1 CONDITION		ICS	OCS	DC	LOC	B/S	G	ODC	RP						



GASCO ENERGY DAILY DRILLING REPORT

AFE # 40129


GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL

T01SR19E S30

43-047-37613

Well: Federal 12-30-9-19		Permit Depth: 12875		Prog. Depth: 12875		Date: 5/14/2007		Days Since Spud: 3	
Current Operations:				Drlg					
Depth: 3464'		Prog: 549		D Hrs: 22		AV ROP: 25.0		Formation: Surface	
DMC: \$895		TMC: \$1,874		TDC: \$120,235		CWC: \$541,714			
Contractor: Nabors 99				Mud Co: M-I DRLG FLUIDS		TANGIBLE COST		INTANGIBLE COST	
MW:	8.6	#1 PZ-10	3.48gal/stk	Bit #:	1	Conductor: \$ 6,540		Loc. Cost: \$ -	
VIS:	28	SPM:	95	Size:	12 1/4	Surf. Csg: \$ 87,000		Rig Move: \$ -	
PV/YP:	1	#2 PZ-10	3.48gal/stk	Type:	HP51a	Int. Csg: \$ -		Day Rate: \$ 23,000	
Gel:	1/1/1	SPM:	95	MFG:	Hycalog	Prod Csg: \$ -		Rental Tools: \$ 1,800	
WL:	nc	GPM:	663	S/N:	JT9607	Float Equip: \$ -		Trucking: \$ -	
Cake:		Press:	863	Jets:	3/22	Well Head: \$ -		Water: \$ -	
Solids:		AV DC:	175	TD Out:	3480	TBG/Rods: \$ -		Fuel: \$ -	
MBT:		AV DP:	112	Depth In:	800	Packers: \$ -		Mud Logger: \$ -	
PH:	8.0	JetVel:	191	FTG:	2664	Tanks: \$ -		Logging: \$ -	
Pf/Mf:	.2/3.4	ECD:	8.41	Hrs:	52	Separator: \$ -		Cement: \$ -	
Chlor:	6000	SPR #1:		FPH:	51.2	Heater: \$ -		Bits: \$ -	
Ca:	20	SPR #2:		WOB:	50	Pumping L/T: \$ -		Mud Motors: \$ -	
Dapp ppb:	2.5	Btm.Up:	27	R-RPM:	125/130	Prime Mover: \$ -		Corrosion: \$ -	
Time Break Down:			Total D.T.	M-RPM:		Misc: \$ -		Consultant: \$ 1,000	
START	END	TIME	1	Total Rot. Hrs: 52.0		Daily Total: \$ 93,540		Drilling Mud: \$ 895	
06:00	07:30	1:30	DRLG f/2914 - 2977 63' @42fph				Misc. / Labor: \$ -		
07:30	08:00	0:30	Re weld conductor - weld cracked				Csg. Crew: \$ -		
08:00	13:00	5:00	DRLG F/ 2977 - 3168 191' @38.2FPH				Daily Total: \$ 26,695		
13:00	13:30	:30	RIG SERVICE				Cum. Wtr: \$ 5,200		
13:30	18:00	4:30	DRLG F/3168 - 3295 127' @28.2FPH				Cum. Fuel \$ 49,700		
18:00	19:00	1:00	Work on top drive - lube pump				Cum. Bits: \$ 15,450		
19:00	06:00	11:00	DRLG F/ 3295 - 3464 169' @15.3FPH				BHA		
							Bits/Bit Sub		4.06
							Ssub/Tele		21.58
							1-8" DC		29.78
							IBS		6.30
							1-8" DC		28.9
							IBS		6.73
							1 - 8" DC		30.32
							21 -6.5 DC		657.34
							TOTAL BHA = 785.01		
							Survey	1/2	3000'
							Survey		
P/U	153	K#	LITH:				BKG GAS		
S/O	150	K#	FLARE:				GAS BUSTER		
ROT.	150	K#	LAST CSG. RAN: 13 3/8				SET @ 218'		
FUEL	Used:	1227	On Hand: 12972				Co. Man Rick Felker		
BIT # 1 CONDITION		ICS	OCS	DC	LOC	B/S	G	ODC	RP




GASCO ENERGY DAILY DRILLING REPORT

CONFIDENTIAL
T09S R19E S-30
43-047-37613

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19		Permit Depth: 12875		Prog. Depth: 12875		Date: 5/15/2007		Days Since Spud: 4	
Current Operations:		Drig							
Depth: 3478'		Prog: 14		D Hrs: 1		AV ROP: 14.0		Formation: Surface	
DMC: \$1,162		TMC: \$1,874		TDC: \$62,045		CWC: \$603,759			
Contractor: Nabors 99		Mud Co: M-I DRLG FLUIDS		TANGIBLE COST		INTANGIBLE COST			
MW:	8.6	#1 PZ-10	3.48gal/stk	Bit #:	1	Conductor:	\$ -	Loc, Cost:	\$ -
VIS:	28	SPM:	95	Size:	12 1/4	Surf. Csg:	\$ -	Rig Move:	\$ -
PV/YP:	1	#2 PZ-10	3.48gal/stk	Type:	HP51a	Int. Csg:	\$ -	Day Rate:	\$ 23,000
Gel:	1/1/1	SPM:	95	MFG:	Hycalog	Prod Csg:	\$ -	Rental Tools:	\$ 1,800
WL:	nc	GPM:	663	S/N:	JT9607	Float Equip:	\$ -	Trucking:	\$ -
Cake:		Press:	863	Jets:	3/22	Well Head:	\$ -	Water:	\$ -
Solids:		AV DC:	175	TD Out:	3480	TBG/Rods:	\$ -	Fuel:	\$ -
MBT:		AV DP:	112	Depth In:	800	Packers:	\$ -	Mud Logger:	\$ -
PH :	8.0	JetVel:	191	FTG:	2664	Tanks:	\$ -	Logging:	\$ -
Pf/Mf:	2/3.4	ECD:	8.41	Hrs:	53	Separator:	\$ -	Cement:	\$ 35,083
Chlor:	6000	SPR #1 :		FPH:	50.3	Heater:	\$ -	Bits:	\$ -
Ca :	20	SPR #2 :		WOB:	50	Pumping L/T:	\$ -	Mud Motors:	\$ -
Dapp ppb:	2.5	Btm.Up:	27	R-RPM:	125/130	Prime Mover:	\$ -	Corrosion:	\$ -
Time Break Down:		Total D.T. 1		M-RPM:		Misc: \$ -		Consultant: \$ 1,000	
START	END	TIME	Total Rot. Hrs: 52.0		Daily Total: \$ -		Drilling Mud: \$ 1,162		
06:00	07:00	1:00	Drig fl 3464 - 3478 14@14fph		Misc. / Labor: \$ -				
07:00	07:30	0:30	Circulate ,spot dry job		Csg. Crew: \$ -				
07:30	09:00	1:30	Trip out of hole		Daily Total: \$ 62,045				
09:00	10:00	1:00	Circulate ,check for flow, well flowing 11 bbls an hr ,approx 300 bbls		Cum. Wtr: \$ 5,200				
10:00	12:00	2:00	Trip out of hole, Rig stuck in low gear,Academy working on issue		Cum. Fuel \$ 49,700				
12:00	14:30	2:30	Lay down 3-8",lbs(2) ,teledrift,bit sub ,shock tool		Cum. Bits: \$ 15,450				
14:30	16:00	1:30	Saftey meeting,rig up casers		BHA				
16:00	20:30	4:30	Run 83 jts of 8 5/8 casing ,32#,landed@ 3468'		Bits/Bit Sub		4.06		
20:30	22:30	2:00	Circulate ,rig up Schlumberger, Well flowing @24bbls an hour		Ssub/Tele		21.58		
22:30			Cement:with		1-8" DC		29.78		
			626 SKS LEAD YIELD 3.89, WT 11.0, H2O 24.2, TAIL 370 SKS G+ ADDS		IBS		6.30		
			H2O 4.89 GL, YIELD 1.15, BUMB PLUG W/ 800psi over - held		1-8" DC		28.9		
			CEMENT TO SURFACE @ 108 BBLS to pits,wait on cement		IBS		6.73		
			Top Job 1"@220' - 85sxs G,yield 1.15, 15.8# Top off stayed ,		1 - 8" DC		30.32		
	04:00	5:00	Plug held on surface cement job		21 -6.5 DC		657.34		
04:00	06:00	2:00	N/D Conductor		TOTAL BHA =		785.01		
			Notified Randy Bywate		Survey		1/2		3000'
					Survey				
P/U	153	K#	LITH:		DIV. OF OIL, GAS & MINES		BKG GAS		
S/O	150	K#	FLARE:		GAS BUSTER		CONN GAS		
ROT.	150	K#	LAST CSG. RAN:		13 3/8	SET @	218'	PEAK GAS 30	
FUEL	Used:	1227	On Hand:		12972	Co. Man	Rick Felker	TRIP GAS	
BIT # 1 CONDITION	ICS	OCS	DC	LOC	B/S	G	ODC	RP	



GASCO ENERGY DAILY DRILLING REPORT

AFE # 40129


GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL

T095 R19E S30

43-047-376L3

Well: Federal 12-30-9-19		Permit Depth: 12875		Prog. Depth: 12875		Date: 5/16/2007		Days Since Spud: 5			
Current Operations:		Drlg									
Depth: 3478'		Prog: 0		D Hrs: 0		AV ROP:		#DIV/0!		Formation: UNITAH	
DMC: \$1,161		TMC: \$3,035		TDC: \$101,008		CWC: \$756,487					
Contractor: Nabors 99				Mud Co: M-I DRLG FLUIDS				TANGIBLE COST		INTANGIBLE COST	
MW:	w	#1 PZ-10	3.48gal/stk	Bit #:	2	Conductor: \$ -		Loc, Cost: \$ 20,000			
VIS:	a	SPM:	95	Size:	7 7/8	Surf. Csg: \$ -		Rig Move: \$ -			
PV/YP:	t	#2 PZ-10	3.48gal/stk	Type:	DSX 516M	Int. Csg: \$ -		Day Rate: \$ 23,000			
Gel:	e	SPM:	95	MFG:	Hycalog	Prod Csg: \$ -		Rental Tools: \$ 2,000			
WL:	r	GPM:		S/N:	115923	Float Equip: \$ -		Trucking: \$ -			
Cake:		Press:		Jets:	5/18,2/14	Well Head: \$ 3,200		Water: \$ 8,007			
Solids:		AV DC:		TD Out:		TBG/Rods: \$ -		Fuel: \$ -			
MBT:		AV DP:		Depth In:	3478	Packers: \$ -		Mud Logger: \$ -			
PH:		JetVel:		FTG:		Tanks: \$ -		Logging: \$ -			
Pf/Mf:		ECD:		Hrs:		Separator: \$ -		Drilling Overhead \$ 12,000			
Chlor:		SPR #1:		FPH:		Heater: \$ -		Bits: \$ 9,500			
Ca:		SPR #2:		WOB:	10/14	Pumping L/T: \$ -		Mud Motors: \$ -			
Dapp ppb:		Btm.Up:		R-RPM:	50	Prime Mover: \$ -		Insurance \$ 10,000			
Time Break Down:				Total D.T.	M-RPM:	Misc: \$ -		Consultant: \$ 1,000			
START	END	TIME	1	Total Rot. Hrs:	53.0	Daily Total: \$ 3,200		Drilling Mud: \$ 1,161			
06:00	07:00	1:00	Install wellhead					Misc. / Labor: \$ 6,160			
07:00	12:00	5:00	Nipple Up BOP					Csg. Crew: \$ 4,980			
12:00	17:00	5:00	Test BOP , -test ,hcr,annular ,all 3 sets of rams ,casing floor vales					Daily Total: \$ 97,808			
17:00	18:00	1:00	Install Rotating Head ,and Flowline					Cum. Wtr: \$ 13,207			
18:00	19:30	1:30	INSTALL FILL UP , WEAR BUSHING					Cum. Fuel \$ 49,700			
19:30	20:00	0:30	PICK UP BHA					Cum. Bits: \$ 24,950			
20:00	00:30	4:30	TRIP IN HOLE W BHA					BHA			
00:30	01:00	0:30	INSTALL ROTATING HEAD					Bit		1.00	
01:00	06:00	5:00	DRLG CEMENT F/ 3322 - 3468					MTR .13		#2070	33.07
								1-6.5" DC			31.21
								Teledrift			8.53
								IBS			4.65
								1- 6.5 DC			31.00
								IBS			4.15
								19 -6.5 DC			597.50
								TOTAL BHA =		711.11	
								Survey		1	3478'
								Survey			
DIV. OF OIL, GAS & MINING											
BKG GAS											
P/U	153	K#	LITH:	SAS BUSTER				CONN GAS			
S/O	150	K#	FLARE:	SET @ 218'				PEAK GAS			
ROT.	150	K#	LAST CSG. RAN:	13 3/8	Co. Man		Rick Felker	TRIP GAS			
FUEL	Used:	944	On Hand:	11128							
BIT # 2 CONDITION		ICS	OCS	DC	LOC	B/S	G	ODC	RP		



GASCO ENERGY DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL
T095 R11E S-30
43-049-37613

Well: Federal 12-30-9-19		Permit Depth: 12875		Prog. Depth: 12875		Date: 5/17/2007		Days Since Spud: 6	
Current Operations:		TRIP IN HOLE							
Depth: 4313'		Prog: 835		D Hrs: 13		AV ROP: 64.2		Formation: UNITAH	
DMC: \$6,954		TMC: \$6,989		TDC: \$42,454		CWC: \$798,941			
Contractor: Nabors 99				Mud Co: M-I DRLG FLUIDS		TANGIBLE COST		INTANGIBLE COST	
MW:	8.5	#1 PZ-10	3.48gal/stk	Bit #:	2	3	Conductor:	\$ -	Loc. Cost: \$ -
VIS:	27	SPM:	75	Size:	7 7/8	7 7/8	Surf. Csg:	\$ -	Rig Move: \$ -
PV/YP:	1	#2 PZ-10	3.48gal/stk	Type:	DSX 516M	FM3555	Int. Csg:	\$ -	Day Rate: \$ 23,000
Gel:	1/1/1	SPM:	75	MFG:	Hycalog	SEC	Prod Csg:	\$ -	Rental Tools: \$ 2,000
WL:		GPM:	523	S/N:	115923	10924591	Float Equip:	\$ -	Trucking: \$ -
Cake:		Press:	1200	Jets:	5/18,2/14	16-Jul	Well Head:	\$ -	Water: \$ -
Solids:	TR	AV DC:	493	TD Out:	4313		TBG/Rods:	\$ -	Fuel: \$ -
MBT:		AV DP:	267	Depth In:	3478	4313	Packers:	\$ -	Mud Logger: \$ -
PH:	8.4	JetVel:	142	FTG:	835		Tanks:	\$ -	Logging: \$ -
Pf/Mf:	.20/5.4	ECD:		Hrs:	13		Separator:	\$ -	Drilling Overhead \$ -
Chlor:	6000	SPR #1:		FPH:	64.2		Heater:	\$ -	Bits: \$ 9,500
Ca:	20	SPR #2:		WOB:	10/14		Pumping L/T:	\$ -	Mud Motors: \$ -
Dapp ppb:	4.2	Btm.Up:	13	R-RPM:	50		Prime Mover:	\$ -	Insurance \$ -
Time Break Down:			Total D.T.	M-RPM:			Misc:	\$ -	Consultant: \$ 1,000
START	END	TIME	2.5	Total Rot. Hrs: 53.0			Daily Total:	\$ -	Drilling Mud: \$ 6,954
06:00	12:00	6:00	DRLG F/ 3478-3947 469'@78.1 FPH				Misc. / Labor: \$ -		
12:00	12:30	:30	RIG SERVICE				Csg. Crew: \$ -		
12:30	14:00	1:30	WORK ON TOP DRIVE - LUBE OIL SYSTEM				Daily Total: \$ 42,454		
14:00	21:00	7:00	DRLG F/ 3947 - 4313 366'@52.3FPH				Cum. Wtr: \$ 13,207		
21:00	22:00	1:00	CIRCULATE , SPOT DRY JOB				Cum. Fuel \$ 49,700		
22:00	03:30	5:30	TRIP OUT OF HOLE				Cum. Bits: \$ 34,450		
03:30	06:00	2:30	TRIP IN HOLE				BHA		
			<div style="border: 1px solid black; padding: 10px; margin: 0 auto; width: 80%;"> <p style="font-size: 24px; margin: 0;">RECEIVED</p> <p style="font-size: 24px; margin: 0;">MAY 17 2007</p> <p style="font-size: 18px; margin: 0;">DIV. OF OIL, GAS & MINING</p> </div>				Bit		1.00
							MTR .13	#2070	33.07
							1-6.5" DC		31.21
							Teledrift		8.53
							IBS		4.65
							1- 6.5 DC		31.00
							IBS		4.15
							19 -6.5 DC		597.50
							TOTAL BHA = 711.11		
							Survey	1/2	4097'
			Survey						
P/U	153	K#	LITH:	BKG GAS					
S/O	150	K#	FLARE:	GAS BUSTER					
ROT.	150	K#	LAST CSG. RAN: 13 3/8	SET @ 218'	CONN GAS				
FUEL	Used: 1230	On Hand: 10842	Co. Man Rick Felker	PEAK GAS					
			TRIP GAS						
BIT # 2 CONDITION	ICS	OCS	DC	LOC	B/S	G	ODC	RP	
	1		BC	S	X	I		PR	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No 1004-0137
Expires March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	
2. Name of Operator Gasco Production Company	
3a Address 8 Inverness Drive East Ste 100 Englewood, Co 80112	3b Phone No (include area code) 303-483-0044
4 Location of Well (Footage, Sec., T., R., M., or Survey Description) SW NW of Section 30-T9S-R19E 2084' FNL. & 716' FWL	

5. Lease Serial No. U-37246
6. If Indian, Allottee, or Tribe Name NA
7. If Unit or CA. Agreement Name and/or No. NA
8. Well Name and No. Federal 12-30-9-19
9. API Well No. 43-047-37613
10. Field and Pool, or Exploratory Area Riverbend
11. County or Parish, State Utah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Keep data confidential</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug back	<input type="checkbox"/> Water Disposal	

- 13 Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection

Gasco Production Company will be moving a rig onto this location to start drilling within the next few weeks we respectfully request that you keep all records confidential for as long of a period as possible.

14 I hereby certify that the foregoing is true and correct

Name (Printed Typed)

Beverly Walker

Title

Engineering Technician

Signature

Date

May 11, 2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on page 2)

RECEIVED
MAY 18 2007


DIV. OF OIL, GAS & MINING

CONFIDENTIAL
T09S R19E S-30
43-047-37613

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/19/07		DAYS: 8		
Current: Operations:			DRILLING								
Depth: 5888'		Prog: 1429		D Hrs: 22		AV ROP: 65.0		Formation: UNITAH			
DMC: \$850		TMC: \$13,412				TDC: \$50,950		CWC: \$1,000,811			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	8.4	#1 PZ-10	3.48GPM	Bit #:	3	Conductor: \$ -		Loc, Cost: \$ -			
VIS:	26	SPM:	100	Size:	7 7/8	Surf. Csg: \$ -		Rig Move: \$ -			
PV/YF:	1	#2 PZ-10	3.48GPM	Type:	3555Z	Int. Csg: \$ -		Day Rate: \$ 23,000			
Gel:	1/1/1	SPM:	100	MFG:	SEC	Prod Csg: \$ -		Rental Tools: \$ 2,000			
WL:		GPM :	698	S/N:	10924591	Float Equip: \$ -		Trucking: \$ -			
Cake:		Press:	1900	Jets:	7-16	Well Head: \$ -		Water: \$ -			
Solids:	tr	AV DC:	658	TD Out:		TBG/Rods: \$ -		Fuel: \$ 24,100			
MBT		AV DP:	356	Depth In:	4313	Packers: \$ -		Mud Logger: \$ -			
PH :	8.4	JetVel:	213	FTG:	1575	Tanks: \$ -		Logging: \$ -			
Pf/Mf:	02/6.0	ECD:	8.86	Hrs:	26.5	Separator: \$ -		Cement: \$ -			
Chlor:	6000	SPR #1 :		FPH:	59.4	Heater: \$ -		Bits: \$ -			
Ca :	20	SPR #2 :		WOB:	20	Pumping L/T: \$ -		Mud Motors: \$ -			
Dapp ppb:	5.5	Btm.Up:	14	R-RPM:	60	Prime Mover: \$ -		Corrosion: \$ -			
Time Break Down:			Total D.T.		M-RPM:		91		Misc: \$ -		
START	END	TIME	3		Total Rot. Hrs:		92.5		Daily Total: \$ -		
06:00	10:30	4:30	DRLG F/4458' - 4809					351' @78FPH		Misc. / Labor: \$ -	
10:30	11:00	0:30	RIG SERVICE							Csg. Crew: \$ -	
11:00	21:00	10:00	DRLG F/4809 - 5570					761' @76.1FPH		Daily Total: \$ 50,950	
21:00	21:30	0:30	WORK ON PUMP THROTTLES							Cum. Wtr: \$ 13,207	
21:30	22:30	1:00	CHECK SURFACE EQUIPMENT FOR PRESSURE LOSS							Cum. Fuel \$ 73,800	
22:30	06:00	7:30	DRLGF/ 5570 -5888					318' @42.4FPH		Cum. Bits: \$ 34,450	
06:00										BHA	
0								RECEIVED		Bit 1.00	
0								MAY 21 2007		MTR .13 35.53	
0								DIV. OF OIL, GAS & MINES		1-6.5" DC 31.21	
0										Teledrift 8.53	
0			Wasatch	5306'	-582'			IBS 4.65			
0			Mesaverde	9125'	3236'			1- 6.5 DC 31.00			
0			Castlegate	11655'	5767'			IBS 4.15			
0			Desert	11875'	5987'			19-6.5 DC 597.50			
0			Grassy	11915'	6027'						
0			Sunnyside	12030'	6142'			TOTAL BHA = 713.57			
0			Spring Canyor	12575'	6687'			Survey 2 5095'			
		24.00	TD	12875'	6987'	BOILER 0		Survey 3 5515'			
P/U	155 K#	LITH:		Centrifuge				BKG GAS 102			
S/O	148 K#	FLARE:		Gas Buster NO				CONN GAS 102			
ROT.	150 K#	LAST CSG.RAN:		8 5/8"		SET @ 3468		PEAK GAS 3268			
FUEL	Used: 1429	On Hand: 15960		Co.Man Rick Felker		TRIP GAS					
BIT #	ICS	OCS	DC	LOC	B/S	G	ODC	RP			
CONDITION											




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

CONFIDENTIAL
 T095 R19E S-30
 43-047-37613
 GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/20/07		DAYS: 9			
Current: Operations:			DRILLING									
Depth: 6905'		Prog: 1017		D Hrs: 23		AV ROP: 44.2		Formation: UNITAH				
DMC: \$1,000			TMC: \$14,412			TDC: \$59,875			CWC: \$1,063,436			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids				TANGIBLE COST			INTANGIBLE COST	
MW:	8.4	#1 PZ-10	3.48GPM	Bit #:	3	Conductor:			\$ -	Loc, Cost:	\$ -	
VIS:	26	SPM:	100	Size:	7 7/8	Surf. Csg:			\$ -	Rig Move:	\$ 30,000	
PV/YP:	1	#2 PZ-10	3.48GPM	Type:	3555Z	Int. Csg:			\$ -	Day Rate:	\$ 23,000	
Gel:	1/1/1	SPM:	100	MFG:	SEC	Prod Csg:			\$ -	Rental Tools:	\$ 2,000	
WL:		GPM:	698	S/N:	10924591	Float Equip:			\$ -	Trucking:	\$ -	
Cake:		Press:	1900	Jets:	7-16	Well Head:			\$ -	Water:	\$ -	
Solids:	tr	AV DC:	661	TD Out:		TBG/Rods:			\$ -	Fuel:	\$ -	
MBT:		AV DP:	358	Depth In:	4313	Packers:			\$ -	Mud Logger:	\$ -	
PH :	8.4	JetVel:	214	FTG:	2592	Tanks:			\$ -	Logging:	\$ -	
Pf/Mf:	.0/5.90	ECD:	8.7	Hrs:	49.5	Separator:			\$ -	Cement:	\$ -	
Chlor:	6500	SPR #1:		FPH:	52.4	Heater:			\$ -	Bits:	\$ -	
Ca :	80	SPR #2:		WOB:	20/23	Pumping L/T:			\$ -	Mud Motors:	\$ 2,875	
Dapp ppb:	6	Btm.Up:	15	R-RPM:	70/70	Prime Mover:			\$ -	Corrosion:	\$ -	
Time Break Down:				Total D.T. 3		M-RPM: 91		Misc:		\$ -	Consultant:	\$ 1,000
START	END	TIME			Total Rot. Hrs:		115.0	Daily Total:		\$ -	Drilling Mud:	\$ 1,000
06:00	07:00	1:00	DRLG F/ 5888 - 5951					63' @ 63FPH	Misc. / Labor:			\$ -
07:00	07:30	0:30	Rig Service						Csg. Crew:			\$ -
07:30	14:30	7:00	DRLG F/ 5951 - 6238					287' @ 41FPH	Daily Total:			\$ 59,875
14:30	15:00	0:30	Rig Repair - generator -blackout on rig						Cum. Wtr:			\$ 13,207
15:00	06:00	15:00	DRLG F/ 6238 - 6905					667' @ 44.4fph	Cum. Fuel			\$ 73,800
06:00									Cum. Bits:			\$ 34,450
0			<div style="border: 1px solid black; padding: 10px; margin: 0 auto; width: 80%;"> RECEIVED MAY 21 2007 DIV. OF OIL, GAS & MINING </div>					BHA				
0								Bit				1.00
0								MTR .13				35.53
0								1-6.5" DC				31.21
0								Teledrift				8.53
0			IBS				4.65					
0			1- 6.5 DC				31.00					
0			IBS				4.15					
0			19 -6.5 DC				597.50					
0								TOTAL BHA =			713.57	
0			Spring Canyon 12575' 5670'					Survey	3	6047'		
		24.00	TD		12875'	5970'	BOILER		0	Survey		
P/U		155 K#	LITH:		Centrifuge				BKG GAS			
S/O		148 K#	FLARE:		Gas Buster NO				CONN GAS 6			
ROT.		150 K#	LAST CSG.RAN:		8 5/8"	SET @		3400	PEAK GAS 1100			
FUEL		Used: 1343	On Hand:		14617	Co.Man		Rick Felker	TRIP GAS			
BIT #		ICS	OCS	DC	LOC	B/S	G	ODC	RP			
CONDITION												



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129


CONFIDENTIAL

T09SR19E S30

43-047-37613

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/21/07		DAYS: 10		
Current: Operations:			Trip in Hole								
Depth: 7211'		Prog: 306		D Hrs: 10		AV ROP: 30.6		Formation: UNITAH			
DMC: \$1,100		TMC: \$15,512				TDC: \$37,850		CWC: \$1,101,286			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	8.4	#1 PZ-10	3.48GPM	Bit #:	3	4	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	26	SPM:	100	Size:	7 7/8	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$ -	
PV/YP:	1	#2 PZ-10	3.48GPM	Type:	3555Z		Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	1/1/1	SPM:	100	MFG:	SEC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 2,000	
WL:		GPM:	670	S/N:	10924591	7111053	Float Equip:	\$ -	Trucking:	\$ -	
Cake:		Press:	2050	Jets:	7-16		Well Head:	\$ -	Water:	\$ -	
Solids:	0.7	AV DC:	635	TD Out:	7211		TBG/Rods:	\$ -	Fuel:	\$ -	
MBT		AV DP:	342	Depth In:	4313		Packers:	\$ -	Mud Logger:	\$ -	
PH :	8.4	JetVel:	204	FTG:	5893		Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.0/630	ECD:	8.81	Hrs:	59.5		Separator:	\$ -	Cement:	\$ -	
Chlor:	9300	SPR #1 :		FPH:	48.7		Heater:	\$ -	Bits:	\$ 9,500	
Ca :	80	SPR #2 :		WOB:	23/24		Pumping L/T:	\$ -	Mud Motors:	\$ 1,250	
Dapp ppb:	6	Btm.Up:	18	R-RPM:	60/70	50	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.		M-RPM:		Misc:		Consultant:		
			3		87		\$ -		\$ 1,000		
START	END	TIME	Total Rot. Hrs:				125.0		Daily Total:		
							\$ -		Drilling Mud:		
									\$ -		
06:00	08:30	2:30	DRLG F/ 6905 - 7000				95' @38FPH		Misc. / Labor:		
									\$ 1,100		
08:30	09:00	0:30	RIG SERVICE						Csg. Crew:		
									\$ -		
09:00	16:30	7:30	DRLG F/ 7000 - 7211				211' @28.1 FPH		Daily Total:		
									\$ 37,850		
16:30	17:00	0:30	Spot dry job						Cum. Wtr:		
									\$ 13,207		
17:00	23:00	6:00	TRTP FOR BIT						Cum. Fuel		
									\$ 73,800		
23:00	00:00	1:00	Change bit , motor , check wear bushing						Cum. Bits:		
									\$ 43,950		
00:00	06:00	6:00	Trip in Hole - break circ @ 5000 , install rotating head						BHA		
0							Bit		1.00		
0							MTR .13		35.53		
0			Formation real sticky pulling off bottom@7211, overpull of 35k for 2 stds				1-6.5" DC		31.21		
0							Teledrift		8.53		
0							IBS		4.65		
0			Mesaverde 9125' 1914'				1- 6.5 DC		31.00		
0			Castlegate 11655' 4444'				IBS		4.15		
0			Desert 11875' 4664'				19 -6.5 DC		597.50		
0			Grassy 11915' 4704'								
0			Sunnyside 12030' 4819'								
0			Spring Canyon 12575' 5364'								
		24.00	TD		12875'	5664'	BOILER 0		TOTAL BHA = 713.57		
P/U		186 K#	LITH:		Centrifuge		BKG GAS				
S/O		170 K#	FLARE:		Gas Buster NO		CONN GAS		6		
ROT.		186 K#	LAST CSG.RAN:		8 5/8"	SET @	3468	PEAK GAS		1100	
FUEL Used:		1312	On Hand:		13305	Co.Man Rick Felker		TRIP GAS			
BIT #		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION		0	0	no	a	x	l	no	pr		




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/22/07		DAYS: 11		
Current: Operations:			DRILLING								
Depth: 8208'		Prog: 997		D Hrs: 21 1/2		AV ROP: 46.4		Formation: UNITAH			
DMC: \$1,000		TMC: \$16,512				TDC: \$30,288		CWC: \$1,131,574			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST			INTANGIBLE COST		
MW:	8.4	#1 PZ-10	3.48GPM	Bit #:	4	Conductor: \$ -			Loc.Cost: \$ -		
VIS:	26	SPM:	75	Size:	7 7/8	Surf. Csg: \$ -			Rig Move: \$ -		
PV/YP:	1	#2 PZ-10	3.48GPM	Type:	505zx	Int. Csg: \$ -			Day Rate: \$ 23,000		
Gel:	1/1/1	SPM:	75	MFG:	HTC	Prod Csg: \$ -			Rental Tools: \$ 2,000		
WL:		GPM:	550	S/N:	7111053	Float Equip: \$ -			Trucking: \$ -		
Cake:		Press:	1600	Jets:	5-16	Well Head: \$ -			Water: \$ -		
Solids:	0.5	AV DC:	510	TD Out:		TBG/Rods: \$ -			Fuel: \$ -		
MBT		AV DP:	276	Depth In:	7211	Packers: \$ -			Mud Logger: \$ -		
PH :	8.0	JetVel:	165	FTG:	997	Tanks: \$ -			Logging: \$ -		
Pf/Mf:	.0/590	ECD:	8.6	Hrs:	21.5	Separator: \$ -			Cement: \$ -		
Chlor:	10800	SPR #1 :		FPH:	46.4	Heater: \$ -			Bits: \$ -		
Ca :	80	SPR #2 :		WOB:	20/22	Pumping L/T: \$ -			Mud Motors: \$ 2,688		
Dapp ppb:	5.5	Btm.Up:	18	R-RPM:	50/65	Prime Mover: \$ -			Corrosion: \$ -		
Time Break Down:			Total D.T.	M-RPM:	87	Misc: \$ -			Consultant: \$ 1,000		
START	END	TIME	3	Total Rot. Hrs:		146.5	Daily Total: \$ -			Drilling Mud: \$ 1,000	
06:00	06:30	0:30	TRIP IN HOLE							Misc. / Labor: \$ 600	
06:30	08:00	1:30	WASH 120' TO BOTTOM							Csg. Crew: \$ -	
08:00	14:30	6:30	DRLG F/ 7211 - 7477 266' @40.9FPH							Daily Total: \$ 30,288	
14:30	15:00	0:30	RIG SERVICE							Cum. Wtr: \$ 13,207	
15:00	06:00	15:00	DRLG F/7477 - 8208 731' @48.7FPH							Cum. Fuel \$ 73,800	
06:00										Cum. Bits: \$ 43,950	
RECEIVED											
MAY 22 2007											
DIV. OF OIL, GAS & MINING											
0			HARD CAP @7630 - 7640@ 12' AN HOUR, DRLG BREAK@7670 TILL REPORT							BHA	
0			DEPTH OF HIGH 100 TO 200 ROP RATE ON EPOCH							Bit	1.00
0			Mesaverde 9125' 917'							MTR .13	35.53
0			Castlegate 11655' 3447'							1-6.5" DC	31.21
0			Desert 11875' 3667'							Teledrift	8.53
0			Grassy 11915' 3707'							IBS	4.65
0			Sunnyside 12030' 3822'							1- 6.5 DC	31.00
0			Spring Canyon 12575' 4367'							IBS	4.15
0			TD 12875' 4667'							19-6.5 DC	597.50
BOILER 0											
TOTAL BHA = 713.57											
Survey 3 1/2 7382'											
Survey 3 8146'											
P/U	186 K#	LITH:		Centrifuge				BKG GAS		37	
S/O	170 K#	FLARE:		Gas Buster NO				CONN GAS		37	
ROT.	186 K#	LAST CSG.RAN:		8 5/8"	SET @		3468	PEAK GAS		1137	
FUEL	Used:	2025	On Hand:		11280	Co.Man		Rick Felker	TRIP GAS		
BIT #	4	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION											



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19		Per.Depth 12875		Per.Depth 12875		DATE 5/23/07		DAYS: 12	
Current: Operations:		TRIP FOR BIT							
Depth: 8517'		Prog: 309		D Hrs: 16		AV ROP: 19.3		Formation: UNITAH	
DMC: \$1,000		TMC: \$16,512		TDC: \$35,700		CWC: \$1,167,274			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST		INTANGIBLE COST	
MW:	8.4	#1 PZ-10	3.48GPM	Bit #:	4	Conductor:	\$ -	Loc, Cost:	\$ -
VIS:	26	SPM:	80	Size:	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$ 2,800
PV/YP:	1	#2 PZ-10	3.48GPM	Type:	505zx	Int. Csg:	\$ -	Day Rate:	\$ 23,000
Gel:	1/1/1	SPM:	80	MFG:	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 2,000
WL:		GPM:	600	S/N:	7111053	Float Equip:	\$ -	Trucking:	\$ 300
Cake:		Press:	2000	Jets:	5-16	Well Head:	\$ -	Water:	\$ 4,600
Solids:	0.5	AV DC:	375	TD Out:		TBG/Rods:	\$ -	Fuel:	\$ -
MBT		AV DP:	205	Depth In:	7211	Packers:	\$ -	Mud Logger:	\$ -
PH :	8.2	JetVel:	130	FTG:	1306	Tanks:	\$ -	Logging:	\$ -
Pr/Mf:	.0/620	ECD:	8.5	Hrs:	37.5	Separator:	\$ -	Cement:	\$ -
Chlor:	11500	SPR #1 :		FPH:	34.8	Heater:	\$ -	Bits:	\$ -
Ca :	40	SPR #2 :		WOB:	20/22	Pumping L/T:	\$ -	Mud Motors:	\$ -
Dapp ppb:	5.5	Btm.Up:	37	R-RPM:	50/65	Prime Mover:	\$ -	Corrosion:	\$ -
Time Break Down:		Total D.T.		M-RPM:		Misc:		\$ - Consultant:	
		3		80		Daily Total:		\$ - Drilling Mud:	
START	END	TIME	Total Rot. Hrs:				162.5		Daily Total:
06:00	15:30	9:30	DRLG F/ 8208 - 8430				222' @23.4 FPH		Misc. / Labor:
15:30	16:00	0:30	RIG SERVICE						Csg. Crew:
16:00	22:30	6:30	DRLG F/8430 - 8517				87' @13.3 FPH		Daily Total:
22:30	01:00	2:30	Circulate and mud up						Cum. Wtr:
01:00	01:30	0:30	SPOT DRY JOB						Cum. Fuel
01:30	06:00	4:30	TRIP OUT OF HOLE						Cum. Bits:
06:00									BHA
0			STARTED MUD UP @ 8400						Bit
0									MTR .13
0									1-6.5" DC
0									Teledrift
0									BS
0									1- 6.5 DC
0									BS
0									19 -6.5 DC
0									TOTAL BHA =
0									713.57
0									Survey
0									Survey
		24.00							3 8146'
			TD		12875'	4358'	BOILER		0
P/U		186 K#	LITH:		Centrifuge		BKG GAS		37
S/O		170 K#	FLARE:		Gas Buster NO		CONN GAS		37
ROT.		186 K#	LAST CSG.RAN:		8 5/8"	SET @	3468	PEAK GAS	
FUEL		Used: 2025	On Hand:		9255	Co.Man		Rick Felker	TRIP GAS
BIT #		4	ICS	OCS	DC	LOC	B/S	G	ODC
CONDITION									




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/24/07		DAYS: 13			
Current: Operations:			SLIP & CUT DRILLING LINE.									
Depth: 8517'		Prog: 0		D Hrs: 0		AV ROP:		#DIV/0!		Formation: UNITAH		
DMC: \$0		TMC: \$16,512				TDC: \$38,100		CWC: \$1,205,374				
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids				TANGIBLE COST		INTANGIBLE COST		
MW:	8.4	#1 PZ-10	3.48GPM	Bit #:	4	5	Conductor:	\$ -	Loc, Cost:	\$ -		
VIS:	26	SPM:	80	Size:	7-7/8"	7-7/8"	Surf. Csg:	\$ -	Rig Move:	\$		
PV/YP:	1	#2 PZ-10	3.48GPM	Type:	505zx	505zx	Int. Csg:	\$ -	Day Rate:	\$ 10,100		
Gel:	1/1/1	SPM:	80	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600		
WL:		GPM:	558	S/N:	7111053	7114209	Float Equip:	\$ -	Trucking:	\$ -		
Cake:		Press:	2000	Jets:	5-16	5X16 2X15	Well Head:	\$ -	Water:	\$ -		
Solids:	0.5	AV DC:	375	TD Out:	8517		TBG/Rods:	\$ -	Fuel:	\$ 24,200		
MBT		AV DP:	205	Depth In:	7211	8,517'	Packers:	\$ -	Mud Logger:	\$ -		
PH :	8.2	JetVel:	130	FTG:	1306		Tanks:	\$ -	Logging:	\$ -		
Pf/Mf:	.0/620	ECD:	8.5	Hrs:	37.5		Separator:	\$ -	Cement:	\$ -		
Chlor:	11500	SPR #1 :		FPH:	34.8		Heater:	\$ -	Bits:	\$ -		
Ca :	40	SPR #2 :		WOB:	20/22		Pumping L/T:	\$ -	Mud Motors:	\$ -		
Dapp ppb:	5.5	Btm.Up:	37	R-RPM:	50/65		Prime Mover:	\$ -	Corrosion:	\$ -		
Time Break Down:			Total D.T. 16.5		M-RPM: 80		Misc: \$ -		Consultant: \$ 2,000			
START	END	TIME	Total Rot. Hrs: 162.5		Daily Total: \$ -		Drilling Mud: \$ -		Misc. / Labor: \$ 200			
06:00	09:30	3:30	POOH FOR BIT							Csg. Crew: \$ -		
09:30	10:30	1.00	L/D MOTOR, TELEDRIFT TOOL & BIT							Daily Total: \$ 38,100		
10:30	11:00	0:30	P/ NEW MOTOR & BIT & RIH W/BHA							Cum. Wtr: \$ 13,207		
11:00	14:00	3:00	CONT. RIH TO 3550'							Cum. Fuel \$ 98,000		
14:00	03:30	13:30	RIG ON DOWN TIME. REPAIR HIGH DRUM CLUTCH, CHANGE OUT LUBE PUMP ON TOP DRIVE & CHANGE OUT BLADDER ON PULSATION DAMPER. AFTER REPAIRING HIGH DRUM CLUTCH.							Cum. Bits: \$ 68,150		
			RUN TOP DRIVE UP & DOWN SEEMS TO BE OK. ATTEMPT TO MAKE UP TOP DRIVE BUT WILL ONLY							BHA		
			RUN IN REVERSE & UNABLE TO CONTROL SPEED. TROUBLE SHOOT SYSTEM. ALSO WILL HAVE TO							Bit		1.00
			READJUST KICK OUT BRACE TO TOP DRIVE, SO TOP DRIVE LINES UP WITH DRILL PIPE IN ROTARY							MTR .13	6026	32.90
			TABLE AFTER TROUBLE. EVERYTHING WORKING EXCEPT TORQUE MECH. DRIVING TO OTHER RIG							1-6.5" DC		31.21
			GET DECODER TO FIX TORQUE READING.									
03:30	06:00	2:30	SLIP & CUT DRILLING LINE.							IBS		4.65
			Mesaverde	9125'	608'				1- 6.5 DC		31.00	
			Castlegate	11655'	3138'				IBS		4.15	
			Desert	11875'	3358'				19 -6.5 DC		597.50	
			Grassy	11915'	3398'							
			Sunnyside	12030'	3513'				TOTAL BHA =		702.41	
			Spring Canyon	12575'	4058'				Survey			
		24.00	TD	12875'	4358'	BOILER	0		Survey	3	8146'	
P/U	K#	LITH:	Centrifuge					BKG GAS		37		
S/O	K#	FLARE:	Gas Buster NO					CONN GAS		37		
ROT.	K#	LAST CSG.RAN:	8 5/8"		SET @	3468		PEAK GAS		1137		
FUEL	Used:	2025	On Hand:		9255		Co.Man	Jim Weir	TRIP GAS			
BIT #	4	ICS	OCS	DC	LOC	B/S	G	ODC	RP			
CONDITION	1	2	CT	S	X	I	BT	PR				




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/25/07		DAYS: 14		
Current: Operations:			POOH FOR BIT DUE TO ROP								
Depth: 9252'		Prog: 735		D Hrs: 15		AV ROP: 49.0		Formation: UNITAH			
DMC: \$7,417			TMC: \$24,102			TDC: \$53,192			CWC: \$1,271,466		
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	8.6	#1 PZ-10	3.48GPM	Bit #:	4	5	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	33	SPM:	70	Size:	7-7/8"	7-7/8"	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	4/4	#2 PZ-10	3.48GPM	Type:	505zx	505zx	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	1/2	SPM:	70	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	15.2	GPM:	558	S/N:	7111053	7114209	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	1	Press:	1600	Jets:	5-16	5X16 2X15	Well Head:	\$ -	Water:	\$ 300	
Solids:	1.3	AV DC:	375	TD Out:	8517	9252	TBG/Rods:	\$ -	Fuel:	\$	
MBT	7.5	AV DP:	205	Depth In:	7211	8,517'	Packers:	\$ -	Mud Logger:	\$ -	
PH :	8.0	JetVel:	130	FTG:	1306	735	Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/3.90	ECD:	8.5	Hrs:	37.5	15	Separator:	\$ -	Cement:	\$ -	
Chlor:	9800	SPR #1 :		FPH:	34.8	49.0	Heater:	\$ -	Bits:	\$ 18,000	
Ca :	40	SPR #2 :		WOB:	20/22	20/26	Pumping L/T:	\$ -	Mud Motors:	\$ 1,875	
Dapp ppb:	4	Btm.Up:	37	R-RPM:	50/65	50/65	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	80	63/75	Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	16.5	Total Rot. Hrs:		177.5	Daily Total:	\$ -	Drilling Mud:	\$ 7,417	
6:00	07:00	1.00	CONT. CUT & SLIP 99' DRILLING LINE							Misc. / Labor:	\$
07:00	10:00	3.00	RIH W/DRILL PIPE TO 8,429' OK							Csg. Crew:	\$ -
10:00	11:00	1.00	REAM & WASH F/8,429' TO 8,517' {4' FILL}							Daily Total:	\$53,192
11:00	02:00	15.00	DRILLING AHEAD 7-7/8" HOLE F/8,517' TO 9,252' ROP=49'							Cum. Wtr:	\$ 13,507
02:00	02:30	0.50	CIRC. & PUMP SLUG & DROP SURVEY TOOL							Cum. Fuel	\$ 98,000
02:30	03:00	0.50	WORK TIGHT HOLE F/9,252' TO 9,235'							Cum. Bits:	\$ 86,150
03:00	06:00	3.00	POOH FOR BIT DUE TO ROP. NOTE: FOUND NEW SURVEY TOOL							BHA	
			BETWEEN STAND # 30 & 31. WILL L/D JT WHEN RIH							Bit	1.00
			(BIT STILL IN HOLE)							MTR .13	6026 32.90
										1-6.5" DC	31.21
										IBS	4.65
			Mesaverde 9125' 608'							1- 6.5 DC	31.00
			Castlegate 11655' 2403'							IBS	4.15
			Desert 11875' 2623'							19 -6.5 DC	597.50
			Grassy 11915' 2663'								
			Sunnyside 12030' 2778'							TOTAL BHA = 702.41	
			Spring Canyon 12575' 3323'							Survey	
		24.00	TD	12875'	3623'	BOILER		0	Survey	3 8146'	
P/U	260 K#	LITH:		Centrifuge				BKG GAS		40	
S/O	210 K#	FLARE:		Gas Buster NO				CONN GAS		300	
ROT.	230 K#	LAST CSG.RAN:		8 5/8"	SET @		3468	PEAK GAS		800	
FUEL	Used: 1476	On Hand: 16,649		Co.Man Jim Weir				TRIP GAS		1400	
BIT #	5	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION											




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

43.047.37613
30 95 19e
GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19		Per.Depth 12875		Per.Depth 12875		DATE 5/26/07		DAYS: 15				
Current: Operations:		DRILLING AHEAD 7-7/8" HOLE										
Depth: 9665'		Prog: 413		D Hrs: 12 1/2		AV ROP: 33'		Formation: MESAVERDE				
DMC: \$4,357		TMC: \$28,460		TDC: \$31,957		CWC: \$1,303,423						
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST		INTANGIBLE COST				
MW:	9.1	#1 PZ-10	3.48GPM	Bit #:	5	6	Conductor:	\$ -	Loc, Cost:	\$ -		
VIS:	34	SPM:	85	Size:	7-7/8"	7-7/8"	Surf. Csg:	\$ -	Rig Move:	\$ -		
PV/YP:	4/6	#2 PZ-10	3.48GPM	Type:	505zx	506ZX	Int. Csg:	\$ -	Day Rate:	\$ 23,000		
Gel:	4/11	SPM:	85	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600		
WL:	18	GPM:	592	S/N:	7114209	7115686	Float Equip:	\$ -	Trucking:	\$ 300		
Cake:	1	Press:	1966	Jets:	5X16 2X16	6X16	Well Head:	\$ -	Water:	\$ 300		
Solids:	5.1	AV DC:	592	TD Out:	9252	9252	TBG/Rods:	\$ -	Fuel:	\$ -		
MBT:	10	AV DP:	320.8	Depth In:	8517	9252	Packers:	\$ -	Mud Logger:	\$ -		
PH:	8.1	JetVel:	152	FTG:	735	413	Tanks:	\$ -	Logging:	\$ -		
Pf/Mf:	.00/3.40	ECD:	8.5	Hrs:	15	12.5	Separator:	\$ -	Cement:	\$ -		
Chlor:	10000	SPR #1:		FPH:	49.0	33.0	Heater:	\$ -	Bits:	\$ -		
Ca:	40	SPR #2:		WOB:	20/26	20/26	Pumping L/T:	\$ -	Mud Motors:	\$ -		
Dapp ppb:	3.5	Btm.Up:	28	R-RPM:	50/65	64/75	Prime Mover:	\$ -	Corrosion:	\$ -		
Time Break Down:		Total D.T.		M-RPM:		Misc:		Consultant:		\$ 1,000		
		16.5		63/75		N/A		Daily Total:		\$ -		
START	END	TIME	Total Rot. Hrs: 177.5							Drilling Mud:		\$ 4,357
6:00	09:00	3.00	CONTINUE POOH NO TIGHT HOLE							Misc. / Labor:		\$ 1,400
09:00	09:30	0.50	L/D MUD MOTOR & BIT							Csg. Crew:		\$ -
09:30	10:00	0.50	RIG SERVICE							Daily Total:		\$31,957
10:00	11:00	1.00	M/U NBS & BIT & RIH W/BHA							Cum. Wtr:		\$ 13,507
11:00	15:30	4.50	RIH NO TIGHT HOLE							Cum. Fuel		\$ 98,000
15:30	16:30	1.00	WASH & REAM F/9,087' TO 9,252' NO TIGHT HOLE							Cum. Bits:		\$ 86,150
16:30	18:30	2.00	DRILLING AHEAD 7-7/8" HOLE F/9,252' TO 9,341' ROP=44.5'							BHA		
18:30	19:30	1.00	RIG DOWN REPAIR ENCODER							Bit		1.00
19:30	06:00	10.50	DRILL F/9,341' TO 9,665' ROP=31'							NBS		3.43
										2-6.5" DC		62.21
										IBS		4.65
			Mesaverde 9125' 608'							1- 6.5 DC		31.00
			Castlegate 11655' 1990'							IBS		4.15
			Desert 11875' 2210'							18 -6.5 DC		566.04
			Grassy 11915' 2250'									
			Sunnyside 12030' 2365'							TOTAL BHA =		672.48
			Spring Canyon 12575' 2910'							Survey	3	8146'
		24.00	TD 12875' 3210'							Survey	M/R	9252'
P/U 260 K#		LITH:		Centrifuge		BKG GAS		955				
S/O 210 K#		FLARE:		Gas Buster NO		CONN GAS		1756				
ROT. 230 K#		LAST CSG.RAN:		8 5/8" SET @		3468		PEAK GAS		1950		
FUEL Used:		1394		On Hand:		15,255		Co.Man Jim Weir		TRIP GAS 7500		
BIT # 5		ICS		OCS		DC		LOC		B/S G	ODC RP	
CONDITION		1		3		WT		S/T		X	I BF PR	



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/27/07		DAYS: 16		
Current: Operations:			DRILLING AHEAD 7-7/8" HOLE								
Depth: 9822'		Prog: 157		D Hrs: 10 1/2		AV ROP: 15'		Formation: UPPER MESAVERDE			
DMC: \$4,107		TMC: \$32,567				TDC: \$55,976		CWC: \$1,359,399			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	9.1	#1 PZ-10	3.48GPM	Bit #:	6	7	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	40	SPM:	85	Size:	7-7/8"	7-7/8"	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	4/6	#2 PZ-10	3.48GPM	Type:	506ZX	506ZX	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	9/14	SPM:	85	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	16	GPM :	592	S/N:	7115686		Float Equip:	\$ -	Trucking:	\$	
Cake:	2	Press:	1966	Jets:	6X16	2X15 4X16	Well Head:	\$ -	Water:	\$ 900	
Solids:	5	AV DC:	592	TD Out:	9822		TBG/Rods:	\$ -	Fuel:	\$	
MBT	10	AV DP:	320.8	Depth In:	9252	9822	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.7	JetVel:	152	FTG:	570		Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/4.00	ECD:	8.5	Hrs:	25.5		Separator:	\$ -	Cement:	\$ -	
Chlor:	10600	SPR #1 :		FPH:	22.4		Heater:	\$ -	Bits:	\$ 18,000	
Ca :	40	SPR #2 :		WOB:	18/30		Pumping L/T:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	3	Btm.Up:	28	R-RPM:	50/75		Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T. 16.5	M-RPM:	N/A		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME		Total Rot. Hrs:		177.5	Daily Total:	\$ -	Drilling Mud:	\$ 4,107	
6:00	15:30	9.50	DRILLING AHEAD 7-7/8" HOLE F/9,665' TO 9,818'						Misc. / Labor:		\$7,369
15:30	16:00	0.50	RIG SERVICE						Csg. Crew:		\$
16:00	17:00	1.00	DRILL F/9818' TO 9,822'						Daily Total:		\$55,976
17:00	17:30	0.50	CIRC WHILE MIX SLUG						Cum. Wtr:		\$ 14,707
17:30	18:00	0.50	SLUG D.P. & DROP TOTCO SURVEY						Cum. Fuel		\$ 98,000
18:00	23:30	5.50	POOH FOR BIT DUE TO ROP						Cum. Bits:		\$ 104,150
23:30	01:00	1.50	L/D BIT & NBS & P/U NEW BIT & RIH W/BHA						BHA		
01:00	06:00	5.00	RIH & BREAK CIRC. @ 5,000' & 9,718'						Bit		1.00
									NBS		3.43
									2-6.5" DC		62.21
			UPPER MESAVERDA 9125						IBS		4.65
			LOWER MESA 10800'						1- 6.5 DC		31.00
			Castlegate	11655'	1833'			IBS		4.15	
			Desert	11875'	2053'			18 -6.5 DC		566.04	
			Grassy	11915'	2093'						
			Sunnyside	12030'	2208'			TOTAL BHA = 672.48			
			Spring Canyon	12575'	2753'			Survey	3	8146'	
		24.00	TD	12875'	3053'	BOILER		0	Survey	M/R 9252'	
P/U 260 K#		LITH:		Centrifuge				BKG GAS		955	
S/O 210 K#		FLARE:		Gas Buster NO				CONN GAS		1756	
ROT. 230 K#		LAST CSG.RAN:		8 5/8"		SET @ 3468		PEAK GAS		1950	
FUEL Used: 1394		On Hand: 15,255		Co.Man		Jim Weir		TRIP GAS		7500	
BIT # 6		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION		1	2	WT	S/T	X	I	CT	PR		




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/28/07		DAYS: 17		
Current: Operations:			DRILLING AHEAD 7-7/8" HOLE								
Depth: 10358'		Prog: 536		D Hrs: 22 1/2		AV ROP: 24.0		Formation: UPPER MESAVERDE			
DMC: \$4,000		TMC: \$36,567				TDC: \$29,600		CWC: \$1,388,999			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST			INTANGIBLE COST		
MW:	9.3	#1 PZ-10	3.48GPM	Bit #:	7	Conductor: \$ -			Loc, Cost: \$ -		
VIS:	43	SPM:	0	Size:	7-7/8"	Surf. Csg: \$ -			Rig Move: \$ -		
PV/YP:	9/14	#2 PZ-10	3.48GPM	Type:	506ZX	Int. Csg: \$ -			Day Rate: \$ 23,000		
Gel:	10/21/	SPM:	117	MFG:	HTC	Prod Csg: \$ -			Rental Tools: \$ 1,600		
WL:	15.2	GPM:	400	S/N:		Float Equip: \$ -			Trucking: \$ -		
Cake:	2	Press:	1000	Jets:	2x15,4x16	Well Head: \$ -			Water: \$ -		
Solids:	5	AV DC:	384	TD Out:		TBG/Rods: \$ -			Fuel: \$ -		
MBT	10	AV DP:	208	Depth In:	9822	Packers: \$ -			Mud Logger: \$ -		
PH :	7.7	JetVel:	152	FTG:	536	Tanks: \$ -			Logging: \$ -		
Pf/Mf:	.00/4.30	ECD:	9.6	Hrs:	22.5	Separator: \$ -			Cement: \$ -		
Chlor:	10500	SPR #1 :		FPH:	24.0	Heater: \$ -			Bits: \$ -		
Ca :	40	SPR #2 :		WOB:	18/20	Pumping L/T: \$ -			Mud Motors: \$ -		
Dapp ppb:	3.5	Btm.Up:	44.3	R-RPM:	50/75	Prime Mover: \$ -			Corrosion: \$ -		
Time Break Down:			Total D.T.	M-RPM:	N/A	Misc: \$ -			Consultant: \$ 1,000		
START	END	TIME	16.5	Total Rot. Hrs:		200.0		Daily Total: \$ -		Drilling Mud: \$ 4,000	
6:00	06:30	0:30	Trip in Hole						Misc. / Labor: \$0		
06:30	07:00	0:30	Ream 100 ft to bottom						Csg. Crew: \$		
07:00	09:00	2:00	DRLG F/ 9822 -9913 91'@45.5FPH						Daily Total: \$29,600		
09:00	09:30	:30	Rig Service						Cum. Wtr: \$ 14,707		
09:30	06:00	20:30	DRLG F/ 9913 -10358 445'@21.7 FPH						Cum. Fuel \$ 98,000		
0		0.00							Cum. Bits: \$ 104,150		
0		0.00							BHA		
0		0.00							Bit	1.00	
		0.00							BS	4.00	
									2-6.5" DC	62.21	
			UPPER MESAVERDA 9125						IBS	4.65	
			LOWER MESA 10800'						1- 6.5 DC	31.00	
			Castlegate		11655'	1297'			IBS	4.15	
			Desert		11875'	1517'			18 -6.5 DC	566.04	
			Grassy		11915'	1557'					
			Sunnyside		12030'	1672'			TOTAL BHA = 673.05		
			Spring Canyon		12575'	2217'			Survey	11 1/2 9822'	
		24.00	TD		12875'	2517'	BOILER 0		Survey		
P/U 260 K#		LITH:		Centrifuge				BKG GAS		2570	
S/O 210 K#		FLARE:		5' -8' FLARE ON VENT				Gas Buster VENTING		CONN GAS 2570	
ROT. 230 K#		LAST CSG.RAN:		8 5/8" SET @ 3468				PEAK GAS		5075	
FUEL Used: 1170		On Hand: 12,958		Co.Man Rick Felker		TRIP GAS				6050	
BIT # 6		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION											



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/29/07		DAYS: 18		
Current: Operations:			WASHING TO BOTTOM								
Depth: 10476'		Prog: 118		D Hrs: 7 1/2		AV ROP: 15.7		Formation: UPPER MESAVERDE			
DMC: \$3,300		TMC: \$39,867				TDC: \$38,400		CWC: \$1,427,399			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	9.6	#1 PZ-10	3.48GPM	Bit #:	7	8	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	41	SPM:	0	Size:	7-7/8"	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	8/15	#2 PZ-10	3.48GPM	Type:	506ZX	506ZX+	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	9/21/	SPM:	117	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	41.4	GPM :	400	S/N:	7114380		Float Equip:	\$ -	Trucking:	\$	
Cake:	2	Press:	1000	Jets:	2x15,4x16	3X15,3X16	Well Head:	\$ -	Water:	\$ -	
Solids:	5	AV DC:	384	TD Out:	104486		TBG/Rods:	\$ -	Fuel:	\$	
MBT	10	AV DP:	208	Depth In:	9822	10476	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.7	JetVel:	99	FTG:	654		Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/5.0	ECD:	10.0	Hrs:	30		Separator:	\$ -	Cement:	\$ -	
Chlor:	9900	SPR #1 :		FPH:	21.8		Heater:	\$ -	Bits:	\$ 9,500	
Ca :	40	SPR #2 :		WOB:	18/20		Pumping L/T:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	4	Btm.Up:	46.4	R-RPM:	50/75		Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	N/A		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	17.5	Total Rot. Hrs:		207.5	Daily Total:	\$ -	Drilling Mud:	\$ 3,300	
6:00	13:30	7:30	DRLG F/10358 - 10476 118' @15.7 FPH						Misc. / Labor:	\$0	
13:30	14:00	:30	PUMP DRY JOB , DROP SURVEY						Csg. Crew:	\$	
14:00	16:00	2:00	TRIP OUT OF HOLE						Daily Total:	\$38,400	
16:00	17:00	1:00	DOWN TIME ST-80 REPAIR						Cum. Wtr:	\$ 14,707	
17:00	20:30	3:30	TRIP OUT OF HOLE						Cum. Fuel	\$ 98,000	
20:30	22:00	1:30	Change bit, recover survey and check wear bushing						Cum. Bits:	\$ 113,650	
22:00	00:30	2:30	TRIP IN HOLE TO SHOE						BHA		
00:30	01:30	1:00	RIG SERVICE - TOP DRIVE - RETIGHTEN WASH PIPE						Bit	1.00	
01:30	03:30	2:00	TRIP IN HOLE						BS	4.00	
03:30	04:00	:30	INSTALL ROTATING HEAD - FILL PIPE @7000						2-6.5" DC	62.21	
04:00	06:00	2:00	TRIP IN HOLE - WASHING 90 FT TO BOTTOM								
			DRLG BY 6:30AM						IBS	4.65	
			LOWER MESA 10800'						1- 6.5 DC	31.00	
			Castlegate		11655'	1179'		IBS	4.15		
			Desert		11875'	1399'		18 -6.5 DC	566.04		
			Grassy		11915'	1439'					
			Sunnyside		12030'	1554'		TOTAL BHA = 673.05			
			Spring Canyon		12575'	2099'		Survey	2 10476'		
		24.00	TD		12875'	2399'	BOILER	0	Survey		
P/U	280 K#	LITH:		Centrifuge			BKG GAS		400		
S/O	240 K#	FLARE:		10' FLARE WHILE TRIPPING IN ON VENT			Gas Buster VENTING		CONN GAS 1178		
ROT.	260 K#	LAST CSG.RAN:		8 5/8"		SET @ 3468		PEAK GAS		3750	
FUEL	Used: 558	On Hand:		12,400		Co.Man Rick Felker		TRIP GAS		7350	
BIT # 7		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION		1	1	CT	ST	X	I	NO	PR		



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/30/07		DAYS: 19		
Current: Operations:			DRILLING								
Depth: 10963'		Prog: 487		D Hrs: 22 1/2		AV ROP: 21.6		Formation: LOWER MESAVERDE			
DMC: \$2,100		TMC: \$41,967				TDC: \$31,129		CWC: \$1,458,528			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids				TANGIBLE COST		INTANGIBLE COST	
MW:	9.8	#1 PZ-10	3.48GPM	Bit #:	8	Conductor:		\$ -	Loc, Cost:	\$ -	
VIS:	43	SPM:	0	Size:	7-7/8"	Surf. Csg:		\$ -	Rig Move:	\$ -	
PV/YP:	8/19	#2 PZ-10	3.48GPM	Type:	506ZX	Int. Csg:		\$ -	Day Rate:	\$ 23,000	
Gel:	9/21/	SPM:	117	MFG:	HTC	Prod Csg:		\$ -	Rental Tools:	\$ 1,600	
WL:	15.2	GPM:	408	S/N:	7114930	Float Equip:		\$ -	Trucking:	\$ 450	
Cake:	2	Press:	1100	Jets:	3x15,3x16	Well Head:		\$ -	Water:	\$ -	
Solids:	8	AV DC:	384	TD Out:		TBG/Rods:		\$ -	Fuel:	\$ -	
MBT	10	AV DP:	208	Depth In:	10476	Packers:		\$ -	Mud Logger:	\$ -	
PH :	7.6	JetVel:	133	FTG:	487	Tanks:		\$ -	Logging:	\$ -	
Pf/Mf:	.00/4.6	ECD:	10.1	Hrs:	22.5	Separator:		\$ -	Cement:	\$ -	
Chlor:	9700	SPR #1 :		FPH:	21.6	Heater:		\$ -	Bits:	\$ -	
Ca :	40	SPR #2 :		WOB:	20/25	Pumping L/T:		\$ -	Mud Motors:	\$ -	
Dapp ppb:	4	Btm.Up:	47.3	R-RPM:	50/75	Prime Mover:		\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	N/A	Misc:		\$ -	Consultant:	\$ 1,000	
START	END	TIME	17.5	Total Rot. Hrs:		230.0	Daily Total:	\$ -	Drilling Mud:	\$ 2,100	
6:00	07:00	1:00	WASHING TO BOTTOM 90 FT - NO FILL						Misc. / Labor:	\$2,979	
07:00	14:30	7:30	DRLG F/ 10476 - 10677 201'@26.8FPH						Csg. Crew:	\$	
14:30	15:00	:30	RIG SERVICE						Daily Total:	\$31,129	
15:00	18:00	3:00	DRLG F/ 10677 - 10772 95'@31.6FPH						Cum. Wtr:	\$ 14,707	
18:00	06:00	12:00	DRLG F/ 10772 - 10963 191'@15.9FPH						Cum. Fuel	\$ 98,000	
									Cum. Bits:	\$ 113,650	
									BHA		
									Bit	1.00	
									BS	4.00	
									2-6.5" DC	62.21	
			AT 10870 - 10880 EPOCH SHOWED 9600 UNITS WITH 20FT FLARE								
									IBS	4.65	
			LOWER MESA 10800'						1- 6.5 DC	31.00	
			Castlegate 11655' 692'						IBS	4.15	
			Desert 11875' 912'						18 -6.5 DC	566.04	
			Grassy 11915' 952'								
			Sunnyside 12030' 1067'						TOTAL BHA = 673.05		
			Spring Canyon 12575' 1612'						Survey	2 10476'	
		24.00	TD		12875'	1912'	BOILER	0	Survey		
P/U		280 K#	LITH:		Centrifuge			BKG GAS		1000	
S/O		240 K#	FLARE:		10' FLARE			Gas Buster VENTING		CONN GAS 2000	
ROT.		260 K#	LAST CSG.RAN:		8 5/8" SET @		3468		PEAK GAS 9600		
FUEL		Used: 853	On Hand:		11,549		Co.Man Rick Felker		TRIP GAS 9600		
BIT #	7	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION											




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 5/31/07		DAYS: 20		
Current: Operations:			DRILLING								
Depth: 11106'		Prog: 143		D Hrs: 10		AV ROP: 14.3		Formation: LOWER MESAVERDE			
DMC: \$2,900			TMC: \$44,867			TDC: \$29,700		CWC: \$1,488,228			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	10.2	#1 PZ-10	3.48GPM	Bit #:	8	9	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	38	SPM:	0	Size:	7-7/8"	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	8/11	#2 PZ-10	3.48GPM	Type:	506ZX+	506ZX+	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	7/17/	SPM:	117	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	15.6	GPM :	408	S/N:	7114930	715677	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	1250	Jets:	3x15,3x16	6X16	Well Head:	\$ -	Water:	\$ 1,200	
Solids:	9	AV DC:	384	TD Out:	11002		TBG/Rods:	\$ -	Fuel:	\$	
MBT	10	AV DP:	208	Depth In:	10476	11002	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.9	JetVel:	133	FTG:	526	104	Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/4.5	ECD:	10.49	Hrs:	26.5	6	Separator:	\$ -	Cement:	\$ -	
Chlor:	9900	SPR #1 :		FPH:	19.8	17.3	Heater:	\$ -	Bits:	\$ -	
Ca :	40	SPR #2 :		WOB:	20/25	20/25	Pumping L/T:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	3.5	Btm.Up:	49.1	R-RPM:	50/75	60/75	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T. 17.5	M-RPM:	N/A		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME		Total Rot. Hrs:		240.0	Daily Total:	\$ -	Drilling Mud:	\$ 2,900	
6:00	10:00	4:00	DRLG F/ 10963 - 11002 39'@9.75FPH						Misc. / Labor:	\$0	
10:00	10:30	:30	DROP SURVEY						Csg. Crew:	\$	
10:30	15:30	5:00	TRIP OUT FOR BIT						Daily Total:	\$29,700	
15:30	16:00	:30	CHANGE BIT RETRIEVE TOTCO						Cum. Wtr:	\$ 15,907	
16:00	21:30	5:50	TRIP IN HOLE						Cum. Fuel	\$ 98,000	
21:30	22:30	1:00	WASH AND REAM TO BOTTOM - 90 FT						Cum. Bits:	\$ 113,650	
22:30	00:30	2:00	DRLG F/ 11002 - 11059 57'@28.5FPH						BHA		
00:30	2:00	1:30	CIRCULATE OUT GAS @11059 - 10200 UNITS						Bit		1.00
2:00	6:00	4:00	DRLG F/11059 - 11106 47'@11.8 FPH						BS		4.00
									2-6.5" DC		62.21
									IBS		4.65
			LOWER MESA 10800'						1- 6.5 DC		31.00
			Castlegate 11655' 549'						IBS		4.15
			Desert 11875' 769'						18 -6.5 DC		566.04
			Grassy 11915' 809'								
			Sunnyside 12030' 924'						TOTAL BHA = 673.05		
			Spring Canyon 12575' 1469'						Survey	2	10476'
		24.00	TD 12875'		1769'	BOILER 0		Survey			
P/U 280 K#		LITH:		Centrifuge				BKG GAS 2159			
S/O 240 K#		FLARE: 20'FLARE		Gas Buster VENTING				CONN GAS 2159			
ROT. 260 K#		LAST CSG.RAN:		8 5/8"		SET @ 3468		PEAK GAS 10000			
FUEL Used: 853		On Hand: 11,549		Co.Man Rick Felker		TRIP GAS 10200					
BIT # 8		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION		1	8	BC	S/T	X	I	WC	PR		




GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 6/1/07		DAYS: 21		
Current: Operations:			DRILLING								
Depth: 11239'		Prog: 133		D Hrs: 8 1/2		AV ROP: 15.6		Formation: LOWER MESAVERDE			
DMC: \$4,547			TMC: \$49,414				TDC: \$49,447		CWC: \$1,537,675		
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	10.4	#1 PZ-10	3.48GPM	Bit #:	10	9	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	40	SPM:	0	Size:	7-7/8"	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	9/15	#2 PZ-10	3.48GPM	Type:	506ZX+	506ZX+	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	9/20/	SPM:	117	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	15	GPM :	408	S/N:	7115676	715677	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	1250	Jets:	6X16	6X16	Well Head:	\$ -	Water:	\$ -	
Solids:	10	AV DC:	384	TD Out:		11121	TBG/Rods:	\$ -	Fuel:	\$	
MBT	10	AV DP:	208	Depth In:	11121	11002	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.8	JetVel:	133	FTG:	118	119	Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/4.6	ECD:	10.79	Hrs:	6.5	8	Separator:	\$ -	Cement:	\$ -	
Chlor:	10600	SPR #1 :		FPH:	18.1	14.8	Heater:	\$ -	Bits:	\$ 18,000	
Ca :	40	SPR #2 :		WOB:	10/18	20/25	Pumping L/T:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	3.5	Btm.Up:	49.7	R-RPM:	60/70	60/75	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T. 17.5	M-RPM:	N/A		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME		Total Rot. Hrs:		248.5	Daily Total:	\$ -	Drilling Mud:	\$ 4,547	
6:00	08:00	2:00	DRLG F/11106 - 11121 15`@7.5FPH					Misc. / Labor:		\$1,300	
08:00	08:30	:30	CIRC AND SPOT PILL					Csg. Crew:		\$	
08:30	15:00	6:30	TRIP OUT OF HOLE					Daily Total:		\$49,447	
15:00	16:00	1:00	XO BIT ,LAY DOWN STABILIZERS					Cum. Wtr:		\$ 15,907	
16:00	22:00	6:00	TRIP IN HOLE					Cum. Fuel		\$ 98,000	
22:00	23:30	1:30	Wash to bottom ,circulate up gas					Cum. Bits:		\$ 113,650	
23:30	06:00	6:30	DRLG F/11121 - 11239 118`@18.1FPH					BHA			
								Bit		1.00	
								BS		4.00	
								2-6.5" DC		62.21	
			10` FLARE WHILE DRILLING, WENT THRU BUSTER WHILE CIRCULATING GAS					IBS		4.65	
			LOWER MESA 10800'					1- 6.5 DC		31.00	
			Castlegate	11655'	416'			IBS		4.15	
			Desert	11875'	636'			18 -6.5 DC		566.04	
			Grassy	11915'	676'						
			Sunnyside	12030'	791'			TOTAL BHA =		673.05	
			Spring Canyon	12575'	1336'			Survey	2	10476'	
		24.00	TD	12875'	1636'	BOILER	0	Survey			
P/U	284 K#	LITH:	Centrifuge				BKG GAS		2159		
S/O	274 K#	FLARE:	80`FLARE BOTTOM UP				Gas Buster VENTING		CONN GAS 2159		
ROT.	267 K#	LAST CSG.RAN:	8 5/8"		SET @	3468		PEAK GAS		10000	
FUEL	Used: 1108	On Hand:	9,505		Co.Man	Rick Felker		TRIP GAS		10200	
BIT # 9		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION		1	4	BC	S/T	X	I	WC	PR		



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

CONFIDENTIAL
43.047 37613
30 95 19e

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 6/2/07		DAYS: 22		
Current: Operations:			TRIP FOR BIT								
Depth: 11565'		Prog: 326		D Hrs: 16		AV ROP: 20.4		Formation: LOWER MESAVERDE			
DMC: \$3,481		TMC: \$52,895				TDC: \$30,081		CWC: \$1,568,756			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST			INTANGIBLE COST		
MW:	10.4	#1 PZ-10	3.48GPM	Bit #:	10	Conductor: \$ -		Loc, Cost: \$ -			
VIS:	40	SPM:	0	Size:	7-7/8"	Surf. Csg: \$ -		Rig Move: \$ -			
PV/YP:	9/16	#2 PZ-10	3.48GPM	Type:	506ZX+	Int. Csg: \$ -		Day Rate: \$ 23,000			
Gel:	8/19/	SPM:	117	MFG:	HTC	Prod Csg: \$ -		Rental Tools: \$ 1,600			
WL:	16	GPM:	408	S/N:	7115676	Float Equip: \$ -		Trucking: \$ -			
Cake:	2	Press:	1250	Jets:	6X16	Well Head: \$ -		Water: \$ -			
Solids:	10	AV DC:	384	TD Out:	11565	TBG/Rods: \$ -		Fuel: \$ -			
MBT	10	AV DP:	208	Depth In:	11121	Packers: \$ -		Mud Logger: \$ -			
PH :	7.6	JetVel:	133	FTG:	444	Tanks: \$ -		Logging: \$ -			
Pf/Mf:	.00/5.10	ECD:	10.81	Hrs:	22.5	Separator: \$ -		Cement: \$ -			
Chlor:	9500	SPR #1:	40@120	FPH:	19.7	Heater: \$ -		Bits: \$ -			
Ca :	40	SPR #2:	60@380	WOB:	28	Pumping L/T: \$ -		Mud Motors: \$ -			
Dapp ppb:	4	Btm.Up:	50.6	R-RPM:	100	Prime Mover: \$ -		Corrosion: \$ -			
Time Break Down:			Total D.T.		M-RPM:		Misc:		Consultant:		
			17.5		N/A		\$ -		\$ 2,000		
START	END	TIME	Total Rot. Hrs:			248.5		Daily Total: \$ -		Drilling Mud: \$ 3,481	
6:00	12:00	6.00	Drlg f/ 11239 - 11335 96'@16fph					Misc. / Labor: \$0			
12:00	12:30	0.50	Rig Service					Csg. Crew: \$			
12:30	22:30	10.00	DRILL F/11,335' TO 11,565' ROP=23'					Daily Total: \$30,081			
22:30	23:00	0.50	MIX & SLUG DRILL PIPE					Cum. Wtr: \$ 15,907			
23:00	04:00	5.00	POOH W/DRILL PIPE					Cum. Fuel \$ 98,000			
04:00	06:00	2.00	POOH W/BHA L/D 3EA 6-1/4" DRILL COLLARS BAD L/D BIT					Cum. Bits: \$ 131,650			
			CHANGE OUT FLOAT SPRING TO FLAPPER					BHA			
								Bit		1.00	
								BS		4.00	
								2-6.5" DC		62.21	
								IBS		4.65	
			LOWER MESA 10800'					1- 6.5 DC		31.00	
			Castlegate 11655' 90'					IBS		4.15	
			Desert 11875' 310'					18 -6.5 DC		566.04	
			Grassy 11915' 350'								
			Sunnyside 12030' 465'					TOTAL BHA = 673.05			
			Spring Canyon 12575' 1010'					Survey	2	10476'	
		24.00	TD 12875'		1310'		BOILER 0		Survey		
P/U 284 K#		LITH:		Centrifuge				BKG GAS		2159	
S/O 274 K#		FLARE: 10'FLARE		Gas Buster VENTING				CONN GAS		2159	
ROT. 267 K#		LAST CSG.RAN:		8 5/8"		SET @ 3468		PEAK GAS		10000	
FUEL Used: 1281		On Hand: 7,265		Co.Man JIM WEIR		TRIP GAS		10200			
BIT # 10		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION 2		8	RO	G/S/T	X	I	RO	PP	RO		



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 6/3/07		DAYS: 23		
Current: Operations:			DRILLING								
Depth: 11693'		Prog: 128		D Hrs: 9		AV ROP: 14.2		Formation: CASTLEGATE			
DMC: \$1,498		TMC: \$54,136				TDC: \$76,348		CWC: \$1,645,104			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	10.6	#1 PZ-10	3.48GPM	Bit #:	10	11	Conductor:	\$ -	Loc, Cost:	\$ -	
VIS:	36	SPM:	0	Size:	7-7/8"	7-7/8"	Surf. Csg:	\$ -	Rlg Move:	\$ -	
PV/YP:	6/18	#2 PZ-10	3.48GPM	Type:	506ZX+	506zx+	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	11/20	SPM:	117	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	18	GPM:	408	S/N:	7115676	7115674	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	1200	Jets:	6X16	6X16	Well Head:	\$ -	Water:	\$ 900	
Solids:	10	AV DC:	384	TD Out:	11565		TBG/Rods:	\$ -	Fuel:	\$ -	
MBT	10	AV DP:	208	Depth In:	11121	11565	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.9	JetVel:	133	FTG:	444	128	Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/5.70	ECD:	10.81	Hrs:	22.5	9	Separator:	\$ -	Cement:	\$ -	
Chlor:	9800	SPR #1 :	40@120	FPH:	19.7	14.2	Heater:	\$ -	Bits:	\$ 48,350	
Ca :	40	SPR #2 :	60@380	WOB:	28	16/24	Pumping LT:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	4	Btm.Up:	50.6	R-RPM:	100	65/70	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	N/A	N/A	Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	17.5	Total Rot. Hrs:		257.5	Daily Total:	\$ -	Drilling Mud:	\$ 1,498	
6:00	08:00	2.00	P/U BHA & RIH SAME							Misc. / Labor:	\$0
08:00	17:00	9.00	RIH TO 11,440' BREAK CIRC. @ 5,000' & 10,000'							Csg. Crew:	\$
17:00	21:00	4.00	REAM & WASH UNDER GAUGE HOLE F/11,440' TO 11,565' MAX WOB 3K							Daily Total:	\$76,348
21:00	06:00	9.00	DRILL F/11,565' TO 11,693' ROP=14.22'							Cum. Wtr:	\$ 16,807
										Cum. Fuel	\$ 98,000
										Cum. Bits:	\$ 180,000
										BHA	
										Bit	1.00
										BS	4.00
										2-6.5" DC	62.21
										IBS	4.15
			LOWER MESA 10800'							1- 6.5 DC	31.46
			Castlegate 11655' -38'							IBS	4.65
			Desert 11875' 182'							15 -6.5 DC	471.89
			Grassy 11915' 222'								
			Sunnyside 12030' 337'							TOTAL BHA = 579.36	
			Spring Canyon 12575' 882'							Survey	2 10476'
		24.00	TD		12875'	1182'	BOILER	0	Survey		
P/U		284 K#	LITH:		Centrifuge			BKG GAS		2488	
S/O		274 K#	FLARE:		10" FLARE			Gas Buster VENTING		CONN GAS 7924	
ROT.		267 K#	LAST CSG.RAN:		8 5/8" SET @			3468		PEAK GAS 8900	
FUEL		Used: 1066	On Hand:		6,199			Co.Man JIM WEIR		TRIP GAS 9200	
BIT #		10	ICS	OCS	DC	LOC	B/S	G	ODC	RP	
CONDITION		2	8	RO	G/S/T	X	3/4"	RO	PP	RO	



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 6/4/07		DAYS: 24		
Current: Operations:			RIH W/NEW BIT								
Depth: 11,768'		Prog: 75		D Hrs: 10		AV ROP: 7.5		Formation: CASTLEGATE			
DMC: \$2,797		TMC: \$57,234				TDC: \$57,797		CWC: \$1,702,901			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	10.5	#1 PZ-10	3.48GPM	Bit #:	10	11	P	\$ -	Loc, Cost:	\$ -	
VIS:	36	SPM:	0	Size:	7-7/8"	7-7/8"	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	7/15	#2 PZ-10	3.48GPM	Type:	506ZX+	506zx+	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	14/31	SPM:	117	MFG:	HTC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	20	GPM :	408	S/N:	7115676	7115674	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	3	Press:	1200	Jets:	6X16	6X16	Well Head:	\$ -	Water:	\$ 1,400	
Solids:	10	AV DC:	384	TD Out:	11565	11765	TBG/Rods:	\$ -	Fuel:	\$	
MBT	10	AV DP:	208	Depth In:	11121	11565	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.8	JetVel:	133	FTG:	444	200	Tanks:	\$ -	Logging:	\$ -	
P#Mf:	.00/6.30	ECD:	10.81	Hrs:	22.5	19	Separator:	\$ -	Cement:	\$ -	
Chlor:	9800	SPR #1 :	40@150	FPH:	19.7	10.5	Heater:	\$ -	Bits:	\$ 28,000	
Ca :	40	SPR #2 :	60@460	WOB:	28	18/29	Pumping L/T:	\$ -	Mud Motors:	\$	
Dapp ppb:	4	Btm.Up:	50.6	R-RPM:	100	55/85	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	N/A	N/A	Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	19	Total Rot. Hrs:		267.5	Daily Total:	\$ -	Drilling Mud:	\$ 2,797	
6:00	13:00	7.00	DRILLING 7-7/8" HOLE F/11,693' TO 11,755'						Misc. / Labor:	\$	
13:00	14:00	1.00	RIG DOWN WORK ON MUD PUMPS						Csg. Crew:	\$	
14:00	16:00	2.00	DRILL F/11,755' TO 11,765' ROP=5'						Daily Total:	\$57,797	
16:00	16:30	0.50	RIG DOWN WORK ON WT. INDICATOR BLEED OFF 40K SET SLIPS &						Cum. Wtr:	\$ 18,207	
			PUMP UP SAME. HAVE TOOLPUSHER CALL ACADEMY & SEND A REP OUT						Cum. Fuel	\$ 98,000	
			ASAP						Cum. Bits:	\$ 208,000	
16:30	17:30	1.00	DRILL F/11,765' TO 11,765' ROP=3'						BHA		
17:30	18:30	1.00	CIRC. WHILE BUILD SLUG. SLUG DRILL PIPE & DROP NEW SURVEY						Bit	1.00	
			TOOL						BS	4.00	
18:30	00:00	5.50	POOH ON SINGLE CHANGE BREAKS ON DRILL PIPE						2-6.5" DC	62.21	
00:00	01:30	1.50	POOH W/BHA L/D BIT & BS RETRIEVE SURVEY TOOL MISS RUN								
01:30	02:00	0.50	PULL WEAR BUSHING OK						IBS	4.15	
02:00	06:00	4:00	M/U BIT & RIH TO 5,871' BREAK CIRC @ 5,500'						1- 6.5 DC	31.46	
			Castlegate	11655'	#VALUE!				IBS	4.65	
			Desert	11875'	#VALUE!				15 -6.5 DC	471.89	
			Grassy	11915'	#VALUE!						
			Sunnyside	12030'	#VALUE!				TOTAL BHA = 579.36		
			Spring Canyon	12575'	#VALUE!				Survey	2 10476'	
		24.00	TD	12875'	#VALUE!		BOILER	0	Survey	M/R 11,765'	
P/U 284 K#		LITH:		Centrifuge				BKG GAS		2600	
S/O 274 K#		FLARE:		10' TO 12' FLARE		Gas Buster VENTING		CONN GAS		7400	
ROT. 267 K#		LAST CSG.RAN:		8 5/8"		SET @ 3468		PEAK GAS		5500	
FUEL Used: 987		On Hand:		5,212		Co.Man JIM WEIR		TRIP GAS		N/A	
BIT # 11		ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION		1	4	WT	G/S/T/N	X	I	CT	PR		



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 6/5/07		DAYS: 25		
Current: Operations:			RIH W/NEW BIT								
Depth: 12010'		Prog: 242		D Hrs: 22 1/2		AV ROP: 11'		Formation: GRASSY			
DMC: \$5,386		TMC: \$62,621				TDC: \$31,986		CWC: \$1,606,278			
Contractor: NABORS 99				Mud Co: M-I Drig. Fluids				TANGIBLE COST		INTANGIBLE COST	
MW:	10.6	#1 PZ-10	3.48GPM	Bit #:	12	P		\$ -	Loc, Cost:	\$ -	
VIS:	39	SPM:	0	Size:	7-7/8"	Surf. Csg:		\$ -	Rig Move:	\$	
PV/YP:	8/19	#2 PZ-10	3.48GPM	Type:	506ZX+	Int. Csg:		\$ -	Day Rate:	\$ 23,000	
Gel:	13/30/39	SPM:	117	MFG:	HTC	Prod Csg:		\$ -	Rental Tools:	\$ 1,600	
WL:	20	GPM:	408	S/N:	7114931	Float Equip:		\$ -	Trucking:	\$ -	
Cake:	3	Press:	1200	Jets:	2X15 4X16	Well Head:		\$ -	Water:	\$	
Solids:	10	AV DC:	384	TD Out:	IN HOLE	TBG/Rods:		\$ -	Fuel:	\$	
MBT	10.25	AV DP:	208	Depth In:	11768	Packers:		\$ -	Mud Logger:	\$ -	
PH :	7.8	JetVel:	133	FTG:	242	Tanks:		\$ -	Logging:	\$ -	
Pf/Mf:	.00/6.40	ECD:	10.81	Hrs:	22.5	Separator:		\$ -	Cement:	\$ -	
Chlor:	10000	SPR #1 :	40@150	FPH:	10.7	Heater:		\$ -	Bits:	\$	
Ca :	20	SPR #2 :	60@460	WOB:	18/28	Pumping L/T:		\$ -	Mud Motors:	\$	
Dapp ppb:	3.3	Btm.Up:	50.6	R-RPM:	55/75	Prime Mover:		\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.		M-RPM:		N/A		Misc:		
START	END	TIME	19		Total Rot. Hrs:		290.0		Daily Total:		
6:00	09:30	3.50	CONTINUE RIH TO 11,768' {NO BRIDGES OR TIGHT SPOTS}							Misc. / Labor:	
09:30	10:30	1.00	REAM & WASH F/11,768' TO 11,768'							Csg. Crew:	
10:30	13:30	3.00	DRILL 7-7/8" HOLE F/11,768' TO 11,820' ROP=17.33							Daily Total:	
13:30	14:00	0.50	SERVICE RIG							Cum. Wtr:	
14:00	06:00	16.00	DRILL F/11,820' TO 12,010' ROP=12'							Cum. Fuel	
										Cum. Bits:	
										BHA	
										Bit	1.00
										BS	4.00
										2-6.5" DC	62.21
										IBS	4.15
										1- 6.5 DC	31.46
			Castlegate 11621' -389'							IBS	4.65
			Desert 11891' -119'							15 -6.5 DC	471.89
			Grassy 12001' -9'								
			Sunnyside 12106' 96'							TOTAL BHA =	
			Spring Canyon 12561' 551'							Survey	2 10476'
		24.00	TD 12761' 751'		BOILER		0		Survey	M/R 11,765'	
P/U	284 K#	LITH:		Centrifuge				BKG GAS		1200	
S/O	274 K#	FLARE:		8' TO 10' FLARE				Gas Buster VENTING		7450	
ROT.	267 K#	LAST CSG.RAN:		8 5/8"		SET @		3468		PEAK GAS	
FUEL	Used:	1345	On Hand:		3,867		Co.Man		JIM WEIR		
BIT #	12	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION											

GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Per.Depth 12875		DATE 6/6/07		DAYS: 26		
Current: Operations:			Reaming								
Depth: 12012'		Prog: 2		D Hrs: 1/2		AV ROP:		Formation: GRASSY			
DMC: \$7,365		TMC: \$69,986				TDC: \$43,190		CWC: \$1,649,468			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	10.8	#1 PZ-10	3.48GPM	Bit #:	12	13	P	\$ -	Loc, Cost:	\$ -	
VIS:	50	SPM:	0	Size:	7-7/8"	7/7/2008	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	10/18	#2 PZ-10	3.48GPM	Type:	506ZX+	mi616	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	14/28/35	SPM:	117	MFG:	HTC	STC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	18	GPM :	408	S/N:	7114931	6417330001	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	1200	Jets:	2X15 4X16	6X16	Well Head:	\$ -	Water:	\$ 1,800	
Solids:	10	AV DC:	384	TD Out:	12012		TBG/Rods:	\$ -	Fuel:	\$	
MBT	12.5	AV DP:	208	Depth In:	11768	12012	Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.9	JetVel:	111	FTG:	244		Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	00/3.80	ECD:	11.8	Hrs:	24.5		Separator:	\$ -	Cement:	\$ -	
Chlor:	10000	SPR #1 :	40@150	FPH:	10.7		Heater:	\$ -	Bits:	\$ 8,000	
Ca :	20	SPR #2 :	60@460	WOB:	18/28		Pumping L/T:	\$ -	Mud Motors:	\$	
Dapp ppb:	3	Btm.Up:	54	R-RPM:	55/75		Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	N/A		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	19.5	Total Rot. Hrs:		292.0	Daily Total:	\$ -	Drilling Mud:	\$ 7,365	
6:00	06:30	:30	DRLG F/ 12010 - 12012						Misc. / Labor:		\$425
06:30	07:30	1:00	CIRC AND SPOT PILL						Csg. Crew:		\$
07:30	08:00	:30	DROP SURVEY						Daily Total:		\$43,190
08:00	16:00	8:00	TRIP FOR BIT						Cum. Wtr:		\$ 18,207
16:00	17:00	1:00	XO BIT , P/U MTR, CHECK WEAR BUSHING						Cum. Fuel		\$ 98,000
17:00	22:00	5:00	TRIP IN HOLE						Cum. Bits:		\$ 86,250
22:00	22:30	:30	Work on ST 80						BHA		
22:30	1:30	3:00	TRIP IN HOLE						Bit		1.00
1:30	6:00	4:30	Ream and wash to bottom						MTR	0.16	33.13
			ST 80 BROKE DOWN , CHAIN TONG GOING IN HOLE						18-6.5" DC		565.56
			Daylights pumped 125 bbls to pit								
			Both pumps- liners and swabs								
			Castlegate	11621'	-391'						
			Desert	11891'	-121'						
			Grassy	12001'	-11'						
			Sunnyside	12106'	94'			TOTAL BHA = 599.69			
			Spring Canyon	12561'	549'			Survey	2	10476'	
		24.00	TD	12761'	749'	BOILER 0		Survey	2	12012'	
P/U		284 K#	LITH:	8" while drilling			Centrifuge		BKG GAS 4273		
S/O		274 K#	FLARE:	80" FLARE after trip			Gas Buster VENTING		CONN GAS 4273		
ROT.		267 K#	LAST CSG.RAN:		8 5/8"	SET @	3468		PEAK GAS 4273		
FUEL		Used: 1345	On Hand:		3,867	Co.Man	JIM WEIR		TRIP GAS 9000		
BIT #		12	ICS	OCS	DC	LOC	B/S	G	ODC	RP	
CONDITION		1	4	BC	S/T	x	WC	wc	pr		

Well: Federal 12-30-9-19			Per.Depth 12875		Prog.Depth 12761		DATE 6/7/07		DAYS: 27		
Current: Operations:			DRILLING								
Depth: 12378'		Prog: 366		D Hrs: 20 1/2		AV ROP: 17.8		Formation:			
DMC: \$2,445			TMC: \$72,431			TDC: \$47,418			CWC: \$1,696,886		
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST			INTANGIBLE COST	
MW:	10.9+	#1 PZ-10	3.48GPM	Bit #:	13		P	\$ -	Loc, Cost:	\$ -	
VIS:	51	SPM:	0	Size:	7 7/8		Surf. Csg:	\$ -	Rig Move:	\$	
PV/Y.P:	17/28	#2 PZ-10	3.48GPM	Type:	mi616		Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	16/36/42	SPM:	117	MFG:	STC		Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	20	GPM :	408	S/N:	6417330001		Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	2400	Jets:	6X16		Well Head:	\$ -	Water:	\$ -	
Solids:	12	AV DC:	384	TD Out:			TBG/Rods:	\$ -	Fuel:	\$ 14,010	
MBT	12.75	AV DP:	208	Depth In:	12012		Packers:	\$ -	Mud Logger:	\$ -	
PH :	8.0	JetVel:	111	FTG:	366		Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/6.60	ECD:	11.45	Hrs:	20.5		Separator:	\$ -	Cement:	\$ -	
Chlor:	10000	SPR #1 :	40@300	FPH:	17.8		Heater:	\$ -	Bits:	\$ -	
Ca :	20	SPR #2 :	60@650	WOB:	20/28		Pumping L/T:	\$ -	Mud Motors:	\$ 2,562	
Dapp ppb:	4.4	Btm.Up:	54.7	R-RPM:	60/70		Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	60		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	30.5	Total Rot. Hrs:		312.5	Daily Total:	\$ -	Drilling Mud:	\$ 2,445	
6:00	13:30	7:30	DRLG F/ 2012 - 12158				146`@19.4FPH		Misc. / Labor:	\$2,800	
13:30	14:00	:30	RIG SERVICE - TOP DRIVE						Csg. Crew:	\$	
14:00	20:00	6:00	DRLG F/ 12158 -12316				158`@26.3FPH		Daily Total:	\$44,855	
20:00	21:00	1:00	Down Time - Generators ran out of fuel ,						Cum. Wtr:	\$ 18,207	
21:00	01:30	4:30	DRLGV F12316-12349 - BIT BALLED UP				33`@7.3' FPH		Cum. Fuel	\$ 98,000	
01:30	02:00	:30	Short trip bit to unball 5 stds						Cum. Bits:	\$ 86,250	
02:00	04:30	2:30	Drlg f/12349 - 12378				39`@15.6fph		BHA		
4:30	6:00	1:30	Rip 10stds out to unball bit						Bit	1.00	
									MTR	0.16	
									18-6.5" DC	565.56	
			Motor man did not transfer fuel ,ran out of fuel								
			ST 80 broke down again after receiving valve and parts								
			Castlegate	11621'	-757'						
			Desert	11891'	-487'						
			Grassy	12001'	-377'						
			Sunnyside	12106'	-272'			TOTAL BHA = 599.69			
			Spring Canyor	12561'	183'			Survey	2	10476'	
		24.00	TD	12761'	383'	BOILER	0	Survey	2	12012'	
P/U	284 K#	LITH:	5' flare while drilling				Centrifuge	BKG GAS		4273	
S/O	274 K#	FLARE:					Gas Buster VENTING	CONN GAS		4273	
ROT.	267 K#	LAST CSG.RAN:	8 5/8"		SET @	3468	PEAK GAS		4273		
FUEL	Used: 1226	On Hand:	5,914		Co.Man	JIM WEIR	TRIP GAS		9000		
BIT #	13	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION											



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19				Per.Depth 12875		Prog.Depth 12761		DATE 6/8/07		DAYS: 28	
Current: Operations:				DRILLING							
Depth: 12447'		Prog: 38		D Hrs: 5		AV ROP: 13.6		Formation:			
DMC: \$2,445		TMC: \$74,876				TDC: \$37,045		CWC: \$1,733,931			
Contractor: NABORS 99				Mud Co: M-I Drig. Fluids				TANGIBLE COST		INTANGIBLE COST	
MW:	11	#1 PZ-10	3.48GPM	Bit #:	13	14	P	\$ -	Loc, Cost:	\$ -	
VIS:	51	SPM:	0	Size:	7 7/8	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	17/28	#2 PZ-10	3.48GPM	Type:	mi616	505ZX	Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	16/36/42	SPM:	117	MFG:	STC	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	20	GPM:	408	S/N:	6417330001	7009469	Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	1400	Jets:	6X16	6X16	Well Head:	\$ -	Water:	\$ -	
Solids:	12	AV DC:	384	TD Out:	12387		TBG/Rods:	\$ -	Fuel:	\$ -	
MBT	12.75	AV DP:	208	Depth In:	12012	12387	Packers:	\$ -	Mud Logger:	\$ -	
PH :	8.0	JetVel:	111	FTG:	366	69	Tanks:	\$ -	Logging:	\$ -	
Pf/Mf:	.00/6.60	ECD:	11.45	Hrs:	20.5	5	Separator:	\$ -	Cement:	\$ -	
Chlor:	10000	SPR #1 :	40@300	FPH:	17.8	13.6	Heater:	\$ -	Bits:	\$ 9,000	
Ca :	20	SPR #2 :	60@650	WOB:	20/28	20/28	Pumping L/T:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	4.4	Btm.Up:	54.7	R-RPM:	60/70	60/80	Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:	60		Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	30.5	Total Rot. Hrs:		317.5	Daily Total:	\$ -	Drilling Mud:	\$ 2,445	
6:00	07:30	1:30	Spot pill ,Trip out							Misc. / Labor:	\$0
07:30	08:00	:30	Pull Rotating Head							Csg. Crew:	\$
08:00	14:00	6:00	Trip out of hole							Daily Total:	\$37,045
14:00	15:00	1:00	Laydown Mtr,check wear bushing							Cum. Wtr:	\$ 18,207
15:00	17:30	2:00	TRIP IN HOLE (STRAP IN)							Cum. Fuel	\$ 98,000
17:30	19:30	2:00	CUT DRLG LINE							Cum. Bits:	\$ 86,250
19:30	00:00	4:30	TRIP IN HOLE (STRAP IN)							BHA	
00:00	00:30	:30	Ream to bottom -90ft - no fill							Bit	1.00
00:30	3:00	2:30	DRLG F/ 12378 -12390 12'@4.8FPH							MTR	0.16 33.13
03:00	3:30	12:00	DOWNTIME - PUMPS- SWABS							18-6.5" DC	565.56
3:30	6:00	2:30	DRLG F/ 12390 - 12447 57'@22.8								
			MTR FAILURE ,RUBBER IN BIT JETS								
			Castlegate	11621'	-826'						
			Desert	11891'	-556'						
			Grassy	12001'	-446'						
			Sunnyside	12106'	-341'						
			Spring Canyon	12561'	114'						
		24.00	TD	12761'	314'		BOILER	0	Survey		
P/U	275 K#	LITH:	5" flare while drilling				Centrifuge	BKG GAS	4273		
S/O	268 K#	FLARE:	30' FLARE AFTER TRIP				Gas Buster VENTING	CONN GAS	4273		
ROT.	271 K#	LAST CSG.RAN:	8 5/8" SET @				3468	PEAK GAS	4273		
FUEL	Used: 748	On Hand:	5,166				Co.Man RICK FELKER	TRIP GAS	7000		
BIT #	13	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION	1		2	EU	S	X	I	CT	EMF		

[illegible]

[illegible]



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129


GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19				Per.Depth 12875		Prog.Depth 12761		DATE 6/11/07		DAYS: 31		
Current: Operations:				Trip out for logs								
Depth: 12730'		Prog:		D Hrs:		AV ROP: 0.0		Formation: Spring Canyon				
DMC: \$2,300		TMC: \$86,100		TDC: \$27,900		CWC: \$1,853,338						
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST			INTANGIBLE COST			
MW:	11.3	#1 PZ-10	3.48GPM	Bit #:	14	P	\$ -	Loc, Cost:	\$ -			
VIS:	51	SPM:	0	Size:	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$			
PV/YP:	11/28	#2 PZ-10	3.48GPM	Type:	505ZX	Int. Csg:	\$ -	Day Rate:	\$ 23,000			
Gel:	15/35/41	SPM:	117	MFG:	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600			
WL:	18	GPM:	408	S/N:	7009469	Float Equip:	\$ -	Trucking:	\$ -			
Cake:	2	Press:	1400	Jets:	6X16	Well Head:	\$ -	Water:	\$ -			
Solids:	13	AV DC:	384	TD Out:	12730	TBG/Rods:	\$ -	Fuel:	\$ -			
MBT	15	AV DP:	208	Depth In:	12387	Packers:	\$ -	Mud Logger:	\$ -			
PH :	7.8	JetVel:	111	FTG:	343	Tanks:	\$ -	Logging:	\$ -			
Pf/Mf:	.00/6.60	ECD:	11.74	Hrs:	45	Separator:	\$ -	Cement:	\$ -			
Chlor:	10000	SPR #1:	40@300	FPH:	7.6	Heater:	\$ -	Bits:	\$ -			
Ca :	20	SPR #2:	60@650	WOB:	20/28	Pumping L/T:	\$ -	Mud Motors:	\$ -			
Dapp ppb:	4.9	Btm.Up:	57.2	R-RPM:	60/80	Prime Mover:	\$ -	Corrosion:	\$ -			
Time Break Down:				Total D.T. 36		M-RPM:		Misc: \$ -		Consultant: \$ 1,000		
START	END	TIME			Total Rot. Hrs:		362.0	Daily Total: \$ -		Drilling Mud: \$ 2,300		
6:00	11:30	5:30	Trip out for logs							Misc. / Labor: \$0		
11:30	12:30	1:00	Rig up PSI to log							Csg. Crew: \$		
12:30	13:00	:30	Saftey Meeting with crews and loggers							Daily Total: \$27,900		
13:00	15:30	2:30	logging - hit bridge@ 6073							Cum. Wtr: \$ 18,207		
15:30	18:00	2:30	Pick up pipe -trip in to clean out hole							Cum. Fuel \$ 135,833		
18:00	23:00	5:00	Downtime - Pipe handler broke down							Cum. Bits: \$ 95,250		
23:00	04:30	5:50	Trip in hole							BHA		
04:30	06:00	1:30	Trip out for logs							Bit		1.00
										MTR	0.16	33.13
										18-6.5" DC		565.56
			Logs went to 6073' on first run									
			Well acting fine no flow ,									
			Sunnyside 12106' -624'							TOTAL BHA = 599.69		
			Spring Canyon 12561' -169'									
		24.00	TD 12730' 0'		BOILER 0							
P/U 275 K#		LITH:		Centrifuge				BKG GAS 4273				
S/O 268 K#		FLARE:		Gas Buster VENTING				CONN GAS 4273				
ROT. 271 K#		LAST CSG.RAN:		8 5/8" SET @		3468		PEAK GAS 10000				
FUEL Used: 2564		On Hand: 10,123		Co.Man RICK FELKER		TRIP GAS						
BIT # 14	ICS	OCS	DC	LOC	B/S	G	ODC	RP				
CONDITION 0	2	ct	s	x	l	cw	td					

Well: Federal 12-30-9-19			Per.Depth 12875		Prog.Depth 12761		DATE 6/12/07		DAYS: 32		
Current: Operations:			Trip out for logs								
Depth: 12730'		Prog:		D Hrs:		AV ROP: 0.0		Formation: Spring Canyon			
DMC: \$300		TMC: \$86,400		TDC: \$34,400		CWC: \$1,887,738					
Contractor: NABORS 99			Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST			
MW:	11.3	#1 PZ-10	3.48GPM	Bit #:	14	P	\$ -	Loc, Cost:	\$ -		
VIS:	51	SPM:	0	Size:	7 7/8	Surf. Csg:	\$ -	Rig Move:	\$		
PV/YP:	11/28	#2 PZ-10	3.48GPM	Type:	505ZX	Int. Csg:	\$ -	Day Rate:	\$ 23,000		
Gel:	15/35/41	SPM:	117	MFG:	HTC	Prod Csg:	\$ -	Rental Tools:	\$ 1,600		
WL:	18	GPM :	408	S/N:	7009469	Float Equip:	\$ -	Trucking:	\$ -		
Cake:	2	Press:	1400	Jets:	6X16	Well Head:	\$ -	Water:	\$ -		
Solids:	13	AV DC:	384	TD Out:	12730	TBG/Rods:	\$ -	Fuel:	\$ -		
MBT	15	AV DP:	208	Depth In:	12387	Packers:	\$ -	Mud Logger:	\$ -		
PH :	7.8	JetVel:	111	FTG:	343	Tanks:	\$ -	Logging:	\$ -		
Pf/Mf:	.00/6.60	ECD:	11.74	Hrs:	45	Separator:	\$ -	Cement:	\$ -		
Chlor:	10000	SPR #1 :	40@300	FPH:	7.6	Heater:	\$ -	Bits:	\$ 8,000		
Ca :	20	SPR #2 :	60@650	WOB:	20/28	Pumping L/T:	\$ -	Mud Motors:	\$ -		
Dapp ppb:	4.9	Btm.Up:	57.2	R-RPM:	60/80	Prime Mover:	\$ -	Corrosion:	\$ -		
Time Break Down:			Total D.T.	M-RPM:		Misc:	\$ -	Consultant:	\$ 1,000		
START	END	TIME	36	Total Rot. Hrs:		362.0	Daily Total:	\$ -	Drilling Mud:	\$ 300	
6:00	07:00	1:00	Trip out for logs					Misc. / Labor: \$500			
07:00	15:00	8:00	Logging , 1st run @11722 - tool quit,2nd run @ 12220 - tools quit and bad head on line					Csg. Crew: \$			
								Daily Total: \$34,400			
15:00	19:30	4:30	Trip in hole - pickup pipe --- 6500units ,48 % flow					Cum. Wtr: \$ 18,207			
19:30	20:30	1:00	Circulate up gas					Cum. Fuel \$ 135,833			
20:30	03:00	6:30	Trip in hole - pickup pipe --- 9000 units, about 25 minutes once started					Cum. Bits: \$ 112,750			
			pumping to catch up with gas and pressure					BHA			
03:00	04:00	1:00	Circulate out gas					Bit / bit sub		5.50	
04:00	05:00	1:00	Wash 150' to bottom - no fill							97.00	
05:00	06:00	1:00	Circulate and spot pill to trip for Logs							0.00	
			Sunnyside 12106' -624'					TOTAL BHA = 102.50			
			Spring Canyon 12561' -169'					Survey	2 1/4	10720'	
		24.00	TD	12730'	0'	BOILER	0	Survey			
P/U	275 K#	LITH:	3' on bottom	Centrifuge			BKG GAS	2100			
S/O	268 K#	FLARE:	80/90 ft flare while tripping in and circ	Gas Buster yes			CONN GAS	4273			
ROT.	271 K#	LAST CSG.RAN:	8 5/8"	SET @	3468	PEAK GAS	10000				
FUEL	Used: 900	On Hand:	9,210	Co.Man	RICK FELKER	TRIP GAS					
BIT #	14	ICS	OCS	DC	LOC	B/S	G	ODC	RP		
CONDITION	0	2	ct	s	x	l	cw	td			

Well: Federal 12-30-9-19			Per.Depth 12875		Prog.Depth 12761		DATE 6/13/07		DAYS: 33		
Current: Operations:			Circulating out gas								
Depth: 12730'		Prog:		D Hrs:		AV ROP: 0.0		Formation: Spring Canyon			
DMC: \$700		TMC: \$87,100				TDC: \$46,550		CWC: \$1,934,288			
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids			TANGIBLE COST		INTANGIBLE COST		
MW:	11.3	#1 PZ-10	3.48GPM	Bit #:	14		P	\$ -	Loc,Cost:	\$ -	
VIS:	51	SPM:	0	Size:	7 7/8		Surf. Csg:	\$ -	Rig Move:	\$	
PV/YP:	11/28	#2 PZ-10	3.48GPM	Type:	505ZX		Int. Csg:	\$ -	Day Rate:	\$ 23,000	
Gel:	15/35/41	SPM:	117	MFG:	HTC		Prod Csg:	\$ -	Rental Tools:	\$ 1,600	
WL:	18	GPM :	408	S/N:	7009469		Float Equip:	\$ -	Trucking:	\$ -	
Cake:	2	Press:	1400	Jets:	6X16		Well Head:	\$ -	Water:	\$ 1,950	
Solids:	13	AV DC:	384	TD Out:	12730		TBG/Rods:	\$ -	Fuel:	\$ -	
MBT	15	AV DP:	208	Depth In:	12387		Packers:	\$ -	Mud Logger:	\$ -	
PH :	7.8	JetVel:	111	FTG:	343		Tanks:	\$ -	Logging:	\$ 17,000	
Pt/Mf:	.00/6.60	ECD:	11.74	Hrs:	45		Separator:	\$ -	Cement:	\$ -	
Chlor:	10000	SPR #1 :	40@300	FPH:	7.6		Heater:	\$ -	Bits:	\$ -	
Ca :	20	SPR #2 :	60@650	WOB:	20/28		Pumping L/T:	\$ -	Mud Motors:	\$ -	
Dapp ppb:	4.9	Btm.Up:	57.2	R-RPM:	60/80		Prime Mover:	\$ -	Corrosion:	\$ -	
Time Break Down:			Total D.T.	M-RPM:			Misc:	\$ -	Consultant:	\$ 1,000	
START	END	TIME	36	Total Rot. Hrs:		362.0	Daily Total:	\$ -	Drilling Mud:	\$ 700	
6:00	06:30	:30	CIRCULATE SPOT PILL						Misc. / Labor:	\$1,300	
06:30	11:30	5:00	TRIP OUT FOR LOGS						Csg. Crew:	\$	
11:30	13:00	1:30	WAIT ON LOGGERS						Daily Total:	\$46,550	
13:00	13:30	:30	SAFTEY MEETING W LOGGERS AND CREW						Cum. Wtr:	\$ 18,207	
13:30	23:00	9:30	RIG UP/AND LOG W/ BAKER ATLAS ,LOGS WENT TO 12739						Cum. Fuel	\$ 135,833	
23:00	01:30	2:30	Trip in Hole @ 7000						Cum. Bits:	\$ 112,750	
01:30	03:00	1:30	Install rotating head ,circulate out gas						BHA		
03:00	05:00	2:00	Trip in Hole						Bit / bit sub	5.50	
05:00	06:00	1:00	Circulate out gas 5000 units							97.00	
										0.00	
									</		

[illegible]



GASCO ENERGY

DAILY DRILLING REPORT

AFE # 40129

GPS- N 39° 52.9', W110° 01.40'

Well: Federal 12-30-9-19			Per.Depth 12875		Prog.Depth 12761		DATE 6/15/07		DAYS: 35			
Current: Operations:			RIG DOWN									
Depth: 12730'		Prog:		D Hrs:		AV ROP: 0.0		Formation: Spring Canyon				
DMC: \$0		TMC: \$95,100				TDC: \$417,770		CWC: \$2,433,158				
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST			INTANGIBLE COST			
MW:	11.3	#1 PZ-10	3.48GPM	Bit #:		P	\$ -	Loc, Cost:	\$ -			
VIS:	51	SPM:	0	Size:		Surf. Csg:	\$ -	Rig Move:	\$			
PV/YP:	11/28	#2 PZ-10	3.48GPM	Type:		Int. Csg:	\$ -	Day Rate:	\$ 143,000			
Gel:	15/35/41	SPM:	117	MFG:		Prod Csg:	\$ 208,000	Rental Tools:	\$ 2,000			
WL:	18	GPM:	408	S/N:		Float Equip:	\$ 5,560	Trucking:	\$ -			
Cake:	2	Press:	1400	Jets:		Well Head:	\$ -	Water:	\$ -			
Solids:	13	AV DC:	384	TD Out:		TBG/Rods:	\$ -	Fuel:	\$ -			
MBT	15	AV DP:	208	Depth In:		Packers:	\$ -	Mud Logger:	\$ -			
PH :	7.8	JetVel:	111	FTG:		Tanks:	\$ -	Logging:	\$ -			
P/Mf:	.00/6.60	ECD:	11.74	Hrs:		Separator:		Cement:	\$ 55,510			
Chlor:	10000	SPR #1 :	40@300	FPH:		Heater:	\$ -	Bits:	\$ -			
Ca :	20	SPR #2 :	60@650	WOB:		Pumping L/T:	\$ -	Mud Motors:	\$ -			
Dapp ppb:	4.9	Btm.Up:	57.2	R-RPM:		Prime Mover:	\$ -	Corrosion:	\$ -			
Time Break Down:			Total D.T.		M-RPM:		Misc:		Consultant:			
START	END	TIME	36		Total Rot. Hrs:		362.0	Daily Total:	\$ 213,560		Drilling Mud:	\$ -
6:00	16:00	10:00	Run Casing , 297jts of 4.5 -15.5# p-110 - set @ 12720							Misc. / Labor:		\$700
16:00	17:00	1:00	Circulate gas out							Csg. Crew:		\$
17:00	18:00	1:00	Install landing ring and rotating rubber - tag up							Daily Total:		\$417,770
18:00	20:30	2:30	Circulate ,wait on Schlumberger to get here from Rig 611							Cum. Wtr:		\$ 26,557
20:30	21:00	:30	Saftey meeting w/cementers							Cum. Fuel		\$ 135,833
21:00	01:30	4:30	TEST CMT LINES TO 5000 PSI OK. CMT 4-1/2" PRODUCTION							Cum. Bits:		\$ 112,750
			CSG W/20BBL CW100, 540 SKS HI-LIFT CLASS G + ADDS LEAD							BHA		
			{YIELD=3.04 H2O=18.4 GL/SK @ 11.5 PPG} 286 BBLS. TAIL IN							Bit / bit sub		5.50
			1305 SKS 50/50 POZ G + ADDS {YIELD=1.28 H2O=5.91 GL/SK @									97.00
			14.1 PPG}. DISPLACE TO FLOAT 199 BBLS KCL WATER									0.00
			BUMP PLUG TO 3900 PSI BLEED BACK 3 BBLS & HELD.									
			LAND CSG W/170K OK.									
1:30	2:00	:30	Rig Down Cementers									
2:00	6:00	4:00	Clean pit, Rig Down									
			RIG RELEASED@6:00 AM									
			Sunnyside	12106'	-624'				TOTAL BHA = 102.50			
			Spring Canyon	12561'	-169'				Survey	2 1/4	10720'	
		24.00	TD	12730'	0'	BOILER		0	Survey			
P/U		275 K#	LITH:		Centrifuge				BKG GAS		2100	
S/O		268 K#	FLARE:		60ft flare after trip in				Gas Buster vent		CONN GAS	
ROT.		271 K#	LAST CSG.RAN:		4.5	SET @		12720	PEAK GAS		5000	
FUEL Used:		1500	On Hand:		6,077	Co.Man		RICK FELKER	TRIP GAS			
BIT #	14	ICS	OCS	DC	LOC	B/S	G	ODC	RP			
CONDITION	0		2	ct	s	x	l	cw	td			

[illegible]

Well: Federal 12-30-9-19			Per.Depth 12875	Prog.Depth 12761	DATE 6/18/07	DAYS: 38		
Current: Operations:			Rig Down to move					
Depth: 12730'		Prog:		D Hrs:		AV ROP: 0.0		Formation: Spring Canyon
DMC: \$0		TMC: \$95,100				TDC: \$442,270		CWC: \$2,457,658
Contractor: NABORS 99				Mud Co: M-I Drlg. Fluids		TANGIBLE COST		INTANGIBLE COST
MW:		#1 PZ-10	3.48GPM	Bit #:		P	\$ -	Loc, Cost: \$ -
VIS:		SPM:	0	Size:		Surf. Csg:	\$ -	Rig Move: \$ -
PV/YP:		#2 PZ-10	3.48GPM	Type:		Int. Csg:	\$ -	Day Rate: \$ -
Gel:		SPM:		MFG:		Prod Csg:	\$ -	Rental Tools: \$ 840
WL:		GPM :		S/N:		Float Equip:	\$ -	Trucking: \$ -
Cake:		Press:		Jets:		Well Head:	\$ 4,666	Water: \$ -
Solids:		AV DC:		TD Out:		TBG/Rods:	\$ -	Fuel: \$ -
MBT		AV DP:		Depth In:		Packers:	\$ -	Mud Logger: \$ -
PH :		JetVel:		FTG:		Tanks:	\$ -	Logging: \$ 34,842
Pf/Mf:		ECD:		Hrs:		Separator:		Cement: \$ -
Chlor:		SPR #1 :		FPH:		Heater:	\$ -	Testing \$ 1,370
Ca :		SPR #2 :		WOB:		Pumping L/T:	\$ -	Fishing Costs \$ -
Dapp ppb:		Btm.Up:		R-RPM:		Prime Mover:	\$ -	Welder \$ 1,500
Time Break Down:			Total D.T.	M-RPM:		Misc:	\$ -	Consultant: \$ 1,000
START	END	TIME	36	Total Rot. Hrs:		362.0	Daily Total:	\$ 4,666
6:00			Finish logging , Top of cement was at 1813`					Drilling Mud: \$ -
			Laydown Top Drive,					Misc. / Labor: \$0
			Install Tubing Head and Frac Head					Csg. Crew: \$ -
	6:00	24.00	Pressure up w/ BC Quick Test @8500 psi					Daily Total: \$44,218
								Total Costs
			Rig Starts back on Reduced rate @ 6:00 am - 6/18/07					
								BHA
			Sunnyside 12106' -624'					TOTAL BHA = 0.00
			Spring Canyon 12561' -169'					Survey
		24.00	TD 12730' 0'		BOILER	0	Survey	
P/U 275 K#		LITH:		Centrifuge			BKG GAS	
S/O 268 K#		FLARE: 60ft flare after trip in		Gas Buster			CONN GAS	
ROT. 271 K#		LAST CSG.RAN: 4.5		SET @ 12720			PEAK GAS	
FUEL Used: 500		On Hand: 55,077		Co.Man RICK FELKER		TRIP GAS		
BIT #	ICS	OCS	DC	LOC	B/S	G	ODC	RP
CONDITION								

CONFIDENTIAL

43-047-37613

30 95 19e

September 17, 2007

State of Utah
Division of Oil, Gas, and Mining
1594 West Temple North Suite 1210
Salt Lake City, Utah 84114-5801


Re: Well Information - FEDERAL 12-30-9-19

Enclosed with this letter are Mudlogs, and an Evaluation for the FEDERAL 12-30-9-19 well. The following copies are included, as per your instructions:

<i>Description</i>	<i>Copies</i>
Mudlog (1" MD)	1

I would like to take this opportunity to thank you for the confidence you have shown in our organization by allowing us to assist you on these important projects. If I can be of any future assistance, please do not hesitate to call me at your convenience.

Most sincerely,



Kevin Romey
Gulf Coast DML Manager
337-364-2322 - Office
337-519-8428 - Cellular

RECEIVED

SEP 18 2007

DIV. OF OIL, GAS & MINING

NOTICE

Utah Oil and Gas Conservation General Rule R649-3-21 states that,

- A well is considered completed when the well has been adequately worked to be capable of producing oil or gas or when well testing as required by the division is concluded.
- Within 30 days after the completion or plugging of a well, the following shall be filed:
 - Form 8, Well Completion or Recompletion Report and Log
 - A copy of electric and radioactivity logs, if run
 - A copy of drillstem test reports,
 - A copy of formation water analyses, porosity, permeability or fluid saturation determinations
 - A copy of core analyses, and lithologic logs or sample descriptions if compiled
 - A copy of directional, deviation, and/or measurement-while-drilling survey for each horizontal well

Failure to submit reports in a timely manner will result in the issuance of a Notice of Violation by the Division of Oil, Gas and Mining, and may result in the Division pursuing enforcement action as outlined in Rule R649-10, Administrative Procedures, and Section 40-6-11 of the Utah Code.

As of the mailing of this notice, the division has not received the required reports for

Operator: Gasco Production Company

Today's Date: 09/18/2007

Well:	API Number:	Drilling Commenced:
Federal 14-31-9-19 wcr	4304736271	01/11/2007
Wilkin Ridge Fed 14-4-11-17 wcr	4301333099	02/10/2007
Wilkin Ridge Fed 43-29-10-17 drlg/wcr	4301333098	02/20/2007
Federal 12-1-10-18 wcr	4304737646	03/21/2007
Federal 12-30-9-19 drlg/wcr	4304737613	04/18/2007
Gate Cyn ST 23-16-11-15 drlg/wcr	4301332685	04/25/2007
Sheep Wash Fed 14-25-9-18 wcr	4304737647	05/03/2007
Federal 32-20-9-19 drlg/wcr	4304736094	05/10/2007

To avoid compliance action, required reports should be mailed within 7 business days to:

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

If you have questions or concerns regarding this matter, please call (801) 538-5284.

cc: Well File
Compliance File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS
*Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.*

SUBMIT IN TRIPLICATE - Other Instructions on reverse side.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	
2. Name of Operator Gasco Production Company	
3a. Address 8 Inverness Drive East Ste 100 Englewood, Co 80112	3b. Phone No. (include area code) 303-483-0044
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) SW NW of Section 30-T9S-R19E 2084' FNL & 716' FWL	

5. Lease Serial No. U-37246
6. If Indian, Allottee, or Tribe Name NA
7. If Unit or CA, Agreement Name and/or No. NA
8. Well Name and No. Federal 12-30-9-19
9. API Well No. 43-047-37613
10. Field and Pool, or Exploratory Area Riverbend
11. County or Parish, State Uintah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/ Resume)	<input type="checkbox"/> Water Shut-off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and abandon	<input type="checkbox"/> Temporarily Abandon	EFM Meter
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

This sundry is being sent to inform you that we will be using a Ferguson Beauregard EFM (Model 3500) to measure production from this well and will be considered as the point of sale for gas produced from this well. A temperature probe has been installed for gas measurement purposes. This unit does have a digital readout display and will be inspected and proved according to all BLM regulations.

COPY SENT TO OPERATOR
DATE: 10-24-07
INITIALS: RM

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

14. I hereby certify that the foregoing is true and correct.
Name (Printed Typed)

Beverly Walker

Signature

Beverly Walker

Title

Engineering Technician

Date

October 2, 2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED
OCT 16 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: November 30, 2000

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

CONFIDENTIAL

Lease Serial No.

U-37246

1a. Type of Well ☐ Oil Well ☒ Gas ☐ Dry Other
b. Type of Completion: ☒ New ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.
Other _____

2. Name of Operator
Gasco Production Company

3. Address 3a. Phone No. (include area code)
8 Inverness Drive East Suite 100, Englewood, Colorado 80112 303-183-0044

4. Location of Well (Report locations clearly and in accordance with Federal requirements) *
SW 1/4 of Section 30, T9S R19E 20X E 1/4 & 716' FWL

At top prod. interval reported below same
At total depth same

14. Date Spudded 05/12/07 15. Date T.D. Reached 06/10/07 16. Date Completed 4/2 ☐ D & A ☒ Ready to Prod.

6. If Indian, Allottee or Tribe Name NA
7. Unit or CA Agreement Name and No. NA
8. Lease Name and Well No. Federal 12-30-9-19
9. API Well No. 43-047-37613
10. Field and Pool, or Exploratory Riverbend
11. Sec., T., R., M., or Block and Survey or Area Sec 30 T9S R19E
12. County or Parish Uinta 13. State Utah
17. Elevations (DF, RKB, RT, GL)* GL: 4781; RKB: 4808

18. Total Depth MD 12730 TVD 12730 19. Plug Back T.D.: MD TVD 20. Depth Bridge Plug Set: MD NA TVD NA

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
CBL, DNL, GR, Cal, CCL HDI, Comp 2, CD, CN, PP

22. Was well ☒ No ☐ Yes (Submit copy)
Was DST run? ☒ No ☐ Yes (Submit copy)
Directional ☒ No ☐ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL.)	Cement Top*	Amount Pulled
17 1/2"	13 3/8 H40	48#	0	218		225 sx Premium		Circ to Surf	
12 1/4"	8 5/8 J-55	32#	0	3468		626 sx Class G		Circ to Surf	
						455 Class G			
7 7/8"	4 1/2 P110	13.5#	0	12720		540 sx HiLift G		1813	
						1305 sx 50/50 Poz G			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Set (MD)

25. Producing Intervals

Formation	Top	Bottom
A) Blackhawk	11905	12600
B) Mesaverde	9414	11626
C) Dark Canyon	9153	9414
D) Wasatch	5323	9153
E)		

26. Perforation Record

Perforated Interval	Size	No. Holes	Perf. Status
See Attached			

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and type of Material
See Attached	

RECEIVED
NOV 30 2007
DIV. OF OIL, GAS & MINING

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL.	Gas MCF	Water BBL.	Oil Gravity Corr. API	Gas Gravity	Production Method
09/30/07	10/01/07	24	→	0	2,132	262			Flowing

Choke Size 12/64 Tbg Press Flwg SI 2632 24 Hr Rate → Oil BBL. 0 Gas MCF 2,132 Water BBL. 262 Oil Gravity Corr. API Well Status Producing from A

28a.

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL.	Gas MCF	Water BBL.	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						

Choke Size Tbg Press Flwg SI 24 Hr Rate → Oil BBL. Gas MCF Water BBL. Oil Gravity Corr. API Well Status

(See instructions and spaces for additional data on reverse side)

28b.

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL.	Gas MCF	Water BBL.	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg SI	Csg. Press	24 Hr. Rate →	Oil BBL.	Gas MCF	Water BBL.	Gas - Oil Ratio	Well Status	

28c. Production - Interval E

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL.	Gas MCF	Water BBL.	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg SI	Csg. Press	24 Hr. Rate →	Oil BBL.	Gas MCF	Water BBL.	Gas - Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

Sold

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
Wasatch	5,323	9,153			
Dark Canyon	9,153	9,414			
Mesaverde	9,414	11,626			
Blackhawk	11,905	12,600	TD'd in the Blackhawk		

32. Additional remarks (include plugging procedure):

33. Circle enclosed attachments:

1. Electrical/Mechanical Logs (1 full set req'd.) 2. Geologic Report 3. DST Report 4. Directional Survey
5. Sundry Notice for plugging and cement verification 5. Core Analysis 7. Other

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Matt OwensTitle Petroleum EngineerSignature Date 11/21/07

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Federal 12-30-9-19
Additional Information to Well Completion Report

27. Perforation Record

Perforated Interval	Size	No. Hole	Perf. Status
12574-82	0.38	24	Open
	0.38		Open
	0.38		Open
	0.38		Open

28. Acid Fracture, Treatment, Cement Squeeze, Etc (continued)

Depth Interval	Amount and Type of Material
12574-82	Fraced Stage 1 w/ 3,000# 100 mesh and 114,300# 20/40 VersaProp using 106,790 gal of 15# & 20# Hybor Gel

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS
*Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.*

SUBMIT IN TRIPLICATE - Other Instructions on reverse side.

1. Type of Well

☐

Oil Well

☒

Gas Well

☐

Other

2. Name of Operator

Gasco Production Company

3a. Address

8 Inverness Drive East Ste 100 Englewood, Co 80112

3b. Phone No. (include area code)

303-483-0044

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SW NW of Section 30-T9S-R19E 2084' FNL & 716' FWL

5. Lease Serial No.

U-37246

6. If Indian, Allottee, or Tribe Name

NA

7. If Unit or CA. Agreement Name and/or No.

NA

8. Well Name and No.

Federal 12-30-9-19

9. API Well No.

43-047-37613

10. Field and Pool, or Exploratory Area

Riverbend

11. County or Parish, State

Uintah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☒ Notice of Intent

☐ Acidize

☐ Deepen

☐ Production (Start/ Resume)

☐ Water Shut-off

☐ Altering Casing

☐ Fracture Treat

☐ Reclamation

☐ Well Integrity

☐ Subsequent Report

☐ Casing Repair

☐ New Construction

☐ Recomplete

☒ Other Site Security

☐ Change Plans

☐ Plug and abandon

☐ Temporarily Abandon

☐ Final Abandonment Notice

☐ Convert to Injection

☐ Plug back

☐ Water Disposal

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Please find attached a copy of the site security diagram for this well.

RECEIVED

DEC 15 2008

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.

Name (Printed/ Typed)

Jessica Berg

Title

Production Clerk

Signature

Jessica Berg

Date

December 11, 2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title


Date

Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

Not To Scale



Note: This Site Security Plan is on file at the Gasco Field Office.

POSITION OF VALVES AND USE OF SEALS DURING PRODUCTION

VALVES	LINE PURPOSE	POSITION	SEAL INSTALLED
D	Drain	Closed	Yes
F	Oil, Gas, Water	Open	No
O	Overflow	Open/Closed	No
V	Vent	Open	No
R	Recycle	Closed	Yes
H	Heat	Open	No
S	Sales	Closed	Yes

POSITION OF VALVES AND USE OF SEALS DURING SALES

VALVES	LINE PURPOSE	POSITION	SEAL INSTALLED
D	Drain	Closed	Yes
F	Oil, Gas, Water	Closed	Yes
O	Overflow	Closed	Yes
V	Vent	Open	No
R	Recycle	Closed	Yes
H	Heat	Closed	No
S	Sales	Open	No

POSITION OF VALVES AND USE OF SEALS DURING WATER DRAIN

VALVES	LINE PURPOSE	POSITION	SEAL INSTALLED
D	Drain	Open	No
F	Oil, Gas, Water	Closed	No
O	Overflow	Closed	No
V	Vent	Open	No
R	Recycle	Closed	Yes
H	Heat	Closed	No
S	Sales	Closed	Yes



LEGEND

- D - Drain Valve
- F - Flow Valve
- O - Overflow
- V - Vent
- R - Recycle
- H - Heat Trace
- S - Sales Valve

BUYS & ASSOCIATES, INC.
ENVIRONMENTAL CONSULTANTS

Gasco Production Company

Federal # 12-30-9-19

Lease UTU # 37246

SW/NW Sec. 30 T9S R19E

Uintah County, Utah

October 2008

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side.


1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-37246
2. Name of Operator Gasco Production Company		6. If Indian, Allottee, or Tribe Name NA
3a. Address 8 Inverness Drive East Ste 100 Englewood, Co 80112	3b. Phone No. (include area code) 303-483-0044	7. If Unit or CA. Agreement Name and/or No. NA
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) SW NW of Section 30-T9S-R19E 2084' FNL & 716' FWL		8. Well Name and No. Federal 12-30-9-19
		9. API Well No. 43-047-37613
		10. Field and Pool, or Exploratory Area Riverbend
		11. County or Parish, State Uintah County, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/ Resume)	<input type="checkbox"/> Water Shut-off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Run tubing</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Gasco landed 361 joints of 2 3/8" 4.7# N-80 tubing with a 1.875" x-nipple on bottom @ 11,993' on 4/18/09.

14. I hereby certify that the foregoing is true and correct.	
Name (Printed/ Typed) Matt Owens	Title Petroleum Engineer
Signature 	Date May 12, 2009

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

MAY 18 2009

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-37246
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
		7. UNIT OR CA AGREEMENT NAME: NA
		8. WELL NAME and NUMBER: Federal 12-30-9-19
1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	9. API NUMBER: 4304737613	10. FIELD AND POOL, OR WILDCAT: Riverbend
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		
3. ADDRESS OF OPERATOR: 8 INVERNESS DR E, #100 ENGLEWOOD CO 80112		PHONE NUMBER: (303) 483-0044

4. LOCATION OF WELL

FOOTAGES AT SURFACE: **2084' FNL & 716' FWL**

COUNTY: **Uintah**

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: **SWNW 30 9S 19E**

STATE: **UTAH**

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 4/15/2009	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input checked="" type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Gasco intends to run 2 3/8" tubing into this well in order to enhance current production. The well has been flowing up 4 1/2" casing since completion and liquid loading is suspected to be hampering potential production. Landing 2 3/8" tubing down near the producing formations will dramatically reduce the flow rate necessary to avoid any liquid lading problems.

Also, landing tubing in the wellbore will allow Gasco to pump a combination foamer/scale inhibitor chemical down the annulus. This will prevent any scaling tendencies from commingled waters as well as greatly lower the specific gravity of the produced water, thus helping the well unload and flow at a more stable rate up the tubing.

(Rec'd after work completed HDM)

RECEIVED

JUL 17 2009

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) **Matt Owens**

TITLE **Petroleum Engineer**

SIGNATURE *Matt Owens*

DATE **7/17/2009**

(This space for State use only)

2/15/08 Updated late costs: (JD) DC \$6,500 CC \$3,135,396

3/12/08 Updated late costs: (PME) DC \$99,968 CC \$3,235,164

3/17/08 Updated late costs: (PME) DC \$99 CC \$3,235,263

5/23/08 Updated costs: (PME) DC \$7,981 CC \$2,861,447

7/9/08 Wellhead Inc Frac Tree Rental (PME) DC \$2,336 CC \$2,863,783

7/10/08 Location clean up (PME) DC \$48 CC \$2,863,831

8/5/08 Late Costs for Huffman clean up and fix fence , Frac Tree Rental for 7/16/08 to 8/16/08 (PME) DC \$3,591 CC \$2,867,422

4/9/09 MT made out for 12,005' tbg, + 63.5' thread loss, 12,068.5' sell amount. (landing depth.) Will have to adjust when RIH. (JD) DC \$101,026 CC \$2,968,820

4/15/09 Move service unit to location. During pre rigup inspection, fd that crown shieve was cracked and had to be replaced. Will continue when rig is repaired. SDFD. (JD) (PME) DC \$6,543 CC \$2,981,662


4/17/09 Replace crown shieve. Rig up service unit. Pump 80 bbls dn casing, well on a suck. ND 4" 10k Frac tree. NU BOP. Talley, pick up and RIH w/1.875 X-nipple w/brass press in plug in bottom of nipple+2 3/8" N-80 EUE 8 rnd tbg. Well started to flow. Leave EOT @ 7,613 w/230 joints tbg. Turn well over to sales for night. (JD) (PME) DC \$4,519 CC \$2,986,181


4/18/09 Fd 500 fcp. 0 sitp. Finish RIH w/tbg. Land tbg @ 11,993' w/361 joints tbg. ND BOP, NU production tree. Pump 20 bbls dn tbg. Eqaulize tbg to csg for night. Rig down service unit. SDFD. (JD)

4/24/09 Fd 300 sicp and 0 sitp. plug in x-nipple has not came off. Rig up pump and pump 15 bbls dn tbg to equal full tbg vol. tbg pressured up to 800 psi and then went on a suck, indicating that plug had came off. Leave well to equalize tbg to csg. SDFD.(JD) (PME) DC \$1,473 CC \$2,987,654

4/25/09 Fd 300 stip, 300 sicp. Rig up rig to swab. RIH w/ swab. Make 1 run and lost swab mandrel in well. Rig up w/3/4" short catch over shot and RIH. Catch swab mandrel where it fell off sand line. RIH again w/swab. Make 3 runs and recover 30 bbls, well started to flow up tbg. Leave rig standing for weekend. Leave well to sales up tbg. SDFD. (JD) (PME) DC \$4,053 CC \$2,991,707

4/30/09	Restroom rental, supervision (PME) DC \$887 CC \$2,992,594
7/1/09	Hydril Rubber for repairing BOP's (PME) DC \$715 CC \$2,993,309

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-37246			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		8. WELL NAME and NUMBER: FEDERAL 12-30-9-19			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2084 FNL 0716 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 30 Township: 09.0S Range: 19.0E Meridian: S		9. API NUMBER: 43047376130000			
PHONE NUMBER: 303 483-0044 Ext		9. FIELD and POOL or WILDCAT: PARIETTE BENCH			
COUNTY: UTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/15/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____ </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco intends to recomplete all remaining productive intervals in the Mesaverde formation with approximately 6 frac stages. Each stage will utilize roughly 1,500 barrels of water and 60,000 lbs of sand. A subsequent report outlining the work done will be submitted shortly after operations have ceased.					
Accepted by the Utah Division of Oil, Gas and Mining Date: June 22, 2010 By: 		TITLE Petroleum Engineer			
NAME (PLEASE PRINT) Matt Owens		PHONE NUMBER 303 996-1839			
SIGNATURE N/A		DATE 6/16/2010			

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-37246			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		8. WELL NAME and NUMBER: FEDERAL 12-30-9-19			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2084 FNL 0716 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 30 Township: 09.0S Range: 19.0E Meridian: S		9. API NUMBER: 43047376130000			
PHONE NUMBER: 303 483-0044 Ext		9. FIELD and POOL or WILDCAT: PARIETTE BENCH			
COUNTY: UTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/15/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____ </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: _____			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco intends to recomplete all remaining productive intervals in the Mesaverde formation with approximately 6 frac stages. Each stage will utilize roughly 1,500 barrels of water and 60,000 lbs of sand. A subsequent report outlining the work done will be submitted shortly after operations have ceased.					
Accepted by the Utah Division of Oil, Gas and Mining Date: June 22, 2010 By: 					
NAME (PLEASE PRINT) Matt Owens		PHONE NUMBER 303 996-1839			
SIGNATURE N/A		TITLE Petroleum Engineer			
		DATE 6/16/2010			

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-37246
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		8. WELL NAME and NUMBER: FEDERAL 12-30-9-19
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2084 FNL 0716 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 30 Township: 09.0S Range: 19.0E Meridian: S		9. API NUMBER: 43047376130000
PHONE NUMBER: 303 483-0044 Ext		9. FIELD and POOL or WILDCAT: PARIETTE BENCH
COUNTY: UTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/15/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input checked="" type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Gasco would like to dispose of water at LaPoint Recycle & Storage state approved commercial disposal facility located in Section 12 Township 5 south Range 19 west in LaPoint UT. This facility would be used in addition to the currently approved disposal facilities that Gasco uses to dispose of water from this well.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 October 11, 2010

NAME (PLEASE PRINT) Roger Knight	PHONE NUMBER 303 996-1803	TITLE EHS Supervisor
SIGNATURE N/A		DATE 10/8/2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-37246
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100 , Englewood, CO, 80112		8. WELL NAME and NUMBER: FEDERAL 12-30-9-19
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2084 FNL 0716 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 30 Township: 09.0S Range: 19.0E Meridian: S		9. API NUMBER: 43047376130000
PHONE NUMBER: 303 483-0044 Ext		9. FIELD and POOL or WILDCAT: PARIETTE BENCH
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 1/7/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input checked="" type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Gasco would like to dispose of water at Integrated Water management, LLC state approved commercial disposal facility located in Section 30, 2 south Range 4 west in North Blue Bench UT. This facility would be used in addition to the currently approved disposal facilities that Gasco uses to dispose of water from this well.

NAME (PLEASE PRINT) Roger Knight	PHONE NUMBER 303 996-1803	TITLE EHS Supervisor
SIGNATURE N/A		DATE 12/30/2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-37246
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		8. WELL NAME and NUMBER: FEDERAL 12-30-9-19
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2084 FNL 0716 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 30 Township: 09.0S Range: 19.0E Meridian: S		9. API NUMBER: 43047376130000
PHONE NUMBER: 303 483-0044 Ext		9. FIELD and POOL or WILDCAT: PARIETTE BENCH
COUNTY: UTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/17/2011			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Gasco has completed fracture treating the 6 remaining productive intervals in the Mesaverde formation. The volumes of sand and water pumped in each stage can be found on the attached wellbore schematic under stages 2-7. Plugs have been drilled and a PL was ran. Gasco is currently waiting on workover rig to become available to lower tubing and install a capstring in the wellbore at which time recompletion operations will be complete.

NAME (PLEASE PRINT) Jessica Berg	PHONE NUMBER 303 996-1805	TITLE Production Clerk
SIGNATURE N/A		DATE 1/13/2011

As of 9/27/2010

LEASE: U-37246 WELL #: Federal 12-30-9-19
 FIELD: Riverbend
 LOCATION: SWNW Section 30 9S 19E
 COUNTY: Uintah ST: Utah API: 43-047-37613

GL: 4781
 SPUD DATE: 5/12/2007
 COMP DATE: 9/27/2007

CONDUCTOR

SIZE: 13 3/8"
 WT/GRD: H-40
 WT/GRD: 48#
 CSA: 218
 SX: 225 sx Premium
 CIRC: Y
 TOC: Surf
 HOLE SIZE: 17 1/2"

SURFACE CASING

SIZE: 8 5/8"
 WT/GRD: J-55
 WT/GRD: 32#
 CSA: 3,468
 SX: 1081 sx Class G
 CIRC: Y
 TOC: Surf
 HOLE SIZE: 12 1/4"

PRODUCTION CASING

SIZE: 4 1/2"
 WT/GRD: P110
 WT/GRD: 13.5#
 CSA: 12,720
 SX: 540 sx Hi-Lift G
 1305 50/50 Pos G
 CIRC: Y
 TOC: Inside Surf
 HOLE SIZE: 1813

DATE FIRST PRODUCED 9/30/07
 PRODUCTION METHOD Flow
 CHOKE SIZE 12/64
 Csg PRESSURE 2632
 OIL (BBL) 0
 GAS (MCF) 2132
 WATER (BBL) 262

274 jts 2 3/8" 4.7# N-80 tbg w/ nipple
 landed @ 9,093' (9/15/2010)

Stimulation

Stage 7: 8/11/2010 Frac w/ 1,281# 100 mesh sand, 44,363# 30/50 white sand, 7,665# resin coated sand using 982 bbls FR slick water

Stage 6: 8/10/2010 Frac w/ 1,428# 100 mesh, 50,306# 30/50 white sand, 9,555# 30/50 resin coated sand using 1,136 bbls FR slick water

Stage 5: 8/10/2010 Frac w/ 1,743# 100 mesh, 62,418# 30/50 white sand, 11,025# 30/50 resin coated sand using 1,399 bbls FR slick water

Stage 4: 8/10/2010 Frac w/ 1,638# 100 mesh, 56,181# 30/50 white sand, 9,240# 30/50 resin coated sand using 1,298 bbls FR slick water

Stage 3: 8/10/2010 Frac w/ 1,869# 100 mesh, 66,434# 30/50 white sand, 11,550# 30/50 resin coated sand using 1,494 bbls FR slick water

Stage 2: 8/10/2010 Frac w/ 1,512# 100 mesh, 56,658# 30/50 white sand, 10,500# 30/50 resin coated sand using 1,569 bbls FR slick water

Stage 1: 9/29/2007 Fraced Stage 1 w/ 3,000# 100 mesh and 114,300# 20/40 VersaProp using 106,790 gal of 15# & 20# Hybor Gel. Problems in frac job.

Landed @ 9093'

Stage 7 9202-06 FORMATION = Dark Canyon
 9242-44
 9396-400

Stage 6 10134-42 FORMATION = Upper Mesaverde

Stage 5 10839-42 FORMATION = Lower Mesaverde
 10859-63
 10955-58

Stage 4 11035-37 FORMATION = Lower Mesaverde
 11091-93
 11131-33
 11176-80

Stage 3 11410-12 FORMATION = Lower Mesaverde
 11501-03
 11549-51
 11596-600

Stage 2 11954-57 FORMATION = Desert / Grassy
 11979-82
 11990-93
 12046-48

Stage 1 12574-82 FORMATION = Spring Canyon

3-5/8" Smill mill x POBS (9/14/2010)

Revised By	Date
KTM	11/12/2010

MD 12,730
 TD 12,730

PBTD @ 12,580' (tagged fill) (9/27/10)

RECEIVED January 13, 2011

Effective Date: 4/16/2015

FORMER OPERATOR:	NEW OPERATOR:
Gasco Production Company N2575 7979 E. Tufts Avenue, Suite 11500 Denver, CO 80237 303-996-1805	Badlands Production Company N4265 7979 E. Tufts Avenue, Suite 11500 Denver, CO 80237 303-996-1805
CA Number(s):	Unit(s): Gate Canyon, Wilkin Ridge Deep, RBU-EOR-GRRV

WELL INFORMATION:

Well Name	Sec	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
See Attached List									

OPERATOR CHANGES DOCUMENTATION:

1. Sundry or legal documentation was received from the **FORMER** operator on: 6/2/2015
2. Sundry or legal documentation was received from the **NEW** operator on: 6/2/2015
3. New operator Division of Corporations Business Number: 1454161-0143

REVIEW:

1. Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: 6/2/2015
2. Receipt of Acceptance of Drilling Procedures for APD on: N/A
3. Reports current for Production/Disposition & Sundries: 6/3/2015
4. OPS/SI/TA well(s) reviewed for full cost bonding: 1/20/2016
5. UIC5 on all disposal/injection/storage well(s) approved on: N/A
6. Surface Facility(s) included in operator change: None
7. Inspections of PA state/fee well sites complete on (only upon operators request): N/A

NEW OPERATOR BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: SUR0027842
2. Indian well(s) covered by Bond Number: N/A
3. State/fee well(s) covered by Bond Number(s): SUR0027845
SUR0035619 -FCB

DATA ENTRY:

1. Well(s) update in the **OGIS** on: 1/22/2016
2. Entity Number(s) updated in **OGIS** on: 1/22/2016
3. Unit(s) operator number update in **OGIS** on: 1/22/2016
4. Surface Facilities update in **OGIS** on: N/A
5. State/Fee well(s) attached to bond(s) in **RBDMS** on: 1/22/2016
6. Surface Facilities update in **RBDMS** on: N/A

LEASE INTEREST OWNER NOTIFICATION:

1. The **NEW** operator of the Fee (Mineral) wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 1/22/2016

COMMENTS:

From: Gasco Production Company
To: Badlands Production Company
Effective Date: 4/16/2015

Well Name	Section	TWN	RNG	API Number	Entity	Mineral	Surface	Type	Status
FEDERAL 23-18G-9-19	18	090S	190E	4304752496		Federal	Federal	OW	APD
FEDERAL 14-17G-9-19	17	090S	190E	4304752522		Federal	Federal	OW	APD
FEDERAL 13-18G-9-19	18	090S	190E	4304752538		Federal	Federal	OW	APD
FEDERAL 23-29G-9-19	29	090S	190E	4304752544		Federal	Federal	OW	APD
FEDERAL 24-20G-9-19	20	090S	190E	4304752545		Federal	Federal	OW	APD
FEDERAL 31-21G-9-19	21	090S	190E	4304752546		Federal	Federal	OW	APD
Federal 323-29-9-19	29	090S	190E	4304753026		Federal	Federal	GW	APD
Federal 421-29-9-19	29	090S	190E	4304753027		Federal	Federal	GW	APD
Federal 322-29-9-19	29	090S	190E	4304753029		Federal	Federal	GW	APD
Federal 431-29-9-19	29	090S	190E	4304753030		Federal	Federal	GW	APD
Federal 432-29-9-19	29	090S	190E	4304753031		Federal	Federal	GW	APD
Federal 414-29-9-19	29	090S	190E	4304753070		Federal	Federal	GW	APD
FEDERAL 412-29-9-19	29	090S	190E	4304753073		Federal	Federal	GW	APD
FEDERAL 213-29-9-19	29	090S	190E	4304753076		Federal	Federal	GW	APD
federal 321-29-9-19	29	090S	190E	4304753078		Federal	Federal	GW	APD
FEDERAL 213-29-9-19	29	090S	190E	4304753079		Federal	Federal	GW	APD
FEDERAL 321-29-9-19	29	090S	190E	4304753080		Federal	Federal	GW	APD
Federal 212-29-9-19	29	090S	190E	4304753133		Federal	Federal	GW	APD
State 321-32-9-19	32	090S	190E	4304754479		State	State	GW	APD
State 423-32-9-19	32	090S	190E	4304754480		State	State	GW	APD
State 421-32-9-19	32	090S	190E	4304754481		State	State	GW	APD
State 413-32-9-19	32	090S	190E	4304754482		State	State	GW	APD
State 323-32-9-19	32	090S	190E	4304754483		State	State	GW	APD
State 431-32-9-19	32	090S	190E	4304754529		State	State	GW	APD
Desert Spring State 224-36-9-18	36	090S	180E	4304754541		State	State	GW	APD
Desert Spring State 243-36-9-18	36	090S	180E	4304754542		State	State	GW	APD
Desert Spring State 241-36-9-18	36	090S	180E	4304754543		State	State	GW	APD
FEDERAL 332-30-9-19	30	090S	190E	4304753012	19650	Federal	Federal	GW	DRL
WILKIN RIDGE FED 43-29-10-17	29	100S	170E	4301333098	15941	Federal	Federal	GW	OPS
LAMB TRUST 11-23-9-19	23	090S	190E	4304736915	16556	Fee	Fee	GW	OPS
SHEEP WASH FED 43-26-9-18	26	090S	180E	4304738573	17201	Federal	Federal	GW	OPS
FEDERAL 13-19-9-19	19	090S	190E	4304739777	18344	Federal	Federal	GW	OPS
FEDERAL 12-17-9-19	17	090S	190E	4304739800	17202	Federal	Federal	GW	OPS
GATE CYN 31-21-11-15	21	110S	150E	4301332391	13787	State	State	GW	P
WILKIN RIDGE ST 12-32-10-17	32	100S	170E	4301332447	14033	State	State	GW	P
GATE CYN 41-20-11-15	20	110S	150E	4301332475	14417	State	State	GW	P
WILKIN RIDGE FED 34-17-10-17	17	100S	170E	4301332560	14726	Federal	Federal	GW	P
GATE CYN 41-19-11-16	19	110S	160E	4301332611	14439	Federal	Federal	GW	P
WILKIN RIDGE ST 44-32-10-17	32	100S	170E	4301332619	15649	State	State	GW	P
WILKIN RIDGE FED 12-4-11-17	4	110S	170E	4301332674	15537	Federal	Federal	GW	P
WILKIN RIDGE ST 24-32-10-17	32	100S	170E	4301332676	15242	State	State	GW	P
WILKIN RIDGE FED 23-29-10-17	29	100S	170E	4301332679	14033	Federal	Federal	GW	P
GATE CYN ST 23-16-11-15	16	110S	150E	4301332685	16082	State	State	GW	P
WILKIN RIDGE ST 34-16-10-17	16	100S	170E	4301332730	15243	State	State	GW	P
WILKIN RIDGE FED 31-29-10-17	29	100S	170E	4301332773	15370	Federal	Federal	GW	P
WILKIN RIDGE 32-08	8	110S	170E	4301332778	14802	Federal	Federal	GW	P
GATE CYN ST 23-16-11-16	16	110S	160E	4301332888	15098	State	State	GW	P
WILKIN RIDGE FED 24-20-10-17	20	100S	170E	4301333081	15714	Federal	Federal	GW	P
WILKIN RIDGE FED 32-20-10-17	20	100S	170E	4301333087	15807	Federal	Federal	GW	P
WILKIN RIDGE FED 14-4-11-17	4	110S	170E	4301333099	15920	Federal	Federal	GW	P
RYE PATCH FED 22-21	22	110S	140E	4301333437	16919	Federal	Federal	GW	P
RYE PATCH FED 24-21	24	110S	140E	4301333443	16367	Federal	Federal	GW	P
SQUAW CROSSING U 5	2	100S	180E	4304730129	16266	State	State	OW	P
RBV 5-11D	11	100S	180E	4304730409	9005	Federal	Federal	OW	P
FEDERAL 7-25A	25	090S	180E	4304730624	9030	Federal	Federal	OW	P

From: Gasco Production Company
To: Badlands Production Company
Effective Date: 4/16/2015

RBU 6-2D	2	100S	180E	4304731190	7075	State	State	OW	P
NGC 33-18J	18	090S	190E	4304731200	6155	Federal	Federal	OW	P
RBU 13-2D	2	100S	180E	4304731280	16267	State	State	OW	P
RBU 16-3D	3	100S	180E	4304731352	16268	Federal	Federal	OW	P
RBU 10-11D	11	100S	180E	4304731357	7053	Federal	Federal	OW	P
RBU 8-10D	10	100S	180E	4304731364	4955	Federal	Federal	OW	P
RBU 15-3D	3	100S	180E	4304731539	9965	Federal	Federal	OW	P
RBU 12-12D	12	100S	180E	4304731651	10688	Federal	Federal	OW	P
RBU 2-10D	10	100S	180E	4304731801	10784	Federal	Federal	OW	P
RBU 3-15D	15	100S	180E	4304733600	13213	Federal	Federal	OW	P
RBU 3-12D	12	100S	180E	4304733739	14492	Federal	Federal	OW	P
STATE 7-36A	36	090S	180E	4304733741	14244	State	State	GW	P
FEDERAL 34-29	29	090S	190E	4304733750	13174	Federal	Federal	GW	P
FEDERAL 24-7 #1	7	100S	180E	4304733983	13182	Federal	Federal	GW	P
FEDERAL 23-29 #1	29	090S	190E	4304734111	13441	Federal	Federal	GW	P
FED 24-20-9-19	20	090S	190E	4304734168	14150	Federal	Federal	GW	P
FED 44-20-9-19	20	090S	190E	4304734169	14140	Federal	Federal	GW	P
FED 23-21-9-19	21	090S	190E	4304734199	13601	Federal	Federal	GW	P
FED 32-31-9-19	31	090S	190E	4304734201	13641	Federal	Federal	GW	P
FED 42-29-9-19	29	090S	190E	4304734202	13455	Federal	Federal	GW	P
PETES WASH 23-12 #1	12	100S	170E	4304734286	13492	Federal	Federal	GW	P
STATE 4-32B	32	090S	190E	4304734314	14440	State	State	GW	P
FED 14-18-2 #1	18	100S	180E	4304734539	13491	Federal	Federal	GW	P
FED 43-24-3 #1	24	100S	170E	4304734551	13726	Federal	Federal	GW	P
LYTHAM FED 22-22-9-19	22	090S	190E	4304734607	13640	Federal	Federal	GW	P
FED 11-21-9-19	21	090S	190E	4304734608	14151	Federal	Federal	GW	P
FED 22-30-10-18	30	100S	180E	4304734924	14280	Federal	Federal	GW	P
FEDERAL 43-30-9-19	30	090S	190E	4304735343	14202	Federal	Federal	GW	P
FED 11-22-9-19	22	090S	190E	4304735404	14203	Federal	Federal	GW	P
FED 42-21-9-19	21	090S	190E	4304735405	14928	Federal	Federal	GW	P
STATE 24-16-9-19	16	090S	190E	4304735588	14418	State	Federal	GW	P
FEDERAL 31-21-9-19	21	090S	190E	4304735606	14441	Federal	Federal	GW	P
FEDERAL 12-29-9-19	29	090S	190E	4304735614	14442	Federal	Federal	GW	P
FEDERAL 24-31-9-19	31	090S	190E	4304735623	14640	Federal	Federal	GW	P
FEDERAL 41-31-9-19	31	090S	190E	4304735624	14419	Federal	Federal	GW	P
LAMB TRUST 24-22-9-19	22	090S	190E	4304735732	14496	Fee	Fee	GW	P
LAMB TRUST 24-14-9-19	14	090S	190E	4304735733	14519	Fee	Fee	GW	P
FEDERAL 11-22-10-18	22	100S	180E	4304735808	15592	Federal	Federal	GW	P
FEDERAL 21-6-10-19	6	100S	190E	4304735844	14356	Federal	Federal	GW	P
DESERT SPRING ST 41-36-9-18	36	090S	180E	4304735845	14639	State	State	GW	P
STATE 12-32-9-19	32	090S	190E	4304735995	14871	State	State	GW	P
FEDERAL 12-20-9-19	20	090S	190E	4304736093	14976	Federal	Federal	GW	P
FEDERAL 32-20-9-19	20	090S	190E	4304736094	16120	Federal	Federal	GW	P
FEDERAL 23-30-9-19	30	090S	190E	4304736095	14872	Federal	Federal	GW	P
SHEEP WASH FED 34-26-9-18	26	090S	180E	4304736113	15096	Federal	Federal	GW	P
DESERT SPRING ST 23-36-9-18	36	090S	180E	4304736219	14738	State	State	GW	P
DESERT SPRING ST 21-36-9-18	36	090S	180E	4304736220	14763	State	State	GW	P
DESERT SPRING ST 12-36-9-18	36	090S	180E	4304736233	14764	State	State	GW	P
DESERT SPRING ST 43-36-9-18	36	090S	180E	4304736241	14992	State	State	GW	P
DESERT SPRING ST 34-36-9-18	36	090S	180E	4304736242	14716	State	State	GW	P
FEDERAL 14-31-9-19	31	090S	190E	4304736271	15884	Federal	Federal	GW	P
FEDERAL 12-31-9-19	31	090S	190E	4304736336	15086	Federal	Federal	GW	P
FEDERAL 21-31-9-19	31	090S	190E	4304736368	15605	Federal	Federal	GW	P
FEDERAL 23-31-9-19	31	090S	190E	4304736442	15715	Federal	Federal	GW	P
SHEEP WASH FED 43-25-9-18	25	090S	180E	4304736600	14977	Federal	Federal	GW	P
FEDERAL 43-19-9-19	19	090S	190E	4304736719	15186	Federal	Federal	GW	P

From: Gasco Production Company
To: Badlands Production Company
Effective Date: 4/16/2015

SHEEP WASH FED 21-25-9-18	25	090S	180E	4304736727	15475	Federal	Federal	GW	P
FEDERAL 21-30-9-19	30	090S	190E	4304736739	15476	Federal	Federal	GW	P
SHEEP WASH FED 23-25-9-18	25	090S	180E	4304736740	15213	Federal	Federal	GW	P
FEDERAL 23-19-9-19	19	090S	190E	4304736771	15355	Federal	Federal	GW	P
SHEEP WASH FED 41-25-9-18	25	090S	180E	4304736772	15338	Federal	Federal	GW	P
FEDERAL 41-30-9-19	30	090S	190E	4304736817	15212	Federal	Federal	GW	P
LAMB TRUST 34-22-9-19	22	090S	190E	4304736913	15187	Fee	Fee	GW	P
LAMB TRUST 14-14-9-19	14	090S	190E	4304736916	17012	Fee	Fee	GW	P
DESERT SPRING ST 33-36-9-18	36	090S	180E	4304737115	15011	State	State	GW	P
FEDERAL 14-17-9-19	17	090S	190E	4304737116	16163	Federal	Federal	GW	P
FEDERAL 34-18-9-19	18	090S	190E	4304737117	16275	Federal	Federal	GW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	15087	State	State	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	15365	State	State	GW	P
FEDERAL 41-19-9-19	19	090S	190E	4304737611	16311	Federal	Federal	GW	P
FEDERAL 32-30-9-19	30	090S	190E	4304737612	16051	Federal	Federal	GW	P
FEDERAL 12-30-9-19	30	090S	190E	4304737613	16052	Federal	Federal	GW	P
FEDERAL 21-19-9-19	19	090S	190E	4304737621	16253	Federal	Federal	GW	P
FEDERAL 14-18-9-19	18	090S	190E	4304737622	16264	Federal	Federal	GW	P
FEDERAL 34-30-9-19	30	090S	190E	4304737630	16557	Federal	Federal	GW	P
DESERT SPRING FED 21-1-10-18	1	100S	180E	4304737631	15961	Federal	Federal	GW	P
FEDERAL 12-1-10-18	1	100S	180E	4304737646	16023	Federal	Federal	GW	P
SHEEP WASH FED 14-25-9-18	25	090S	180E	4304737647	16121	Federal	Federal	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	16254	State	State	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	15806	State	State	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	16868	State	State	GW	P
FEDERAL 14-19-9-19	19	090S	190E	4304738336	16467	Federal	Federal	GW	P
FEDERAL 34-19-9-19	19	090S	190E	4304738337	16119	Federal	Federal	GW	P
SHEEP WASH FED 41-26-9-18	26	090S	180E	4304738351	16884	Federal	Federal	GW	P
SHEEP WASH FED 32-25-9-18	25	090S	180E	4304738352	16349	Federal	Federal	GW	P
SHEEP WASH FED 34-25-9-18	25	090S	180E	4304738353	16210	Federal	Federal	GW	P
FEDERAL 12-19-9-19	19	090S	190E	4304738407	16236	Federal	Federal	GW	P
SHEEP WASH FED 23-26-9-18	26	090S	180E	4304738465	16558	Federal	Federal	GW	P
SHEEP WASH FED 12-25-9-18	25	090S	180E	4304738469	16449	Federal	Federal	GW	P
FEDERAL 23-18-9-19	18	090S	190E	4304738575	16312	Federal	Federal	GW	P
LAMB TRUST 34-22A-9-19	22	090S	190E	4304738673	15832	Fee	Fee	GW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	16792	Federal	Federal	GW	P
STATE 21-32B	32	090S	190E	4304739170	16309	State	State	GW	P
STATE 22-32A	32	090S	190E	4304739171	16308	State	State	GW	P
STATE 21-32A	32	090S	190E	4304739172	16310	State	State	GW	P
FEDERAL 11-19-9-19	19	090S	190E	4304739717	17054	Federal	Federal	GW	P
SHEEP WASH FED 31-25-9-18	25	090S	180E	4304739729	17241	Federal	Federal	GW	P
SHEEP WASH FED 11-25-9-18	25	090S	180E	4304739730	17266	Federal	Federal	GW	P
DESERT SPG FED 41-1-10-18	1	100S	180E	4304739773	17013	Federal	Federal	GW	P
FED 32-19X-9-19(RIGSKID)	19	090S	190E	4304740233	17014	Federal	Federal	GW	P
FEDERAL 23-30G-9-19	30	090S	190E	4304751280	18211	Federal	Federal	OW	P
FEDERAL 34-19G-9-19	19	090S	190E	4304751281	18210	Federal	Federal	OW	P
FEDERAL 442-30-9-19	30	090S	190E	4304752870	19647	Federal	Federal	GW	P
FEDERAL 333-30-9-19	30	090S	190E	4304752872	19648	Federal	Federal	GW	P
FEDERAL 423-30-9-19	30	090S	190E	4304753011	19649	Federal	Federal	GW	P
Desert Springs State 412-36-9-18	36	090S	180E	4304753324	19783	State	State	GW	P
Desert Springs State 424-36-9-18	36	090S	180E	4304753325	19783	State	State	GW	P
Desert Springs State 133-36-9-18	36	090S	180E	4304753326	19747	State	State	GW	P
Desert Spring State 142-36-9-18	36	090S	180E	4304753327	19747	State	State	GW	P
DESERT SPRINGS ST 422-36-9-18	36	090S	180E	4304753328	19783	State	State	GW	P
WILKIN RIDGE ST 31-32-10-17	32	100S	170E	4301332677	15144	State	State	GW	S
RBW 4-11D	11	100S	180E	4304730718	16269	Federal	Federal	OW	S

From: Gasco Production Company
 To: Badlands Production Company
 Effective Date: 4/16/2015

RBU 2-11D	11	100S	180E	4304730826	16270	Federal	Federal	OW	S
RBU 6-11D	11	100S	180E	4304731192	16271	Federal	Federal	OW	S
STATE 2-32B	32	090S	190E	4304732221	11371	State	State	GW	S
STATE 9-36A	36	090S	180E	4304732225	11364	State	State	GW	S
FEDERAL 13-30B	30	090S	190E	4304733581	13249	Federal	Federal	GW	S
STATE 13-36A	36	090S	180E	4304733598	17838	State	State	GW	S
FEDERAL 16-26A	26	090S	180E	4304733601	12928	Federal	Federal	GW	S
FEDERAL 31-29	29	090S	190E	4304733653	13077	Federal	Federal	GW	S
RBU 1-10D	10	100S	180E	4304734312	16265	Federal	Federal	OW	S
FEDERAL 13-18-9-19	18	090S	190E	4304739776	17149	Federal	Federal	GW	S

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-76482
2. NAME OF OPERATOR: Gasco Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 7979 E. Tufts Ave. CITY Denver STATE CO ZIP 80237		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0633 FNL 1512 FWL		8. WELL NAME and NUMBER: Desert Spring Fed 21-1-10-18
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 1 10S 18E S		9. API NUMBER: 4304737631
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Uteland Butte
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 4/16/2015	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Gasco Production Company requests a change of operator on this well, in addition to the wells on the attached list from Gasco Production Company to Badlands Production Company, effective date of 4/16/2015.

Gasco Production Company
7979 E Tufts Ave, Suite 1150
Denver CO 80237
303-996-1805

Michael Decker, Exec. Vice President & COO

Badlands Production Company
7979 E Tufts Ave, Suite 1150
Denver CO 80237
303-996-1805

Michael Decker, Exec. Vice President & COO

RECEIVED

JUN 02 2015

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Lindsey Cooke	TITLE Engineering Tech
SIGNATURE <i>Lindsey Cooke</i>	DATE 5/18/2015

(This space for State use only)

APPROVED

JAN 22 2016

DIV. OIL GAS & MINING
BY: *Rachel Medina*

Well Name	Section	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
FEDERAL 332-30-9-19	30	090S	190E	4304753012	19650	Federal	Federal	GW	DRL
WILKIN RIDGE FED 43-29-10-17	29	100S	170E	4301333098	15941	Federal	Federal	GW	OPS
LAMB TRUST 11-23-9-19	23	090S	190E	4304736915	16556	Fee	Fee	GW	OPS
SHEEP WASH FED 43-26-9-18	26	090S	180E	4304738573	17201	Federal	Federal	GW	OPS
FEDERAL 13-19-9-19	19	090S	190E	4304739777	18344	Federal	Federal	GW	OPS
FEDERAL 12-17-9-19	17	090S	190E	4304739800	17202	Federal	Federal	GW	OPS
GATE CYN 31-21-11-15	21	110S	150E	4301332391	13787	State	State	GW	P
WILKIN RIDGE ST 12-32-10-17	32	100S	170E	4301332447	14033	State	State	GW	P
GATE CYN 41-20-11-15	20	110S	150E	4301332475	14417	State	State	GW	P
WILKIN RIDGE FED 34-17-10-17	17	100S	170E	4301332560	14726	Federal	Federal	GW	P
GATE CYN 41-19-11-16	19	110S	160E	4301332611	14439	Federal	Federal	GW	P
WILKIN RIDGE ST 44-32-10-17	32	100S	170E	4301332619	15649	State	State	GW	P
WILKIN RIDGE FED 12-4-11-17	4	110S	170E	4301332674	15537	Federal	Federal	GW	P
WILKIN RIDGE ST 24-32-10-17	32	100S	170E	4301332676	15242	State	State	GW	P
WILKIN RIDGE FED 23-29-10-17	29	100S	170E	4301332679	14033	Federal	Federal	GW	P
GATE CYN ST 23-16-11-15	16	110S	150E	4301332685	16082	State	State	GW	P
WILKIN RIDGE ST 34-16-10-17	16	100S	170E	4301332730	15243	State	State	GW	P
WILKIN RIDGE FED 31-29-10-17	29	100S	170E	4301332773	15370	Federal	Federal	GW	P
WILKIN RIDGE 32-08	8	110S	170E	4301332778	14802	Federal	Federal	GW	P
GATE CYN ST 23-16-11-16	16	110S	160E	4301332888	15098	State	State	GW	P
WILKIN RIDGE FED 24-20-10-17	20	100S	170E	4301333081	15714	Federal	Federal	GW	P
WILKIN RIDGE FED 32-20-10-17	20	100S	170E	4301333087	15807	Federal	Federal	GW	P
WILKIN RIDGE FED 14-4-11-17	4	110S	170E	4301333099	15920	Federal	Federal	GW	P
RYE PATCH FED 22-21	22	110S	140E	4301333437	16919	Federal	Federal	GW	P
RYE PATCH FED 24-21	24	110S	140E	4301333443	16367	Federal	Federal	GW	P
RBUS 5-11D	11	100S	180E	4304730409	9005	Federal	Federal	OW	P
FEDERAL 7-25A	25	090S	180E	4304730624	9030	Federal	Federal	OW	P
RBUS 6-2D	2	100S	180E	4304731190	7075	State	State	OW	P
NGC 33-18J	18	090S	190E	4304731200	6155	Federal	Federal	OW	P
RBUS 13-2D	2	100S	180E	4304731280	16267	State	State	OW	P
RBUS 16-3D	3	100S	180E	4304731352	16268	Federal	Federal	OW	P
RBUS 10-11D	11	100S	180E	4304731357	7053	Federal	Federal	OW	P
RBUS 8-10D	10	100S	180E	4304731364	4955	Federal	Federal	OW	P
RBUS 15-3D	3	100S	180E	4304731539	9965	Federal	Federal	OW	P
RBUS 12-12D	12	100S	180E	4304731651	10688	Federal	Federal	OW	P
RBUS 2-10D	10	100S	180E	4304731801	10784	Federal	Federal	OW	P
RBUS 3-15D	15	100S	180E	4304733600	13213	Federal	Federal	OW	P
RBUS 3-12D	12	100S	180E	4304733739	14492	Federal	Federal	OW	P
STATE 7-36A	36	090S	180E	4304733741	14244	State	State	GW	P
FEDERAL 34-29	29	090S	190E	4304733750	13174	Federal	Federal	GW	P
FEDERAL 24-7 #1	7	100S	180E	4304733983	13182	Federal	Federal	GW	P
FEDERAL 23-29 #1	29	090S	190E	4304734111	13441	Federal	Federal	GW	P
FED 24-20-9-19	20	090S	190E	4304734168	14150	Federal	Federal	GW	P
FED 44-20-9-19	20	090S	190E	4304734169	14140	Federal	Federal	GW	P
FED 23-21-9-19	21	090S	190E	4304734199	13601	Federal	Federal	GW	P
FED 32-31-9-19	31	090S	190E	4304734201	13641	Federal	Federal	GW	P
FED 42-29-9-19	29	090S	190E	4304734202	13455	Federal	Federal	GW	P
PETES WASH 23-12 #1	12	100S	170E	4304734286	13492	Federal	Federal	GW	P
STATE 4-32B	32	090S	190E	4304734314	14440	State	State	GW	P
FED 14-18-2 #1	18	100S	180E	4304734539	13491	Federal	Federal	GW	P
FED 43-24-3 #1	24	100S	170E	4304734551	13726	Federal	Federal	GW	P
LYTHAM FED 22-22-9-19	22	090S	190E	4304734607	13640	Federal	Federal	GW	P
FED 11-21-9-19	21	090S	190E	4304734608	14151	Federal	Federal	GW	P
FED 22-30-10-18	30	100S	180E	4304734924	14280	Federal	Federal	GW	P
FEDERAL 43-30-9-19	30	090S	190E	4304735343	14202	Federal	Federal	GW	P
FED 11-22-9-19	22	090S	190E	4304735404	14203	Federal	Federal	GW	P
FED 42-21-9-19	21	090S	190E	4304735405	14928	Federal	Federal	GW	P
STATE 24-16-9-19	16	090S	190E	4304735588	14418	State	Federal	GW	P

FEDERAL 31-21-9-19	21	090S	190E	4304735606	14441	Federal	Federal	GW	P
FEDERAL 12-29-9-19	29	090S	190E	4304735614	14442	Federal	Federal	GW	P
FEDERAL 24-31-9-19	31	090S	190E	4304735623	14640	Federal	Federal	GW	P
FEDERAL 41-31-9-19	31	090S	190E	4304735624	14419	Federal	Federal	GW	P
LAMB TRUST 24-22-9-19	22	090S	190E	4304735732	14496	Fee	Fee	GW	P
LAMB TRUST 24-14-9-19	14	090S	190E	4304735733	14519	Fee	Fee	GW	P
FEDERAL 11-22-10-18	22	100S	180E	4304735808	15592	Federal	Federal	GW	P
FEDERAL 21-6-10-19	6	100S	190E	4304735844	14356	Federal	Federal	GW	P
DESERT SPRING ST 41-36-9-18	36	090S	180E	4304735845	14639	State	State	GW	P
STATE 12-32-9-19	32	090S	190E	4304735995	14871	State	State	GW	P
FEDERAL 12-20-9-19	20	090S	190E	4304736093	14976	Federal	Federal	GW	P
FEDERAL 32-20-9-19	20	090S	190E	4304736094	16120	Federal	Federal	GW	P
FEDERAL 23-30-9-19	30	090S	190E	4304736095	14872	Federal	Federal	GW	P
SHEEP WASH FED 34-26-9-18	26	090S	180E	4304736113	15096	Federal	Federal	GW	P
DESERT SPRING ST 23-36-9-18	36	090S	180E	4304736219	14738	State	State	GW	P
DESERT SPRING ST 21-36-9-18	36	090S	180E	4304736220	14763	State	State	GW	P
DESERT SPRING ST 12-36-9-18	36	090S	180E	4304736233	14764	State	State	GW	P
DESERT SPRING ST 43-36-9-18	36	090S	180E	4304736241	14992	State	State	GW	P
DESERT SPRING ST 34-36-9-18	36	090S	180E	4304736242	14716	State	State	GW	P
FEDERAL 14-31-9-19	31	090S	190E	4304736271	15884	Federal	Federal	GW	P
FEDERAL 12-31-9-19	31	090S	190E	4304736336	15086	Federal	Federal	GW	P
FEDERAL 21-31-9-19	31	090S	190E	4304736368	15605	Federal	Federal	GW	P
FEDERAL 23-31-9-19	31	090S	190E	4304736442	15715	Federal	Federal	GW	P
SHEEP WASH FED 43-25-9-18	25	090S	180E	4304736600	14977	Federal	Federal	GW	P
FEDERAL 43-19-9-19	19	090S	190E	4304736719	15186	Federal	Federal	GW	P
SHEEP WASH FED 21-25-9-18	25	090S	180E	4304736727	15475	Federal	Federal	GW	P
FEDERAL 21-30-9-19	30	090S	190E	4304736739	15476	Federal	Federal	GW	P
SHEEP WASH FED 23-25-9-18	25	090S	180E	4304736740	15213	Federal	Federal	GW	P
FEDERAL 23-19-9-19	19	090S	190E	4304736771	15355	Federal	Federal	GW	P
SHEEP WASH FED 41-25-9-18	25	090S	180E	4304736772	15338	Federal	Federal	GW	P
FEDERAL 41-30-9-19	30	090S	190E	4304736817	15212	Federal	Federal	GW	P
LAMB TRUST 34-22-9-19	22	090S	190E	4304736913	15187	Fee	Fee	GW	P
LAMB TRUST 14-14-9-19	14	090S	190E	4304736916	17012	Fee	Fee	GW	P
DESERT SPRING ST 33-36-9-18	36	090S	180E	4304737115	15011	State	State	GW	P
FEDERAL 14-17-9-19	17	090S	190E	4304737116	16163	Federal	Federal	GW	P
FEDERAL 34-18-9-19	18	090S	190E	4304737117	16275	Federal	Federal	GW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	15087	State	State	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	15365	State	State	GW	P
FEDERAL 41-19-9-19	19	090S	190E	4304737611	16311	Federal	Federal	GW	P
FEDERAL 32-30-9-19	30	090S	190E	4304737612	16051	Federal	Federal	GW	P
FEDERAL 12-30-9-19	30	090S	190E	4304737613	16052	Federal	Federal	GW	P
FEDERAL 21-19-9-19	19	090S	190E	4304737621	16253	Federal	Federal	GW	P
FEDERAL 14-18-9-19	18	090S	190E	4304737622	16264	Federal	Federal	GW	P
FEDERAL 34-30-9-19	30	090S	190E	4304737630	16557	Federal	Federal	GW	P
DESERT SPRING FED 21-1-10-18	1	100S	180E	4304737631	15961	Federal	Federal	GW	P
FEDERAL 12-1-10-18	1	100S	180E	4304737646	16023	Federal	Federal	GW	P
SHEEP WASH FED 14-25-9-18	25	090S	180E	4304737647	16121	Federal	Federal	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	16254	State	State	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	15806	State	State	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	16868	State	State	GW	P
FEDERAL 14-19-9-19	19	090S	190E	4304738336	16467	Federal	Federal	GW	P
FEDERAL 34-19-9-19	19	090S	190E	4304738337	16119	Federal	Federal	GW	P
SHEEP WASH FED 41-26-9-18	26	090S	180E	4304738351	16884	Federal	Federal	GW	P
SHEEP WASH FED 32-25-9-18	25	090S	180E	4304738352	16349	Federal	Federal	GW	P
SHEEP WASH FED 34-25-9-18	25	090S	180E	4304738353	16210	Federal	Federal	GW	P
FEDERAL 12-19-9-19	19	090S	190E	4304738407	16236	Federal	Federal	GW	P
SHEEP WASH FED 23-26-9-18	26	090S	180E	4304738465	16558	Federal	Federal	GW	P
SHEEP WASH FED 12-25-9-18	25	090S	180E	4304738469	16449	Federal	Federal	GW	P
FEDERAL 23-18-9-19	18	090S	190E	4304738575	16312	Federal	Federal	GW	P

LAMB TRUST 34-22A-9-19	22	090S	190E	4304738673	15832	Fee	Fee	GW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	16792	Federal	Federal	GW	P
STATE 21-32B	32	090S	190E	4304739170	16309	State	State	GW	P
STATE 22-32A	32	090S	190E	4304739171	16308	State	State	GW	P
STATE 21-32A	32	090S	190E	4304739172	16310	State	State	GW	P
FEDERAL 11-19-9-19	19	090S	190E	4304739717	17054	Federal	Federal	GW	P
SHEEP WASH FED 31-25-9-18	25	090S	180E	4304739729	17241	Federal	Federal	GW	P
SHEEP WASH FED 11-25-9-18	25	090S	180E	4304739730	17266	Federal	Federal	GW	P
DESERT SPG FED 41-1-10-18	1	100S	180E	4304739773	17013	Federal	Federal	GW	P
FED 32-19X-9-19(RIGSKID)	19	090S	190E	4304740233	17014	Federal	Federal	GW	P
FEDERAL 23-30G-9-19	30	090S	190E	4304751280	18211	Federal	Federal	OW	P
FEDERAL 34-19G-9-19	19	090S	190E	4304751281	18210	Federal	Federal	OW	P
FEDERAL 442-30-9-19	30	090S	190E	4304752870	19647	Federal	Federal	GW	P
FEDERAL 333-30-9-19	30	090S	190E	4304752872	19648	Federal	Federal	GW	P
FEDERAL 423-30-9-19	30	090S	190E	4304753011	19649	Federal	Federal	GW	P
Desert Springs State 412-36-9-18	36	090S	180E	4304753324	19783	State	State	GW	P
Desert Springs State 424-36-9-18	36	090S	180E	4304753325	19783	State	State	GW	P
Desert Springs State 133-36-9-18	36	090S	180E	4304753326	19747	State	State	GW	P
Desert Spring State 142-36-9-18	36	090S	180E	4304753327	19747	State	State	GW	P
DESERT SPRINGS ST 422-36-9-18	36	090S	180E	4304753328	19783	State	State	GW	P
WILKIN RIDGE ST 31-32-10-17	32	100S	170E	4301332677	15144	State	State	GW	S
SQUAW CROSSING U 5	2	100S	180E	4304730129	16266	State	State	OW	S
RBW 4-11D	11	100S	180E	4304730718	16269	Federal	Federal	OW	S
RBW 2-11D	11	100S	180E	4304730826	16270	Federal	Federal	OW	S
RBW 6-11D	11	100S	180E	4304731192	16271	Federal	Federal	OW	S
STATE 2-32B	32	090S	190E	4304732221	11371	State	State	GW	S
STATE 9-36A	36	090S	180E	4304732225	11364	State	State	GW	S
FEDERAL 13-30B	30	090S	190E	4304733581	13249	Federal	Federal	GW	S
STATE 13-36A	36	090S	180E	4304733598	17838	State	State	GW	S
FEDERAL 16-26A	26	090S	180E	4304733601	12928	Federal	Federal	GW	S
FEDERAL 31-29	29	090S	190E	4304733653	13077	Federal	Federal	GW	S
RBW 1-10D	10	100S	180E	4304734312	16265	Federal	Federal	OW	S
FEDERAL 13-18-9-19	18	090S	190E	4304739776	17149	Federal	Federal	GW	S